

## Finnish Railway Network Statement 2017





# Finnish Railway Network Statement

## 2017

Transport infrastructure data of the  
Finnish Transport Agency 3/2015

Finnish Transport Agency  
Helsinki 2015

*Photograph on the cover: Tehanu Tapola*

Online publication pdf ([www.liikennevirasto.fi](http://www.liikennevirasto.fi))

ISSN-L 1798-8276

ISSN 1798-8284

ISBN 978-952-317-165-7

Finnish Transport Agency  
P.O. Box 33  
FI-00521 Helsinki, Finland  
Tel. +358 (0)29 534 3000

## Foreword

The Finnish Transport Agency (FTA) publishes the Finnish Railway Network Statement (hereinafter the Network Statement) for the timetable period 2017. This is the fourteenth Network Statement prepared in Finland, in accordance with the Finnish Railway Act. The Network Statement describes the access conditions, the state-owned railway network, the rail capacity allocation process, the services supplied to Railway Undertakings and the principles of determining the infrastructure charge. The Network Statement is published for applicants for capacity for each timetable period separately. The present Network Statement is intended for the timetable period 11.12.2016-9.12.2017.

The Network Statement 2017 has been prepared based on the previous Network Statement taking into account the feedback received from users and the Network Statements of other European Infrastructure Managers.

The structure of the Network Statement follows the common European structure and comprises the following chapters:

- 1 General
- 2 Access conditions
- 3 Railway network
- 4 Capacity allocation
- 5 Services supplied to Railway Undertakings
- 6 Infrastructure charge

The amendment to the Railway Act entered into force on 8 December 2015, and the decrees to be issued under the Act are being prepared at the time of publication. The amendments resulting from the revised statutes will be made in the Network Statement at the beginning of 2016.

Within the Finnish Transport Agency, the Network Statement is the responsibility of the Traffic Services Department. Several specialists inside and outside the Finnish Transport Agency have been involved in the preparation of the Network Statement.

Helsinki, 11 December 2015

Finnish Transport Agency  
Traffic and Information, Traffic Services Department

## Table of Contents

1	GENERAL INFORMATION .....	7
1.1	Introduction.....	7
1.2	Objective .....	7
1.3	Legal Framework .....	7
1.4	Legal Status.....	8
1.4.1	General Remarks.....	8
1.4.2	Liability .....	8
1.4.3	Appeals Procedure.....	8
1.5	Structure of the Network Statement.....	9
1.6	Validity and Updating.....	9
1.6.1	Validity Period .....	9
1.6.2	Updating Process .....	9
1.7	Publishing .....	10
1.8	Contacts .....	10
1.9	Cooperation Between Infrastructure Managers .....	12
1.10	Glossary .....	13
2	ACCESS CONDITIONS .....	16
2.1	Introduction.....	16
2.2	General Access Requirements .....	16
2.2.1	General Requirements for Operating Railway Traffic .....	16
2.2.2	General Requirements for Access to the Railway Network.....	18
2.2.3	Operating Licence.....	18
2.2.4	Safety Certificate .....	18
2.2.5	Cover of Liabilities.....	20
2.3	General Business Conditions .....	20
2.3.1	Framework Agreement.....	20
2.3.2	Access Agreement .....	20
2.3.3	Other Railway Network Access Agreements.....	21
2.4	Operational Rules and Legislative Information.....	23
2.5	Exceptional Transport .....	23
2.6	Dangerous Goods.....	23
2.7	Rolling Stock Acceptance Process Guidelines.....	23
2.8	Staff Acceptance Process .....	25
3	INFRASTRUCTURE .....	27
3.1	Introduction.....	27
3.2	Extent of Network .....	27
3.2.1	Multi-Track Line Sections .....	27
3.2.2	Limits.....	27
3.2.3	Connected Railway Networks .....	28
3.3	Network Description .....	28
3.3.1	Geographic Identification .....	28
3.3.2	Capabilities .....	32
3.3.3	Traffic Control and Communications Systems .....	34
3.4	Traffic Restrictions.....	38
3.4.1	Specialised Infrastructure Capacity.....	38
3.4.2	Environmental Restrictions.....	38
3.4.3	Dangerous Goods .....	39

3.4.4	Tunnel Restrictions .....	41
3.4.5	Bridge Restrictions.....	41
3.4.6	Overweight Load Transport .....	41
3.5	Availability of the Infrastructure .....	41
3.6	Passenger Stations .....	41
3.7	Freight Terminals.....	41
3.8	Service Facilities .....	42
3.8.1	Train Formation Yards.....	42
3.8.2	Storage Sidings.....	42
3.8.3	Maintenance and Service Facilities.....	42
3.8.4	Refuelling Facilities.....	42
3.8.5	Technical Equipment .....	42
3.8.6	Security Control Centre.....	42
3.8.7	Technical Control Centre .....	43
3.9	Infrastructure Development.....	43
4	CAPACITY ALLOCATION .....	44
4.1	Introduction .....	45
4.2	Description of Process .....	45
4.2.1	Requesting Rail Capacity .....	46
4.2.2	Requesting Rail Capacity for Shunting Operations .....	46
4.2.3	Requesting Marshalling Yard Capacity .....	47
4.2.4	Developing the Process of Requesting Rail Capacity .....	47
4.3	Schedule for Train Path Requests and Allocation Capacity Requests.....	48
4.3.1	Schedule for Working Timetable .....	48
4.3.2	Requesting Rail Capacity for Temporary Traffic .....	49
4.4	Allocation Process .....	49
4.4.1	Coordination Process.....	49
4.4.2	Dispute Resolution .....	50
4.4.3	Congested Infrastructure Capacity .....	50
4.4.4	Allocating Marshalling Yard Capacity.....	51
4.4.5	Impact of the Framework Agreements .....	52
4.5	Allocation of Capacity for Maintenance, Renewal and Enhancements.....	52
4.6	Non-Usage Rules.....	53
4.7	Exceptional Transport and Dangerous Goods.....	54
4.8	Special Measures to be taken in the Event of Disturbance .....	54
4.8.1	Principles.....	54
4.8.2	Operational Regulation .....	55
4.8.3	Foreseen Problems.....	55
4.8.4	Unforeseen Problems.....	55
5	SERVICES .....	57
5.1	Introduction .....	57
5.2	Services Offered by the Finnish Transport Agency .....	57
5.2.1	Services in Return for the Infrastructure Charge .....	57
5.2.2	Chargeable Services .....	59
5.3	Services Offered by Others .....	60
5.3.1	Obligation to Provide Services.....	60
5.3.2	Power Supply on Electrified Railway Lines .....	61
5.3.3	Maintenance and Service Facilities.....	61
5.3.4	Refuelling Facilities.....	61
5.3.5	Technical Equipment .....	61

6	CHARGES.....	62
6.1	Charging Principles and Services Included in the Infrastructure Charge .....	62
6.2	Charging System .....	62
6.3	Tariffs.....	63
6.4	Performance Scheme.....	63
6.5	Changes to Charges.....	63
6.6	Billing Arrangements.....	64

## APPENDICES

Appendix 1	Basic Information on Line Sections
Appendix 2	Rail Traffic Operating Points
Appendix 3	Transport Operating Regulations for the Tornio–Haaparanta Line Section
Appendix 4	Loading Gauge
Appendix 5	Structure Gauge
Appendix 6	Superstructure Categories, EN Categories Derived from the Superstructure Categories and Permitted Speeds for Different Axle Loads
Appendix 7	Electrification
Appendix 8	Signalling Systems
Appendix 9	Vibration-Related Speed Restrictions
Appendix 10	Speed Limits due to Track Conditions
Appendix 11	Maximum Train Speeds in Tunnels
Appendix 12	Bridge-Related Restrictions
Appendix 13	Track Work
Appendix 14	Passenger Information at the Traffic Operating Points in the State-Owned Railway Network
Appendix 15	Description and Pricing of the Traffic Control Service for Shunting Operations
Appendix 16	Speed Depending on Rolling Stock
Appendix 17	Transport of Overweight Wagons
Appendix 18	Transport of Wagons Complying with the Russian Standard
Appendix 19	Monitoring of Rolling Stock
Appendix 20	Safety Issues



# 1 General information

## 1.1 Introduction

The Network Statement is published in accordance with the Railway Act ([304/2011](#))<sup>1</sup> and [Directive 2012/34/EU](#)<sup>2</sup> of the European Parliament and of the Council on the allocation of railway infrastructure capacity and the levying of charges for the use of railway infrastructure and safety certification (hereinafter referred to as the "Capacity and Infrastructure Charge Directive"). The Network Statement for the timetable period 2017 is the fourteenth Network Statement published in Finland.

## 1.2 Objective

The Network Statement is published for the use of applicants for capacity for each timetable period separately. The Network Statement describes the access conditions, the state-owned railway network, capacity allocation, services supplied to Railway Undertakings and the basis on which the infrastructure charge is determined. The Network Statement specifies in detail the general rules, deadlines, procedures and grounds applicable to capacity allocation and the charging systems.

Railway Undertakings can request capacity for international traffic within the European Economic Area, as well as for domestic freight traffic. Domestic passenger traffic may only be operated by VR Group Ltd in those rail lines which include in monopoly agreement between the Ministry of Transport and Communications and VR Group Ltd. Any railway undertaking can operate passenger traffic on the line sections which are not included in the agreement. VR Group Ltd has the exclusive right to operate railway transit traffic to and from Russia in the Finnish railway network, until the renewed agreement on transit traffic between Finland and Russia enters into force.

## 1.3 Legal Framework

### Current Legislation

In accordance with the Railway Act, the Finnish Transport Agency publishes information on the provisions of the Railway Act, as well as on the provisions issued under this Act and other provisions, concerning

1. the right of access to the railway network;
2. the principles of determining the infrastructure charge;
3. applying for rail capacity and the related deadlines;
4. the requirements for and approval of railway rolling stock; as well as
5. other conditions concerning operating and starting the operation of railway traffic.

---

<sup>1</sup> <http://www.finlex.fi/fi/rautatielaki>

<sup>2</sup> <http://eur-lex.europa.eu/directive/2012/34/EU>

The Finnish Transport Agency publishes information on the nature and extent of the railway network in the Network Statement for each timetable period. This information is contained in Chapter 3 of this Network Statement. The provisions issued by the Finnish Transport Agency on:

1. specialised infrastructure capacity under the Railway Act (point 3.4.1)
2. the priority order to be applied to congested infrastructure under the Railway Act (point 4.4.3)
3. the threshold quota for the minimum use of railway infrastructure on each train path under the Railway Act (point 4.6) is also published in the Network Statement.

## 1.4 Legal Status

### 1.4.1 General Remarks

The Network Statement is not a regulation issued by the Finnish Transport Agency but a document providing information.

### 1.4.2 Liability

Information published in the Network Statement does not affect regulations issued by the Finnish Transport Safety Agency or instructions issued by the Finnish Transport Agency. Information on the third parties mentioned in the Network Statement may also change during the timetable period.

### 1.4.3 Appeals Procedure

Under the Railway Act, an appeal against a decision by the Finnish Transport Agency is made by filing a claim for rectification with the Regulatory Body, which in Finland operates in connection with the Finnish Transport Safety Agency. A claim for rectification may be filed if the decision concerns:

- congested infrastructure capacity (23 §)
- priority order for allocating capacity in individual cases (24 §)
- capacity allocation (26 §)
- allocation of ad hoc capacity (27 §)
- cancelled capacity (29 §)
- infrastructure charge (37 §)

The claim for rectification shall be filed with the Regulatory Body within 30 days of the notice of the decision. The Regulatory Body shall decide on the claim for rectification within two months of the date on which the applicant has submitted the information required to make a decision. The decision shall, however, be taken within ten days of the date on which all relevant information has been delivered if the claim concerns the priority order in individual cases, capacity allocation or a request for ad hoc capacity.

## 1.5 Structure of the Network Statement

This Network Statement follows the common structure set for Network Statements by RailNetEurope.

The Network Statement consists of five more chapters in addition to this one. The second chapter deals with the requirements for accessing the railway network, the third handles the railway network infrastructure, the fourth covers issues related to capacity allocation, the fifth chapter is about services offered to Railway Undertakings, and the sixth chapter deals with the infrastructure charge and charging principles. The Network Statement includes appendices that provide a more detailed description of the railway network features and other issues related to railway traffic operations.

## 1.6 Validity and Updating

### 1.6.1 Validity Period

The Network Statement is valid for one timetable period. It is published four months ahead of the expiry of the deadline for submission of capacity requests that is 12 months ahead of the timetable period. This Network Statement is intended for the timetable period 2017, that is, for the period 11.12.2016–9.12.2017. The Network Statement for the timetable period 2018 will be published by 9.12.2016 at the latest.

### 1.6.2 Updating Process

If information contained in section 1.3 changes, the Finnish Transport Agency will publish the changes on its website <http://www.liikennevirasto.fi><sup>3</sup>.

The Appendix 13 of the Network Statement presents an estimate of the track work that is to be done during the timetable period 2017 and which may affect traffic. The working programme, timing of tasks and the required track work will change as the funding and plans become more focused. The Finnish Transport Agency will publish the list of track work and maintain an updated version of the document on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>4</sup>.

The text and appendices of the Network Statement may be updated once it has been published. The updates will be made available on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>5</sup>.

---

<sup>3</sup> <http://www.liikennevirasto.fi/network-statement>

<sup>4</sup> <http://www.liikennevirasto.fi/ammattiliikenne-raiteilla/liikennesuunnittelu/ratatyot>

<sup>5</sup> <http://www.liikennevirasto.fi/network-statement>

## 1.7 Publishing

The Network Statement is published in three languages: Finnish, Swedish and English. If any discrepancies are found between the different language versions, the Finnish language version will prevail. All language versions are available in PDF format on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>6</sup>.

Development plans for the railway network for 2015–2018 are presented in the Finnish Transport Agency's action plan (TTS)<sup>7</sup>. Statistics concerning the railway network and railway traffic are presented in the annually published [Finnish Railway Statistics](#)<sup>8</sup>.

## 1.8 Contacts

### Finnish Transport Agency

The Finnish Transport Agency operates under the auspices of the Ministry of Transport and Communications, assuming responsibility for maintaining and developing the state-owned railway network, allocating rail capacity, conducting traffic control and directing traffic. The Finnish Transport Agency is also responsible for maintaining roads and developing and safeguarding the operating prerequisites of merchant shipping and other forms of waterborne traffic.




Figure 1. The Finnish Transport Agency's organisational chart.

P.O. Box 33 (street address: Opastinsilta 12 A)  
FI-00521 HELSINKI  
FINLAND  
E-mail: [kirjaamo@liikennevirasto.fi](mailto:kirjaamo@liikennevirasto.fi)  
Internet: <http://www.liikennevirasto.fi><sup>9</sup>

<sup>6</sup> [http://portal.liikennevirasto.fi/sivu/www/e/professionals/network\\_statement](http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement)

<sup>7</sup> [http://www2.liikennevirasto.fi/liikenneviraston\\_tts\\_2015-2018](http://www2.liikennevirasto.fi/liikenneviraston_tts_2015-2018)

<sup>8</sup> <http://www.liikennevirasto.fi/railway-statistics>

On matters regarding entering the market or railway traffic, e-mail can be sent to [oss\(at\)liikennevirasto.fi](mailto:oss(at)liikennevirasto.fi).

Other contact information can be found on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>9</sup>.

### **Ministry of Transport and Communications**

The Ministry of Transport and Communications is responsible for two broad sectors: transport policy and communications policy.

In the transport sector, the Ministry's responsibilities include transport systems and networks, transport of people and goods, traffic safety, and issues relating to climate and the environment. In the communications sector, the Ministry takes care of issues relating to communications networks, information security and data protection, information society policy, the mass media, and postal services.

PO Box 31 (street address: Eteläesplanadi 16-18)  
FI-00023 VALTIONEUVOSTO  
FINLAND  
E-mail: [kirjaamo\(at\)lvm.fi](mailto:kirjaamo(at)lvm.fi)  
Internet: <http://www.lvm.fi><sup>11</sup>

### **Finnish Transport Safety Agency**

The Finnish Transport Safety Agency operates under the auspices of the Ministry of Transport and Communications. The Finnish Transport Safety Agency develops the safety of the transport system, promotes environmentally friendly transport solutions and is responsible for transport system regulatory duties.

P.O. Box 320 (Street Address: Kumpulantie 9)  
FI-00101 HELSINKI  
FINLAND  
E-mail: [kirjaamo\(at\)trafi.fi](mailto:kirjaamo(at)trafi.fi)  
Internet: <http://www.trafi.fi><sup>12</sup>

### **Rail Regulatory Body**

The rail regulatory body monitors the competitive situation of the rail market. The rail regulatory body ensures the fair and non-discriminatory treatment of all operators in the railway sector.

P.O. Box 320 (Street Address: Kumpulantie 9)  
FI-00101 HELSINKI  
FINLAND  
E-mail: [kirjaamo\(at\)trafi.fi](mailto:kirjaamo(at)trafi.fi) and [railregulator\(at\)trafi.fi](mailto:railregulator(at)trafi.fi)

---

<sup>9</sup> <http://www.liikennevirasto.fi>

<sup>10</sup> <http://www.liikennevirasto.fi/contact-information>

<sup>11</sup> <http://www.lvm.fi/web/en/home>

<sup>12</sup> <http://www.trafi.fi/en>

---

Internet: <http://www.saantelyelin.fi><sup>13</sup>

### **Finnish Competition and Consumer Authority**

The responsibilities of the Finnish Competition and Consumer Authority relate to implementing competition and consumer policy, ensuring good market performance, implementing competition legislation and EU competition rules, and securing the financial and legal position of the consumer. The agency also handles the supervision responsibilities of the Consumer Ombudsman.

P.O. Box 5 (Street address: Siltasaarencatu 12 A)  
FI-00531 HELSINKI  
FINLAND  
E-mail: kirjaamo(at)kkv.fi  
Internet: <http://www.kkv.fi><sup>14</sup>

## **1.9 Cooperation between Infrastructure Managers**

RailNetEurope (**RNE**)<sup>15</sup> is a non-profit making association of Infrastructure Managers and Allocation Bodies (IMs/ABs). It is dedicated to facilitating International Traffic on the European Rail Infrastructure.

RNE has established one OSS (One Stop Shop) contact point in every member country. Each customer can choose its favorite OSS contact point for all its needs regarding international rail services. From the initial questions related to network access to international path requests and performance review after a train run – all these issues and more are handled by one contact point for the whole international train journey at the customers' convenience.

A list of OSS contact persons is available at RailNetEurope's Internet pages at <http://www.rne.eu><sup>16</sup>.

The Finnish Transport Agency is no longer a member of RNE, but it is still active in the OSS. For more information, please send an e-mail to oss(at)fta.fi

---

<sup>13</sup> <https://www.saantelyelin.fi>

<sup>14</sup> <http://www.kkv.fi>

<sup>15</sup> <http://www.rne.eu/>

<sup>16</sup> [http://www.rne.eu/oss\\_network.html](http://www.rne.eu/oss_network.html)

## Network Statements of other countries

Internet addresses of Network Statements published by other railway network administrators are available at RailNetEurope's website at

[http://www.rne.eu/members\\_ns.html](http://www.rne.eu/members_ns.html)<sup>17</sup>.

## 1.10 Glossary

**ATP** is a class B system "ATP-VR/RHK - Junankulunvalvonta (JKV)" according to appendix B to the technical specification for interoperability relating to the control-command and signalling subsystem of the trans-European conventional rail system of 28 March 2006.

**Ad hoc capacity** refers to rail capacity requested for temporary, short-term and individual train paths. Example: trains operating on individual days; machinery and trains with deviating routes or stopping behaviour.

**Advance information on train traffic (JETI)** is a system, which includes the advance plans of track work and information on changes affecting traffic. Otherwise, these would have to be delivered by a traffic control message.

**Capacity for operating regular train services** refers to rail capacity requested for regular, long-term and identical train services. Example: services required year round from Monday to Saturday or on every Tuesday and Thursday for three months.

**Coordination** refers to a procedure by which the Finnish Transport Agency and the applicants attempt to solve situations where there are competing requests for rail capacity.

**Engaging in railway traffic** refers to the traffic conducted by a Railway Undertaking, traffic related to railway maintenance, traffic conducted by a museum train operator, a company or other association under private law whose main activity is some other than operating railway traffic, or the railway Infrastructure Manager on the railway network.

**Infrastructure management** refers to construction, maintenance and development of tracks, structures, equipment and systems connected with them, as well as the immovable property needed for infrastructure management.

**KUPLA** is a data terminal equipment for train drivers, which enables electronic data transfers between the railway traffic management systems, and between the traffic control and train drivers.

**LIIKE** is a data system for requesting rail capacity.

---

<sup>17</sup> [http://www.rne.eu/members\\_ns.html](http://www.rne.eu/members_ns.html)

**Museum track** refers to a track designated as a museum track by the Infrastructure Manager of the Finnish railway network. Before designating a museum track, the Infrastructure Manager shall hear the Finnish Transport Safety Agency and the railway operators using the track in question. Only museum traffic may be operated on a museum track; no other passenger or freight traffic.

**Museum train traffic** refers to traffic operated on a small scale on the railway network by a non-profit association with museum trains. Museum train refers to a stock registered as a museum train on the Finnish Transport Safety Agency's stock register.

**POHA** (System for handling traffic anomalies) specifies how the reporting of disruptions and the handling of anomalies shall be implemented between the parties. When the POHA System is taken into use, the railway operators are expected to insert their disruption information, i.e. disruptions caused by railway operators, into the system.

**Private siding** refers to a track other than track owned by the Finnish Transport Agency.

**Rail capacity** refers to the potential to use the railway network and to schedule a train path as laid down in the Railway Act. Rail capacity may also, based on several parameters in the railway network, be defined as the maximum number of trains which can be scheduled on a section of infrastructure for a given period.

**Railway operator** refers to Railway Undertakings, railway maintenance companies, Infrastructure Managers operating in the railway network, and museum train operators. Other companies or associations operating in the railway network, and whose operations in the railway network are not part of their core activities, are also referred to as railway operators.

**Railway Infrastructure Manager** refers to the Finnish Transport Agency or a railway Infrastructure Manager of a private siding, on which the Railway Act ([304/2011](#))<sup>18</sup> is applied.

**Railway Undertaking** refers to a company or other association, either public or under private law, whose main activity is to operate rail passenger or freight traffic. The company must have an appropriate operating licence issued in the European Economic Area and it is obliged to provide traction services. Undertakings providing only traction services are also regarded as Railway Undertakings.

**Ratapurkki** is a data warehouse for railway data, which provides information about railway infrastructure for companies and data systems in the railway sector. The user interface is a browser, through which data can be searched via a map or through database reporting.

---

<sup>18</sup> <http://www.finlex.fi/fi/laki/alkup/2011/20110304>



**RATO** refers to railway track's technical instructions, which include basic information on development, inspection and maintenance of a track and its equipment. RATO is based on the provisions issued by the Finnish Transport Safety Agency. **RATO**<sup>19</sup> is published by the Finnish Transport Agency.

**Brackets ( )** indicate that the subject is not included in the list.

**Traffic control** is the management of traffic on individual train paths. In addition traffic control duties include issuing permits and notices required for train traffic. Traffic control also includes protecting the track work areas, issuing permits for track work and receiving information on the termination of such work. If so required due to the volume and nature of traffic, or type of safety apparatus, a signal or turnout worker, shunting foreman, locomotive driver or a worker responsible for the safety of work done near the tracks or other person appointed in due order for the task may participate in traffic control to the extent required by their task.

**TURI** is a data system for safety-related anomalies and risk management. Traffic operators are expected to use this system for submitting their required safety reports to the Finnish Transport Agency.

**TURO** refers to safety instructions in track maintenance. The Finnish Transport Agency publishes the instructions on its website <http://www.liikennevirasto.fi><sup>20</sup>.

**VIRVE** is the radio network used for internal communication between the authorities. The VIRVE network is the world's first nationwide radio network based on TETRA technology, and it was taken into use throughout the country in 2002.

Other, more detailed, definitions can be found in RATO (**Railway track technical instructions**)<sup>21</sup>.

---

<sup>19</sup> [http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat\\_suunnittelijat/vaylanpidon\\_ohjeet/rakennuttaminen/rautatiet](http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet/rakennuttaminen/rautatiet)

<sup>20</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/lo\\_2012-01\\_turo\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf)

<sup>21</sup> [http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat\\_suunnittelijat/vaylanpidon\\_ohjeet/rakennuttaminen/rautatiet](http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet/rakennuttaminen/rautatiet)

## 2 Access Conditions

### 2.1 Introduction

Access requirements to the railway network are listed in this chapter. The prerequisites for operating railway traffic are an operating licence, safety certificate, allocated capacity and an access agreement. In addition, for example, the rolling stock acceptance process and traffic safety staff qualifications are described in this chapter.

### 2.2 General Access Requirements

The legal framework of access to infrastructure is described in the Railway Act (304/2011)<sup>22</sup>. The provisions and instructions issued by the Finnish Transport Safety Agency and the Finnish Transport Agency shall be observed on the state-owned railway network. Information on the instructions issued by the Finnish Transport Safety Agency currently in force is available from the Finlex website, <http://www.finlex.fi><sup>23</sup> and on The Finnish Transport Safety Agency's website <http://www.trafi.fi><sup>24</sup>. Provisions issued by the Finnish Transport Agency are available on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>25</sup>.

The Act on safety and interoperability of the rail system (372/2011)<sup>26</sup> lays down, for example, the essential requirements for the rail system.

Locomotives operating in the state-owned railway network must be fitted with an automatic train protection system (ATP). Further information can be read from a chapter 3.3.3.6 ATP Systems.

#### 2.2.1 General Requirements for Operating Railway Traffic

Operation of railway traffic on the state-owned railway network requires that the Railway undertaking meet the following conditions:

1. The Railway Undertaking or international grouping of Railway Undertakings shall have an operating licence in accordance with the Railway Act or a corresponding operating licence issued in the European Economic Area.
2. The Railway Undertaking shall have a safety certificate in accordance with the Railway Act, issued or approved by the Finnish Transport Safety Agency, which covers all the train paths on which traffic will be operated.

---

<sup>22</sup> <http://www.finlex.fi/fi/laki/alkup/2011/20110304>

<sup>23</sup> <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

<sup>24</sup> [http://www.trafi.fi/rautatiet/saadokset/kansalliset\\_maaraykset](http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset)

<sup>25</sup> [http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat\\_suunnittelijat/vaylanpidon\\_ohjeet](http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet)

<sup>26</sup> <http://www.finlex.fi/fi/laki/alkup/2011/20110372>

3. Capacity in accordance with the Railway Act has been allocated to the Railway Undertaking for its traffic.
4. The Railway Undertaking shall make an access agreement with Finnish Transport Agency on necessary practical arrangements concerning the operating of railway traffic.
5. Other conditions for operating rail traffic, laid down in or under the Railway Act are in all respects fulfilled.

Access conditions and phases for entering the freight transport market are presented in Figure 2.




Figure 2. Phases for entering the freight transport market.

### Museum train traffic

The same requirements described in this Network Statement are applied to museum train traffic as to other rail traffic, except with regard to the operating licence and to the access agreement. The law provides that a museum train traffic operator must have a safety certificate granted by the Finnish Transport Safety Agency. The safety certificate will be granted upon application for a maximum of five years at a time. The prerequisites in order to be granted a safety certificate are presented in chapter 2.2.4. The Finnish Transport Agency expects access agreement to be agreed upon for each timetable period.

Capacity may be requested only as ad hoc capacity.

The Museum Train Traffic Regulation (RVI/295/411/2008) has been repealed and replaced by the Finnish Transport Safety Agency's regulation on operation and traffic management [Käyttötoiminta ja liikenteen hallinta \(TRAFI/22100/03.04.02.00/2012\)](#)<sup>27</sup>. The new regulation does not cover all aspects of museum traffic, so museum traffic operators should among other things check the

<sup>27</sup> [https://www.finlex.fi/TRAFI\\_2438\\_03.04.02.00\\_2015](https://www.finlex.fi/TRAFI_2438_03.04.02.00_2015)

Finnish Transport Safety Agency's instructions on ATP Systems. Further information in section 3.3.3.6.

### **2.2.2 General Requirements for Access to the Railway Network**

The following Railway Undertakings or international groupings of Railway Undertakings may access the state-owned railway network to operate train traffic.

1. the Railway Undertakings and international groupings of Railway Undertakings referred to in the Railway Act providing domestic freight services or passenger services in international railway traffic between states belonging to the European Economic Area
2. VR Group Ltd has the exclusive right to operate domestic passenger traffic in the Finnish railway network on the line sections referred to in the agreement on exclusive rights between VR Group Ltd and the Ministry of Transport and Communications. Any Railway Undertaking can operate passenger traffic on the line sections which are not included in the agreement. VR Group Ltd has the exclusive right to operate railway transit traffic to and from Russia in the Finnish railway network, until the renewed agreement on transit traffic between Finland and Russia enters into force.

These Railway Undertakings and international groupings of Railway Undertakings may use the railway network in accordance with the Railway Act and the traffic operating points on the state-owned railway network for their traffic operating on separately agreed conditions (access agreement). Other railway operators may also use the state-owned railway network, provided that the Finnish Transport Agency has given its consent.

### **2.2.3 Operating Licence**

The Ministry of Transport and Communications issues an operating licence for the operation of railway traffic to applicants established in Finland. The granted operating licence is valid for the time being and the Ministry reviews the operating licence and its conditions every five years. An operating licence issued in one state belonging to the European Economic Area is valid throughout the territory of the European Economic Area. An operating licence granted elsewhere must be delivered to the Ministry of Transport and Communications for information.

The prerequisite for granting the operating licence is that the main activity of the undertaking is to operate railway traffic. The undertaking must also have a solid financial standing, a competent management team and sufficient liability insurance. The application for an operating licence is delivered to the Ministry of Transport and Communications.

### **2.2.4 Safety Certificate**

The safety certificate is issued by the national safety authority. In Finland, it is issued by the Finnish Transport Safety Agency.

If a Railway Undertaking has been granted part A of the safety certificate in another country belonging to the European Economic Area, it must apply to the Finnish Transport Safety Agency for part B of the safety certificate before it can commence train operations or infrastructure management in Finland.

The safety certificate will be granted or approved for a maximum of five years at a time. The Railway Undertaking must apply for a new safety certificate as soon as its old certificate is no longer valid.

The safety certificate comprises two parts. Part A approves the safety management system, while part B accepts the documents and arrangements that the holder of the safety certificate has issued and put in place that indicates that the set requirements are fulfilled. The purpose of the safety certificate is to ensure that the applicant fulfills the safety requirements for its operations and that the undertaking has the necessary qualifications to operate safely on the railway network. These requirements are presented in the Railway Act. It is also possible to include other requirements in the safety certificate regarding railway safety. The purpose of these requirements is to ensure railway safety while taking into consideration the nature and scope of the railway traffic of the applicant. The aforementioned requirements are presented in more detail and explained in the instructions on how to apply for a safety certificate drawn up by the Finnish Transport Safety Agency.

The Finnish Transport Safety Agency requires that:

- the applicant's safety management system complies with regulations
- the applicant proves that it fulfils *those* rules and regulations on the use of the railway network that concern that part of the network where it intends to operate or engage in traffic operation and the applicant shows that it can safeguard compliance with the rules and regulations,
- the applicant proves that its staff groups and the staff groups of the subcontractor that it uses are appropriately trained and competent in their duties in accordance with the relevant regulations [concerning the network];
- the applicant proves that the rolling stock that it uses complies with the relevant regulations [concerning the network] and that the maintenance and servicing of the rolling stock are in order.

The Finnish Transport Safety Agency has drawn up instructions on how to apply for a safety certificate. The form used to apply for the safety certificate can be obtained from the Finnish Transport Safety Agency. The written application shall be submitted to the Finnish Transport Safety Agency. The Finnish Transport Safety Agency shall consider the application and if necessary request further information. The Finnish Transport Safety Agency shall decide on the issuance or approval of the safety certificate within four months after the request has been filed. The Finnish Transport Safety Agency may grant a safety certificate for the entire state-owned railway network or individual train paths. If the rules or regulations on the safety of the rail system are essentially amended, the Finnish Transport Safety agency may review the certificate or part thereof. If the operation of the holder of the safety certificate alters essentially in nature or extent, it shall re-apply for approval of the safety certificate insofar as the change has an effect on the terms and conditions of the safety certificate.

### 2.2.5 Cover of Liabilities

The rail transport operator and infrastructure management company shall have sufficient liability insurance or other corresponding arrangement in case of such damage incurred by a party due to rail transport operations for which the rail transport operator or infrastructure management company is by law or agreement responsible. The nature and scope of operations and risks related to the operations must be taken into account in evaluating the sufficiency of the insurance or a similar arrangement. The insurance or other corresponding arrangement shall be in force for the duration of the entire period during which rail transport is operated. More information can be found from the Finnish Transport Safety Agency's [guideline](#)<sup>28</sup> regarding the insurance.

## 2.3 General Business Conditions

### 2.3.1 Framework Agreement

The Finnish Transport Agency may make a framework agreement on the use of capacity with applicants for capacity. The purpose of such an agreement is to specify the characteristics of the capacity requested by the applicant. The framework agreement does not, however, entitle the applicant to obtain such capacity as is specified in the agreement.

Railway Undertakings shall request the capacity specified in the framework agreement for each timetable period separately. If requested, the Finnish Transport Agency allocates the capacity specified in the framework agreement following the procedure laid down in the Railway Act. Correspondingly, the access agreement shall be concluded for each timetable period separately regardless of the framework agreement. The framework agreement does not, however, impede the application of the provisions of the Railway Act to other applicants for capacity.

The framework agreement is made for a maximum of five years. For special reasons, the Finnish Transport Agency may, however, also conclude framework agreements for a longer period. Conclusion of an agreement for more than five years can, however, be justified only by agreements, special investments or special business risks connected with the transport business of the party with which the agreement is concluded, as well as by the large-scale and long-term investments of the party with which the agreement is concluded or the contractual obligations connected with such activities.

At present, the Finnish Transport Agency does not enter into framework agreements.

### 2.3.2 Access Agreement

Railway Undertakings and museum train traffic operators shall make an access agreement with the Finnish Transport Agency on the access to necessary services with regard to the state-owned railway network and railway traffic operations. These services include, for example, access to marshalling yards, storage sidings and other tracks, as well as access to traffic control services. It is also possible to agree on other practical arrangements concerning railway traffic operations.

<sup>28</sup> [http://www.trafi.fi/filebank/a/1327667636/d582c3ee14540cf9601cad2e3d3e6401/9079-OHJE\\_RAUTATIELIIKENTEEN\\_HARJOITTAJAN\\_vastuuvakuutuksesta.pdf](http://www.trafi.fi/filebank/a/1327667636/d582c3ee14540cf9601cad2e3d3e6401/9079-OHJE_RAUTATIELIIKENTEEN_HARJOITTAJAN_vastuuvakuutuksesta.pdf)

The railway traffic operator shall contact the Finnish Transport Agency to prepare the access agreement and contractual negotiations as early as possible, preferably before applying for capacity. The Finnish Transport Agency enters into this agreement with each licence holder while taking into account the nature and scale of capacity allocated. The access agreement is made for each timetable period and can be changed if decisions made during the timetable period concerning the allocation of capacity or other facts, for example, concerning the condition of the railway network so require. The access agreement can only be concluded after all conditions stipulated in the Railway Act for operating railway traffic have been fulfilled. After the agreement has been concluded, traffic may begin.

### **2.3.3 Other Railway Network Access Agreements**

#### **Agreement between Infrastructure Managers**

The agreement comprises e.g. the operation between railway networks, traffic control, the dividing line between railway networks, its ownership and maintenance, as well as the cooperation between Infrastructure Managers. In order to enter into an agreement, the Infrastructure Manager shall submit a request in free form to the Finnish Transport Agency at the address kirjaamo(at)fta.fi.

#### **Agreement on access to individual traffic operating points**

Railway operators, whose operations in the railway network are not part of their core activities, have only access to the state-owned railway network or individual traffic operating points in the network, if they have concluded an access agreement with the Finnish Transport Agency before commencing operation. The agreement is renewed every timetable period. In order to enter into an agreement, the railway operator shall send an application in free form to the Finnish Transport Agency at the address: kirjaamo(at)fta.fi.

#### **Marshalling yard agreement**

At traffic operating points where there are many railway operators, the parties negotiate a marshalling yard agreement, if necessary. The agreement relates to the common rules, the access to and operation of tracks on the marshalling yard in question, or on parts of it. The marshalling yard agreement is an appendix to the railway network access agreement. The marshalling yard agreement is renewed every timetable period. The Finnish Transport Agency summons the parties to negotiate the marshalling yard agreement.

#### **Agreement on the operation of track cars**

Track cars must not be operated on line sections with commercial traffic in the state-owned railway network. However, an agreement can be concluded on operation of track cars on certain line sections which are closed to traffic, provided that the track conditions are satisfactory and the safety requirements met. The entry of such an agreement is always decided on a case-by-case basis and the Finnish Transport Agency may reject an agreement. Requests concerning this matter shall be addressed to kirjaamo(at)fta.fi.

**Maintenance contractors' network access agreement**

Maintenance contractors, who have a valid maintenance agreement with the Infrastructure Manager (or the subcontractor of the maintenance provider of the Infrastructure Manager), do not need a separate network access agreement, since access to the railway network is already included in the maintenance agreement. Contractors who do not have an agreement with the Infrastructure Manager or a link through a subcontractor shall contact the Infrastructure Manager for an assessment of the need for a network access agreement. More information can be obtained from the Finnish Transport Agency's Railway Network Usage Unit.

**Agreement on track access to the state-owned railway network for rolling stock storage**

Railway Undertakings shall, in connection with their annual requests for rail capacity for regular services, report their requirements concerning the marshalling yards (operating time, operational requirements e.g. marshalling and storage and, if possible, track reservations). The need for access to tracks in the marshalling yards and the right to track access are negotiated and included in the network access agreement.

If museum train operators need to store rolling stock in the state-owned railway network, they must enter into an agreement about this with the Infrastructure Manager. The entry of such an agreement is always decided on a case-by-case basis and the Infrastructure Manager may reject the agreement on reasonable grounds. Applications to draw up an agreement shall be addressed to kirjaamo(at)fta.fi

**VIRVE agreement**

In the state-owned railway network, the RAILI and VIRVE networks are used for verbal communication between traffic control and train drivers. 2017 will be a transitional year, during which the VIRVE network will replace the RAILI network. The railway operators must enter into an agreement on RAILI and VIRVE with the Finnish Transport Agency. In order to enter into an agreement, the company shall fill in the form on the Finnish Transport Agency's website and send it to the Finnish Transport Agency.



## 2.4 Operational Rules and Legislative Information

Operational rules drafted by the Finnish Transport Agency can be viewed on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>29</sup> and regulations drafted by the Finnish Transport Safety Agency on its website <http://www.trafi.fi><sup>30</sup>. Legislative information can be viewed on the Finlex website <http://www.finlex.fi><sup>31</sup>.

## 2.5 Exceptional Transport

Traffic restrictions are dealt with in section 3.4 and in Appendix 17. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex website <http://www.finlex.fi><sup>32</sup> and other instructions on the Finnish Transport Safety Agency's website <http://www.trafi.fi><sup>33</sup>. Other provisions can be viewed on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>34</sup>.

For the time being VR Transpoint issues permits for exceptional transports. The procedures for exceptional transports will be developed in 2016. Further information about special permits in appendices 4, 12 and 17.

## 2.6 Dangerous Goods

Transport of dangerous goods is dealt with in section 3.4.3 and in appendix 17. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex website <http://www.finlex.fi><sup>35</sup> and other instructions on the Finnish Transport Safety Agency's website <http://www.trafi.fi><sup>36</sup>.

## 2.7 Rolling Stock Acceptance Process Guidelines

An authorisation issued by the Finnish Transport Safety Agency is required for placing rolling stock in service. This authorisation can be issued for rolling stock that meets the requirements valid in Finland, which is laid down in legislation.

The requirements are based on the interoperability requirements for the rail system in accordance with Community law and the Finnish Transport Safety Agency has issued

---

<sup>29</sup> <http://www.liikennevirasto.fi/julkaisut/ohjeet>

<sup>30</sup> <http://www.trafi.fi/rautatiet/saadokset>

<sup>31</sup> <http://www.finlex.fi/fi/viranomaiset>

<sup>32</sup> <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

<sup>33</sup> <http://www.trafi.fi/rautatiet/saadokset>

<sup>34</sup> [http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat\\_suunnittelijat/vaylanpidon\\_ohjeet](http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet)

<sup>35</sup> <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

<sup>36</sup> <http://www.trafi.fi/rautatiet>

complementary and more detailed instructions. Conformity can be proved by the EC Declaration of Conformity or a corresponding declaration issued within the European Economic Area. Before issuing the authorisation, the Finnish Transport Safety Agency will ask for the Finnish Transport Agency's statement on stock type's or unit's suitability for railway network, in order to define possible restrictions.

The Finnish Transport Safety Agency maintains a register monitoring the validity and traffic safety of rolling stock. The purpose is to promote rail system safety and identify rolling stock. The rolling stock is recorded in a register maintained by the Finnish Transport Safety Agency, if the rolling stock has been granted a commissioning licence in Finland. Rolling stock that will be used on the state's railway network and has been granted a commissioning licence elsewhere within the European Economic Area or in a country outside the EEA must also be recorded in the register. Any rolling stock used on private sidings will also be recorded in the register.

The Finnish Transport Safety Agency can also register rolling stock for a limited time upon request. A fixed-period registration is also possible for any rolling stock that has been granted a commissioning licence in another country, if it has been granted a commissioning licence in Finland and is used on the state's railway network only temporarily.

The rolling stock register must include information on the owner, holder and renter of the rolling stock. The more detailed regulations on related information on other rolling stock to be recorded in the register will be set forth in a Council of State decree.

With regards to any rolling stock used for railway traffic between Finland and Russia, the register must include information on the vehicle owner or renter, any possible limitations on the vehicle use and information on the vehicle's maintenance plan in so far as is essential to the vehicle safety.

The Finnish Transport Safety Agency provides more detailed information about the requirements and other matters related rolling stock.

The Railway Technology Unit at the Finnish Transport Agency shall approve any rolling stock that is used solely for track work. If the stock at any point is used as a train or for shunting, it shall be approved by the Finnish Transport Safety Agency.

20 level crossings on the line section Toijala–Valkeakoski have been equipped with level crossing warning devices. The traction units of rolling stock and track construction/maintenance machines on this line section shall use a portable appliance in order to activate the warning devices. These appliances are available at Toijala station or railway yard. In 2017, other line sections will also be provided with warning devices. Instructions for this can be found on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>37</sup>.

RFID tags must be attached to all rolling stock.

---

<sup>37</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf4/paatos\\_2014\\_huomiolaitteiden\\_kayttoonotto\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf4/paatos_2014_huomiolaitteiden_kayttoonotto_web.pdf)

The Finnish Transport Agency expects the KUPLA application supplied by the Finnish Transport Agency to be used in all rolling stock operating in the state-owned railway network, as well as for shunting operations at single rail traffic operating points. Further information can be found in section 3.3.3.4.

The regulations and guidelines for track construction and maintenance machines can be found in chapter 6 of LIMO<sup>38</sup> (technical regulations and guidelines for rolling stock).

## 2.8 Staff Acceptance Process

Personnel with tasks related to traffic safety shall meet the health, training and other qualification requirements laid down in Finnish legislation. Specific provisions on qualifications are laid down in the Act on Traffic Safety Tasks in the Railway System (hereinafter the Qualification Act) which entered into force on 1 January 2010. The Act 860/2012 of 1 January 2013 on Traffic Safety Tasks in the Railway System, as amended, amends the Qualification Act (1664/2009)<sup>39</sup>. The Qualification Act lays down provisions for the qualifications required for personnel performing traffic safety tasks which have a direct impact on traffic safety. Those performing these tasks shall also meet the Finnish Transport Safety Agency requirements concerning health, training and other qualifications. The qualification requirements vary depending on the tasks.

Three Government Decrees have been issued pursuant to the Qualification Act. These entered into force on 15 January 2013. The Government Decree 12/2013<sup>40</sup> lays down provisions on the language skills required by personnel with traffic safety tasks in the railway system. Government Decree 13/2013<sup>41</sup> applies e.g. to the requirements regarding educational institutes providing railway safety training, instructors and examiners of tests taken by drivers of rolling stock. Government Decree 11/2013<sup>42</sup> applies to the qualification data of the traffic safety personnel to be entered into the railway system qualification register maintained by the Finnish Transport Safety Agency and into the supplementary certificate register of the traffic operator.

The Finnish Transport Safety Agency has issued more specific regulations pursuant to the Qualification Act. The regulation on training programmes for traffic safety tasks in the railway systems entered into force on 1 January 2011. Furthermore, the agency has issued regulations on the health requirements and health examinations for personnel with traffic safety tasks in the railway system. These regulations entered into force on 3 January 2011. The Finnish Transport Safety Agency has also issued a regulation, which entered into force on 15 May 2012, on the requirements regarding psychological aptitude and psychological personality assessments of personnel with traffic safety tasks in the railway system.

---

<sup>38</sup> [http://www.trafi.fi/filebank/a/1337751267/76847b3ff91e21745ca9ff5193d7c8eg/9723-Kumottu-LIMO\\_6.pdf](http://www.trafi.fi/filebank/a/1337751267/76847b3ff91e21745ca9ff5193d7c8eg/9723-Kumottu-LIMO_6.pdf)

<sup>39</sup> <http://www.finlex.fi/fi/laki/alkup/2009/20091664>

<sup>40</sup> <http://www.finlex.fi/fi/laki/alkup/2013/20130012>

<sup>41</sup> <http://www.finlex.fi/fi/laki/alkup/2013/20130013>

<sup>42</sup> <http://www.finlex.fi/fi/laki/alkup/2013/20130011>

The amended Qualification Act and the Government Decrees and Regulations issued under the Qualification Act can be found (in Finnish) on the Finnish Transport Safety Agency's website <http://www.trafi.fi> (Säädökset)<sup>43</sup>.

The Qualification Act does, however, not apply to any such tasks which only have an indirect impact on traffic safety in the railway system. Therefore, the Finnish Transport Agency has issued safety instructions for track maintenance, which entered into force on 16 April 2012, regarding the specific technical qualifications (other than traffic safety qualifications) required for e.g. track work. These instructions can be found in Finnish on the Finnish Transport Agency's website:

<http://www.liikennevirasto.fi><sup>44</sup>.

A safety certificate can only be granted or approved, if the railway operator has submitted information to the Finnish Transport Safety Agency on the qualifications of personnel or any other persons performing traffic safety tasks in the railway system and to the extent necessary, on a case-to-case basis, of the qualifications of persons handling the technical certificates for track maintenance. If necessary, the Finnish Transport Safety Agency may upon issuing the safety certificate examine in other ways and in more detail whether a person or persons employed by the railway traffic operator or otherwise connected to his or her operation meets the set qualifications.

#### **Qualification requirements for operating in a restricted area (train driver qualification)**

Restricted area refers to a private siding, connected to the state-owned railway network or to another private siding; and to/from which traffic is operated; or to an area of the state-owned railway network where a unit arriving from a private siding may operate within the framework of a transport agreement with the Finnish Transport Agency.

Successful completion of the training programme "Driver, shunting, restricted area" (Kuljettaja, vaihtotyö, rajoitettu alue) leads to the task-specific qualification to act as a train driver in a restricted area doing shunting operations and to act as the shunting foreman in the restricted area. Moreover, the training programme provides a task-specific qualification for traffic control, i.e. the person can establish a train path and authorize track use under the supervision of the traffic management operator.

---

<sup>43</sup> <http://www.trafi.fi/rautatiet/saadokset>

<sup>44</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/lo\\_2012-01\\_turo\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf)

## 3 Infrastructure

### 3.1 Introduction

The infrastructure refers to the state-owned railway network managed by the Finnish Transport Agency. The Finnish Transport Agency's infrastructure management comprises the construction and maintenance of tracks, structures and equipment connected with them, as well as of the immoveable property needed for infrastructure management and planning.

### 3.2 Extent of Network

#### 3.2.1 Multi-Track Line Sections

##### 3.2.1.1 *Double-Track Line Sections*

Leppävaara–Kirkkonummi  
Huopalahti–Havukoski  
Kytömaa–Kyrölä  
Purola–Riihimäki–Sääksjärvi  
Kouvola–Juurikorpi  
Pohjois-Louko–Seinäjoki asema–Lapua  
Kytömaa–Hakosilta  
Riihimäki asema–Luumäki  
Tampere tavara–Lielähti  
Tampere Järvensivu–Orivesi  
Kokkola–Karhukangas

##### 3.2.1.2 *Three-Track Line Sections*

Kyrölä–Purola  
Sääksjärvi–Tampere tavara

##### 3.2.1.3 *Four-Track Line Sections*

Helsinki asema–Leppävaara  
Helsinki asema–Kytömaa

#### 3.2.2 Limits

The available network is presented graphically in Figure 3 and in Appendix 1.

The following line sections are closed to traffic:

- Aittaluoto–Parkano
- Kihniö–Haapamäki
- Pesiökylä–Taivalkoski
- Kolari–Äkäsjoki
- Niesa–Rautuvaara
- Kiukainen–Säkylä

- Isokylä–Kellosekä
- Lautiosaari–Elijärvi
- Lohja–Lohjanjärvi
- Otava–Otavan satama
- Yläkoski–Iisvesi
- Rantasalmi–Savonlinna
- Vaasa–Vaskiluoto
- Seinäjoki–Kaskinen

All changes will be published on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>45</sup>.

### **3.2.3 Connected Railway Networks**

There is a rail connection from Finland to Sweden via Tornio. The main outlines of traffic operating on the Tornio–Haaparanta line section are presented in Appendix 3. The Swedish Infrastructure Manager is Trafikverket.

A rail connection exists from Finland to Russia via Vainikkala, Imatrankoski, Niirala and Vartius. Railway traffic between Finland and Russia is based on the Rail Traffic Agreement between Finland and Russia. VR Group Ltd has the exclusive right to operate railway transit traffic to and from Russia in the Finnish railway network, until the renewed agreement on transit traffic between Finland and Russia enters into force.

## **3.3 Network Description**

### **3.3.1 Geographic Identification**

#### **3.3.1.1 Track Typologies**

The network is presented in Figure 3 and in the Appendix 1.

#### **3.3.1.2 Track Gauges**

The nominal track gauge on the railway network is 1,524 mm. The speed-dependent limit values for the track gauge are indicated in the Finnish Transport Safety Agency's provision called "Rautatiejärjestelmän infrastruktuuriasajärjestelmä" (Trafi/18116/03.04.02.00/2012). The provision is available from the Finlex website, <http://www.finlex.fi><sup>46</sup>.

#### **3.3.1.3 Stations and Nodes**

The available traffic operating points (stations) are presented in Figure 4 and in Appendix 2.

---

<sup>45</sup> <http://www.liikennevirasto.fi/network-statement>

<sup>46</sup> [https://www.finlex.fi/TRAFI\\_8591\\_03.04.02.00\\_2014](https://www.finlex.fi/TRAFI_8591_03.04.02.00_2014)




Figure 3. State-owned railway network at the beginning of timetable period 2017.




Figure 4. Traffic operating points on the state-owned railway network at the beginning of timetable period 2017.






Figure 5. Trans-European railway network in Finland (The Finnish TEN network).

### **3.3.2 Capabilities**

#### **3.3.2.1 Loading Gauge and Structure Gauge**

The loading gauge (KU) in Appendix 4, and the structure gauge (ATU) in Appendix 5, are used throughout the state-owned railway network. On private sidings, there may be both loading and structure gauge limitations, which Railway Undertakings shall clarify separately before carrying out transportation.

Further information on the vehicle gauge and the structure gauge of the track can be found in the Finnish Transport Safety Agency [regulation \(Trafi/18116/03.04.02.00/2012\)](#)<sup>47</sup> (Infrastructure subsystem of the conventional rail system). Further information on the track work gauge can be found in [TURO](#)<sup>48</sup> (safety instructions in track maintenance).

#### **3.3.2.2 Weight Limits**

##### **Axle loads**

225 kN axle loads are permitted on most of the railway network. The maximum permitted axle loads per line section are indicated in Appendix 6. Appendices 17 and 18 specifies the axle loads and restrictions in connection with overweight loads and the wagons used in the eastern transit traffic.

##### **Metre loads**

The permitted metre load of rolling stock throughout the state-owned railway network is 80 kN/m.

#### **3.3.2.3 Line Gradients**

The maximum gradient is 20 mm/m on the main lines and 22.5 mm/m on the secondary lines. The maximum gradient of line sections measured over a distance of 1,200 metres is presented in Appendix 1.

The gradient between the traffic operating points Leinelä and Kivistö on the Ring Rail Line is 40 mm/m.

#### **3.3.2.4 Line Speeds**

The maximum speed is 220 km/h for passenger trains and 120 km/h for freight trains. The maximum speed on tracks without ATP is 80 km/h. The speeds permitted for passenger and freight trains on the railway network are indicated in Appendix 6.

---

<sup>47</sup> <https://www.finlex.fi/fi>

<sup>48</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/lo\\_2012-01\\_turo\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf)

### **Areas where speed can be temporarily increased due to a steep gradient**

A train with a maximum speed of 70 km/h is allowed to exceed its train-specific speed by 10 km/h in the following areas:

- Taavetin mäki in the direction Lä-Kvl: km 244.0-234.0
- Sitikkalan mäki in the direction Lä-Kvl: km 170.2-161.5
- Härmänmäki in the direction Aro-Kon: km 683.0-673.0

If in areas mentioned above (Taavetin mäki, Sitikkalan mäki and Härmänmäki) are temporary speed limits which are under 70 km/h, they must be obeyed.

#### **3.3.2.5 Maximum Train Lengths**

The maximum train length permitted on a line section shall be such that trains can also use secondary tracks at the traffic operating points. Trains need not, however, be capable of using all secondary tracks at all traffic operating points. The train lengths used for dimensioning line sections are 700, 750, 925 and 1100 metres. The longest secondary tracks at each traffic operating point are indicated in Appendix 2.

#### **3.3.2.6 Power Supply**

The nominal voltage of the electrification is 25 kV/50 Hz AC. On all electrified lines, power is taken from the contact line above the track. One or both of the running rails and return conductors form a return circuit. The neutral sections are adjacent to the feeding sections of the contact line feeder stations. Rolling stock cannot collect current from the neutral sections. The main switch of the electric locomotive or electric train unit must be opened at the neutral sections. The electric traction unit of the train is not allowed to stop at a neutral section.

The width of the pantograph head shall be 1,950 mm. The maximum stagger of the contact wire is 400 mm. The contact wire height can vary from 5,600 to 6,500 mm. Therefore a current collector in an elevated position must be operational within the range 5,600–6,600 mm. The nominal height of contact wire is 6,150 mm. The electrified line sections are indicated in Appendix 7.

The maximum current supply capacity of the overhead line for electrically hauled stock is 350-800 A. The available current is affected by the number and position of stock using electric power at the same time in the power supply area.

For fixed installations, electrification is described in part 5 "**Sähköistetty rata**"<sup>49</sup> (Electrified railway) of the Ratatekniset ohjeet (RATO) publication.

The provision is available in the Finlex website <http://www.finlex.fi><sup>50</sup> and in section 21 'Rolling Stock' of the Finnish Transport Agency's publication 'Ratatekniset ohjeet' (RATO)<sup>51</sup>.

All new electric traction stock acquired after 2012 shall be equipped with an energy measurement system compliant with the requirements for billing according to

---

<sup>49</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf4/rato\\_5\\_sahkoistetty\\_rata.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf4/rato_5_sahkoistetty_rata.pdf)

<sup>50</sup> <http://www.finlex.fi/fi/viranomaiset/normi/499001/35169>

<sup>51</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/lo\\_2012-21\\_rato\\_21\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-21_rato_21_web.pdf)

standard EN 50463 (2012). For example, UTILTS or MSCONS messages can be used for transferring data to the Finnish Transport Agency's asset-liability management system.

### **3.3.3 Traffic Control and Communications Systems**

#### **3.3.3.1 Signalling Systems**

The signalling systems in use are indicated in Appendix 1 and graphically in Appendix 8.

A line with section block is a line divided into block sections. Only one train may be in a block section at a time. Issues related to section blocks are presented in the Finnish Transport Safety Agency's provision called "Määräys ohjaus-, hallinta- ja merkinanto-osajärjestelmästä" as well as in RATO publication, part 6 "[Turvalaitteet](#)"<sup>52</sup> (Signalling systems). The provision is available from the Finlex website <http://www.finlex.fi><sup>53</sup>.

Combined-aspect signals refer to the signals for railway traffic control developed by the Finnish Transport Agency. These signals may be used to replace older signals in the railway network. Combined-aspect signals have been introduced on some line sections and traffic operating points in the state-owned railway network. A map of the combined-aspect signals can be found in Appendix 8.

#### **3.3.3.2 Rolling Stock Monitoring Equipment**

Hot box detectors have been placed on the railway network at approx. 50 km intervals. The distance can be greater on line sections on which the maximum speed is less than 160 km/h. The devices are installed on the track and to ensure that they function as intended, the axle-box cases of the rolling stock must be positioned so that their lower surface is within the range of the detector. The alarms given by the system are forwarded to the traffic control of the railway line section in question as well as to the Finnish Transport Agency's Technical Control Centre.

The wheel force measuring stations are so closely spaced that the rolling stock will cross a measuring station at least once on its normal route. The devices measure the static and dynamic load impact of the wheelset on the rail. Based on these measuring results, excess weight, uneven loading and certain defects in the wheel tread can be detected. The devices are installed in the track. Device alarms caused by critical wheel defects are forwarded to the traffic control of the railway line section in question. Alarms caused by uneven loading are forwarded to the Finnish Transport Agency's Rail Traffic Management Centre.

The camera systems for monitoring the condition of contact strips in pantographs on electric traction units have mainly been installed on road bridges overpassing the track. The monitoring points are placed so that they photograph the active pantographs approaching the measuring station. The photos are analysed automatically or manually. Defective pantographs are reported to the company operating the rolling stock.

---

<sup>52</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/2012\\_rato6\\_en\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/2012_rato6_en_web.pdf)

<sup>53</sup> [https://www.finlex.fi/TRAFI\\_26494\\_03.04.02.00\\_2014](https://www.finlex.fi/TRAFI_26494_03.04.02.00_2014)

Rolling stock equipped with radio frequency identifiers (RFID), which are interoperable with the Finnish Transport Agency's system, enables prompt allocation of the information to the correct rolling stock unit and its maintenance manager. The interoperability requirements are specified in the Finnish Transport Agency's publication [RATO 21 Liikkuva kalusto](#)<sup>54</sup>.

A map of the location of the hot box detectors is presented in Appendix 19.

The Finnish Transport Agency's Technical Control Centre monitors and maintains the network of control devices. The control centre uses the VALTSU system to collect all measuring data produced by the control devices, adding it to the available RFID reading and forwarding this information to all concerned parties. More information about the Technical Control Centre can be found in section 3.8.7.

### **3.3.3.3 Traffic Control Systems**

The line sections equipped with an automated traffic control system are indicated in Appendix 1 and in Appendix 8. The following automated traffic control systems are in use: centralised traffic control (CTC) and radio control. On the CTC- and radio-controlled lines, all routes are equipped with the remote control of turnouts and routes. On secondary, loading and storage sidings of these line sections, however, local route setting may also be necessary. On radio-controlled lines, routes shall be set locally if it is necessary to operate on secondary, loading or storage sidings.

### **3.3.3.4 Communications Systems**

#### **VIRVE network**

The RAILI or VIRVE networks shall be used for communication between traffic control, operation and track work during the timetable period. In 2017, the Finnish Transport Agency will replace the RAILI network with the VIRVE network. During the transitional period in 2017, both networks will be used. Initially, the coverage of the VIRVE network was planned to be the same as that of the RAILI network. The RAILI network covers most of the state-owned railway network. Some track sections remain outside the RAILI network. Further information can be found on the Finnish Transport Agency website <http://www.liikennevirasto.fi><sup>55</sup>.

If the RAILI or VIRVE networks cannot be used for technical reasons or poor GSM-R or VIRVE radio network reception, the parties must use other available phone or mobile phone networks. The traffic control, or the corresponding train drivers, shunting managers and persons responsible for the track works must be informed of any disruptions preventing or hindering the use of the network, and of alternative contact information in accordance with the communications instructions.

The RAILI or VIRVE networks are only used for communication concerning traffic safety.

---

<sup>54</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/lo\\_2012-21\\_rato\\_21\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-21_rato_21_web.pdf)

<sup>55</sup> <http://www.liikennevirasto.fi>

The Finnish Transport Safety Agency sets regulations on, for example, traffic operation, track work and communications. The valid regulations can be obtained at the Finlex website <http://www.finlex.fi><sup>56</sup>.

The Finnish Transport Agency provides working instructions that deal with traffic control, traffic operation, track work and communications, and complement the regulations. The valid [working instructions](#)<sup>57</sup> can be obtained at the Finnish Transport Agency's website. Contact information for traffic control can be obtained at the Finnish Transport Agency [Extranet sites](#)<sup>58</sup>.

Information of abnormal events or situations will be provided via the Advance Information System (JETI), maintained by the Finnish Transport Agency, and through notifications given by the traffic control. Drivers and persons responsible for the track work must have knowledge of the advance plans that are valid for the duration of the work/journey and in the working area/track sections of the journey. They must also have the contact information for the traffic control.

Before the VIRVE network is taken into use, the railway operators must enter into a VIRVE agreement with the Finnish Transport Agency on the subscription charge for the VIRVE phones to be installed in the rolling stock. More information about this can be found in section 2.3.3.

#### **Train drivers' data terminal equipment application (KUPLA)**

The Finnish Transport Agency expects the data terminal equipment application (KUPLA), supplied by the Finnish Transport Agency, to be used in all rolling stock in the railway network, also for shunting operations at separate traffic operating points and for traffic in connection with track works. For the time being, this requirement does not apply to infrastructure management units only used on sections reserved for track work. Railway operators are fully responsible for the acquisition and operating costs of the terminal device in which the train drivers' terminal application is installed. KUPLA application requires a Windows touch-screen tablet (Windows 8.1 or a more recent version) with a GPS function and a GSM-based commercial internet connection. More detailed instructions and the technical specifications required to use the KUPLA application are available on the Finnish Transport Agency's website. The Finnish Transport Agency cooperates with the railway operators to further develop the functions of the KUPLA application. The Finnish Transport Agency uses the positioning data of the device in their traffic management systems, but the data is not disclosed to a third party, unless otherwise provided by law.

---

<sup>56</sup> [http://www.finlex.fi/fi/viranomaiset/normi/499001/?\\_offset=0&\\_max=49](http://www.finlex.fi/fi/viranomaiset/normi/499001/?_offset=0&_max=49)

<sup>57</sup> [http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat\\_suunnittelijat/vaylanpidon\\_ohjeet](http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet)

<sup>58</sup> [http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat\\_suunnittelijat/konsultille/Extranet](http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/konsultille/Extranet)

### 3.3.3.5 Other Systems

Many of the larger stations have camera surveillance. The system allows traffic controllers to monitor the movement of trains and the Information Centre to observe the movement of passengers on platforms as well as the technical functioning of the information equipment. The Security Control Centre is able to monitor passenger safety and control vandalism. The Technical Control Centre and property maintenance can use the system to check on the tidiness of platform areas and spot any need for technical maintenance work.

### 3.3.3.6 ATP Systems

Automatic train protection (ATP) is a system that controls the speed of a train.

Locomotives operating in the state-owned railway network must be fitted with an automatic train protection system (ATP) according to class B in the Finnish system (ATP-VR/RHK), or equipped with the European Train Control System in conjunction with legacy ATPs through a specific transmission module (ETCS + STM). Information about the availability and terms of delivery of ATP equipment is given by [Bombardier Transportation Finland Oy](#)<sup>59</sup>. Information regarding the conjunction ETCS+STM is provided by both Bombardier Transportation Finland Oy and [Ansaldo STS Finland Oy](#)<sup>60</sup>.

ATP locomotive equipment must be used in train traffic or, if operating without ATP locomotive equipment, an exceptional permit as referred to in section 76 of the Railway Act ([304/2011](#))<sup>61</sup> is compulsory. The Finnish Transport Safety Agency may grant an exceptional permit provided that it does not endanger the safety of the rail system. In cases concerning the use of ATP locomotive equipment, a fixed-term exceptional permit may be granted if the case involves a need for exceptional and temporary train operation or if ATP locomotive equipment or spare parts are not available. An exceptional permit may not be granted for a train unit or locomotive which is used in passenger or commercial freight traffic, when it is not directly connected with infrastructure management. ATP locomotive equipment is not required in stock that is used for shunting only.

The Museum Train Traffic Regulation (RVI/295/411/2008) has been repealed and replaced by the Finnish Transport Safety Agency's regulation on traffic operation and management "[Käyttötoiminta ja liikenteen hallinta \(TRAFI/22100/03.04.02.00/2012\)](#)"<sup>62</sup>. The new regulation does not cover all aspects of museum traffic, so museum traffic operators should among other things check the Finnish Transport Safety Agency's instructions on ATP systems. Updated instructions are also changed in the Network statement as required. Updates are posted on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>63</sup>.

---

<sup>59</sup> <http://www.bombardier.com/>

<sup>60</sup> <http://www.ansaldo-sts.com/en/about-us/ansaldo-around-world/our-companies/ansaldo-sts-finland>

<sup>61</sup> <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

<sup>62</sup> <https://www.finlex.fi>

<sup>63</sup> <http://www.liikennevirasto.fi/network-statement>

Please contact the Finnish Transport Safety Agency for more information about ATP systems and operations and for instructions about museum traffic. The Finnish Transport Safety Agency's regulations can be found on the website <http://www.trafi.fi><sup>64</sup>.

#### **3.3.3.7 Data system interfaces**

The Finnish Transport Agency has made a description of the most important data system interfaces, application services and the required technological components from the railway operators' perspective. The description is available on the web address: <http://www.rautatiemarkkinoille.fi/jarjestelmat><sup>65</sup>

## **3.4 Traffic Restrictions**

### **3.4.1 Specialised Infrastructure Capacity**

The Finnish Transport Agency may designate a train path or a part of it as specialised infrastructure capacity, if there are sufficiently alternative routes for other traffic. Specialised infrastructure capacity refers to a train path or a part of it on which priority is given to the type of traffic for which the infrastructure is specialised. The Finnish train paths with specialised infrastructure capacity are: Helsinki–Kerava easternmost track and eastern middle track, Helsinki–Leppävaara southernmost track and southern middle track and both tracks between Huopalahti and Havukoski. These urban tracks are reserved primarily for Helsinki Area commuter traffic. It is not allowed to operate passenger trains between Kerava and Vuosaari and freight trains between Havukoski and Huopalahti. In addition to these line sections, platform tracks 1-4 and 16-19 at the Helsinki Central Railway Station are designated as specialised infrastructure reserved for commuter traffic. Access to track 4 especially requires coordination between rail capacity applicants.

### **3.4.2 Environmental Restrictions**

When registering rolling stock, the Finnish Transport Safety Agency's regulations and instructions are applied. The regulations set out general and special requirements for rolling stock concerning noise, vibration, electromagnetic interferences, emissions, substances hazardous to the environment and the use of recycled construction materials. For more information, go to the Finnish Transport Safety Agency's website <http://www.trafi.fi><sup>66</sup>.

Vibration-related speed restrictions are imposed on parts of the railway line on 18 line sections throughout Finland. The restrictions mainly apply to over 3,000 ton gross weight heavy trains. More information can be found in Appendix 9.

---

<sup>64</sup> [http://www.trafi.fi/rautatiet/saadokset/kansalliset\\_maaraykset](http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset)

<sup>65</sup> <http://www.liikennevirasto.fi/ammattiliikenne-raiteilla#.VmWAtF6RNoc>

<sup>66</sup> [http://www.trafi.fi/rautatiet/saadokset/kansalliset\\_maaraykset](http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset)



### **3.4.3 Dangerous Goods**

#### **Carriage by rail of dangerous goods**

In domestic rail transport, the following statutes and regulation are observed: the Act on the Transport of Dangerous Goods (719/1994, as amended), applicable to all transport modes, the Government Decree on the Transport of Dangerous Goods by Rail (195/2002, as amended) and the Finnish Transport Safety Agency's (Trafí) regulation on the carriage of dangerous goods by rail.

In the appendices to Trafí's regulation, there are detailed provisions concerning the classification of dangerous goods, packaging, required documentation, equipment and approval of vehicles, drivers' certificates, excepted quantities, marking in the bill of lading and on the packages, placarding and marking of vehicles/wagons.

Finland's regulations on transport by rail are based on the international RID regulations.

Trafí supervises the carriage of dangerous goods by rail and the related temporary storage. Dangerous goods rail transports arriving to and departing from Finland and the related temporary storage is also supervised by Finnish Customs and the Finnish Border Guard in their respective areas of responsibility. In these cases, Trafí still carries the primary responsibility.

#### **Reporting of incidents**

If an accident or incident, as referred to in section 1.8.5 of the Trafí regulation (concerning carriage of dangerous goods by rail) occurs during loading, filling, carriage or unloading of dangerous goods, the loader, filler, carrier or consignee shall ascertain that a report conforming to the model prescribed in the regulation is made to Trafí and the competent authority of the Safety Investigation Authority without delay.

Reports on transport of radioactive goods shall only be made to the Radiation and Nuclear Safety Authority in Finland (STUK).

#### **Special agreements**

RID special agreements can also be applied when signed by the states involved in the transport operation.

An RID special agreement, signed by Finland, may also be applied to domestic rail transports of dangerous goods. At present, there are no RID special agreements signed by Finland in force.

#### **Safety Advisor**

Companies transporting or loading dangerous goods or whose operations impact on the safe transport of these goods on roads or railways must appoint a certified Safety Advisor.

The person appointed Safety Advisor must pass an examination, where Trafí serves as the examiner.

Provisions on the Safety Advisor have been laid down in the Government Decree 274/2002.

---

**Convention on International Carriage of Dangerous Goods by Rail****RID regulations**

Finland and other countries that have signed the intergovernmental COTIF Convention, comply with the regulations in Appendix C of the Convention concerning the carriage of dangerous goods by rail (RID, Appendix to COTIF Convention).

**COTIF Convention**

Convention concerning International Carriage of Goods by Rail COTIF (52/2006)

- The Ministry of Transport and Communications' notification on the entry into force of the amendments to the regulations in Appendix C (RID) of the COTIF Convention concerning carriage by rail of dangerous goods (107/2014).
- RID 2015
- RID special agreements

RID special agreements can be applied to the carriage of dangerous goods by rail between countries which have signed the special agreement. At present there are no RID special agreements signed by Finland in force.

**Agreements on transport of dangerous goods in direct international railway traffic between Finland and Russia**

TREATY between the Government of the Republic of Finland and the Government of the Russian Federation on the transport of dangerous goods in the direct international railway traffic between Finland and Russia.

- Act on the implementation of the provisions of a legislative nature in the Treaty on the transport of dangerous goods in the direct international railway traffic between Finland and Russia (76/2014) (Government Bill 41/2014)
- Government Decree on the implementation of the Treaty and on the entry into force of the Act on the implementation of the provisions of a legislative nature in the Treaty on the transport of dangerous goods in the direct international railway traffic between Finland and Russia (Treaty Series No. 77/2014)

TREATY on the implementation of the treaty between the Ministry of Transport and Communications in the Republic of Finland and the Ministry of Transport of the Russian Federation on the transport of dangerous goods in the direct international railway traffic between Finland and Russia.

- Government Decree on the implementation of the Treaty between Finland and Russia entered into with the Ministry of Transport of the Russian Federation on the transport of dangerous goods in the direct international railway traffic between Finland and Russia (Treaty Series No. 96/2014)
- An administrative agreement is a technical agreement, with provisions concerning details such as packages, containers, contents and marking of the bill of lading. The technical provisions are based on the provisions laid down in the SMGS Agreement 2009, which largely correspond to the RID provisions included in the COTIF Agreement which is applied in EU countries. Negotiations with Russia on the updating of the technical provisions started in January 2015.

#### **3.4.4 Tunnel Restrictions**

There are tunnel restrictions on the Helsinki–Turku and Orivesi–Jyväskylä line sections. The restrictions are indicated in Appendix 11.

Only freight trains and rolling stock required in track work are allowed to operate in tunnels on the Vuosaari line. It is forbidden to take passengers through the tunnels on the Vuosaari line. Only electric freight traffic is allowed. Individual diesel locomotive transfers are permitted. The Finnish Transport Agency examines the possibility of using diesel locomotives in the tunnels of the Vuosaari railway line.

In the Vuosaari tunnel the locomotive and track work machinery must be equipped with an oxygen apparatus.

Only passenger trains and rolling stock intended for track work are allowed to operate between Huopalahti and Havukoski. Passenger traffic between the traffic operating points Leinelä and Kivistö is only allowed when electric traction units are used. Individual diesel locomotive transfers are permitted.

#### **3.4.5 Bridge Restrictions**

Bridge restrictions are described in Appendix 12.

#### **3.4.6 Overweight Load Transport**

Details concerning the axle loads and restrictions applicable to the carriage of overweight loads and wagons used in the eastern transit traffic can be found from the Appendices 17 and 18.

### **3.5 Availability of the Infrastructure**

The restrictions affecting traffic are presented in appendices 9, 10, 11, 12 and in the JETI system (the system for advance information on train traffic). Track work causing traffic restrictions is presented in Appendix 13.

The substations of the electrified line sections have a limited capacity for supplying power to the contact line. The power supply will shut down automatically in overload situations, which will cause a temporary power failure in the contact line.

### **3.6 Passenger Stations**

The lengths of passenger platforms (shortest/longest) are indicated in Appendix 2. *Platforms not maintained by the Finnish Transport Agency* are indicated in brackets.

### **3.7 Freight Terminals**

Loading possibilities are indicated in Appendix 2. K means “yes” and Y “private”. For loading platforms, the register lists their available length.

Private siding connections at traffic operating points are indicated by the marking "Private sidings" in Appendix 2.

## 3.8 Service Facilities

### 3.8.1 Train Formation Yards

Train formation yards are marshalling yards in which the layout and size of the track system make it possible to form trains. The train formation yards are indicated by the marking "K" in column "Shunting" in Appendix 2. More information about train formation yards can be found in section 5.2.1.

#### 3.8.1.1 Inclines

At the traffic operating points in Kouvola and Tampere the railway companies have access to inclines for the recomposing of train wagons. Further information about inclines and access to them can be found in section 5.2.1.

### 3.8.2 Storage Sidings

Storage sidings are yard tracks primarily intended for the parking of wagons and coaches waiting for a transport task. Wagons can only be stored temporarily on these tracks. More information about storage sidings can be found in section 5.2.1.

### 3.8.3 Maintenance and Service Facilities

Access to maintenance and service facilities requires an agreement with their maintenance provider.

### 3.8.4 Refuelling Facilities

The Appendix 2 shows the refuelling facilities on traffic operating points. More information can be found in section 5.3.4.

### 3.8.5 Technical Equipment

Appendix 2 shows the cranes located at traffic operating points. More information can be found in section 5.3.5.

### 3.8.6 Security Control Centre

The Finnish Transport Agency's Security Control Centre has the main responsibility for improving personal security at stations and in platform areas and for protection against vandalism of railway infrastructure. The Security Control Centre monitors situations, receives reports and creates a situation picture, as well as guides security officers, security guards or other authorities to the location where help is required. The operative work in the field is led from the Security Control Centre.

The camera surveillance of the railway and bus stations for commuter transport in the metropolitan area and of the park-and-ride facilities of the Ring Rail Line has been transferred to the Finnish Transport Agency's Security Control Centre. The Security Control Centre acts as the operations and control centre for security guard services.

The Security Control Centre collaborates with the cities of Vantaa, Helsinki and Espoo and with HSL (Helsinki Region Transport) and HKL (Helsinki City Transport).

Security control and security guard services at traffic operating points for commuter transport comprise security control and security guard services at bus terminals and their vicinity, traffic operating points, park-and ride facilities and possibly also on trains. Services on buses, bus lines, bus stops in the region of the municipal federation of HSL (Helsinki Regional Transport) are also considered security control and security guard services. The services, which if necessary can be expanded, cover most of the commuter area.

The Security Control Centre's duties include receiving and forwarding reports from alarm devices, personal safety devices, fire alarms and HVAC systems, as well as other related activities. The Security Control Centre also gives emergency alerts to the stations in the commuter area.

### **3.8.7 Technical Control Centre**

The tunnel and facilities management systems on the Ring Rail Line and the Vuosaari railway line are monitored from the Finnish Transport Agency's Technical Control Centre.

The Technical Control Centre has two main duties: The first is to monitor the tunnel and building automation system and to take the required action in both normal and exceptional situations. The alarms activated by the systems in exceptional situations are on a case-to-case basis forwarded to different partners, for example the fire and rescue authority, the police, system managers, traffic operators, the Security Control Centre and operations centre.

The second duty is to monitor and analyse rolling stock monitoring systems and take the required action based on the analysis. Rolling stock monitoring refers to monitoring of the properties of tractive stock, wagons and trains which have a direct or indirect interface with the traditional railway infrastructure. Geographically, the rolling stock monitoring systems are located throughout the railway network.

## **3.9 Infrastructure Development**

The Finnish Transport Agency has published several web-based reports on, for example, the development strategy of railway network capacity 2035, further electrification of the railway network and the future of passenger rail services. The Finnish Transport Agency has also ordered railway plans on a project basis. The development plans for the railway network are presented in [the Finnish Transport Agency's Action and Financial Plan](#) <sup>67</sup> for the years 2015–2018.

In 2017, five development projects will be underway in the railway network:

- Ostrobothnian rail line, project to be completed in 2017
- Western track in Central Pasila: will be built at the same time as the first new block to be built in Central Pasila. The track will be opened to traffic by 2020.
- Riihimäki triangle line

---

<sup>67</sup> [http://www2.liikennevirasto.fi/tts\\_2015-2018](http://www2.liikennevirasto.fi/tts_2015-2018)

- Added capacity on the line section Helsinki–Riihimäki, 1st phase to be completed 2015–2019.
- Improvement of the efficiency of Helsinki railway yard, 2016–2020.
- Repair backlog reduction in the railway network

In 2016, three projects in the Transport Policy Report will be implemented with funding for the basic transport infrastructure management:

- Development of the traffic control system
- Improvement of timber terminals
- Repairs of areas with ground frost damage and soft soils in the main railway network

## 4 Capacity Allocation

### 4.1 Introduction

The legal framework of capacity allocation is described in the [Directive 2012/34/EU](#)<sup>68</sup> of the European Parliament and of the Council on the allocation of railway infrastructure capacity and the levying of charges for the use of railway infrastructure and safety certification (hereinafter referred to as the "Capacity and Infrastructure Charge Directive"), but also Railway Act ([304/2011](#))<sup>69</sup> and in the Government Decree on the Timetable Period in Railway Traffic and Applying for Infrastructure Capacity ([413/2011](#))<sup>70</sup>.

### 4.2 Description of Process

Capacity for operating regular train services on the state-owned railway network shall be requested from the Finnish Transport Agency for each timetable period within the time defined. Capacity for regular train services can also be requested during the timetable period. The schedule for train path requests and for allocation is shown in a diagrammatic form in Figure 6. It is also possible to make *ad hoc* requests for capacity for other than regular traffic.




Figure 6. Diagrammatic presentation of the schedule for train path requests and for allocation process.

<sup>68</sup> <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2012:343:0032:0077:EN:PDF>

<sup>69</sup> <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

<sup>70</sup> <http://www.finlex.fi/fi/laki/alkup/2011/20110413>

#### 4.2.1 Requesting Rail Capacity

The principles of capacity requests are described in the Railway Act (304/2011)<sup>71</sup> and in the Government Decree on the Timetable Period in Railway Traffic and Applying for Infrastructure Capacity (413/2011)<sup>72</sup>. In order to specify the Act and Decree, the Finnish Transport Agency has drawn up [an instruction for requesting rail capacity](#)<sup>73</sup>.

Requests for rail capacity for regular services, alterations to the regular services and for ad hoc capacity are to be submitted in the data system [LIIKE](#)<sup>74</sup> or using the interface specified by the Finnish Transport Agency (further information in the instructions for requesting rail capacity).

In addition, a separate report of the operational requirements concerning the use of the freight yards when requesting rail capacity for regular services for the timetable period shall be submitted to the Finnish Transport Agency's registry office.

If the LIIKE system is inoperative due to a widespread malfunction, the Rail Traffic Management Centre can approve requests for capacity changes by phone. If the JETI system is inoperative due to malfunctions, the Rail Traffic Management Centre instructs users to use the backup systems containing driver timetables and advance report information.

Further information about requesting rail capacity and the background information regarding timetable planning is found in the instruction for requesting rail capacity.

#### 4.2.2 Requesting Rail Capacity for Shunting Operations

Rail capacity for shunting operations between traffic operating points and between parts of divided traffic operating points is requested in the LIIKE system. The above mentioned distances between traffic operating points and the sections of the railway yards are specified in the instructions for requesting and allocating rail capacity. Rail capacity which has been requested and allocated, as well rail capacity allocated for track work in the LIIKE system is prioritised on all line sections. If rail capacity is available, the traffic control may in an operative situation allocate rail capacity for shunting operations to be performed between parts of the traffic operating points without using the LIIKE system.

The procedure for requesting rail capacity for shunting operations will be changed, and the revised procedure will be effective starting with the timetable period 2018. It will then be possible to request capacity for the transfers between Ilmala railway yard and Helsinki in the annual request for rail capacity for regular rail services. Requests for capacity included in the request for the timetable period will in that case be prioritised over capacity requested at a later stage. However, the capacity on the line section in question will be coordinated in more detail after the decision on allocation

---

<sup>71</sup> <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

<sup>72</sup> <http://www.finlex.fi/fi/laki/alkup/2011/20110413>

<sup>73</sup> [http://www.liikennevirasto.fi/documents/20473/23990/ohje\\_2015\\_ratakapasiteetin\\_hakuohje\\_web.pdf/0475d618-ea67-48fe-8c16-8ed53ebc21f8](http://www.liikennevirasto.fi/documents/20473/23990/ohje_2015_ratakapasiteetin_hakuohje_web.pdf/0475d618-ea67-48fe-8c16-8ed53ebc21f8)

<sup>74</sup> <http://www.liikennevirasto.fi/ammattiliikenne-raiteilla/liikennesuunnittelu/liike#.Vjic3rU8Kpo>



of capacity has been published and as the plans on the circulation of transport operators' stock and the plans on track access have become more specific.

Shunting operations performed at the freight yards of traffic operating points are separately agreed upon in the marshalling yard agreement. The main order of priority for the traffic at the traffic operating point is the following:

1. Train traffic (passenger, freight, including border traffic and track work units using the line)
2. Shunting operations between traffic operating points
3. Traffic between different parts of the traffic operating point due to shunting operations
4. Wagon sorting operations (formation/splitting-up of trains)
5. Moving of rolling stock to holding siding.

#### **4.2.3 Requesting Marshalling Yard Capacity**

Railway Undertakings shall in connection with their annual requests for rail capacity for regular services also report their requirements concerning the marshalling yards (operating time, operational requirements e.g. marshalling and storage and, if possible, track reservation).

Regarding needs for storage of rolling stock which have arisen during the timetable period, all other railway operators shall contact the Finnish Transport Agency's unit Railway Network Usage.

In exceptional situations, rolling stock can be temporarily stored on separately specified storage sidings, reserved for train traffic as described in section 5.2.1 of this Network Statement. The Infrastructure Manager (the Rail Management Centre) decides on the rail capacity for marshalling yards and gives an operative solution to the access to tracks in demanding situations, including urgent, short-term storage needs. The Infrastructure Manager's Railway Network Usage Unit approves storage requested for longer than one week.

#### **4.2.4 Developing the Process of Requesting Rail Capacity**

The Finnish Transport Agency is developing the process for specifying a more detailed level of capacity management on marshalling yards (such as the level of precision for track reservations, purpose of use and focusing on daily operations as opposed to management at the annual level). The objective of this development work is to ensure impartial capacity allocation in a multi-operator environment and sufficient dissemination of situational awareness information to the various parties. The development work is carried out cooperatively between the railway operators, the traffic control and railway maintenance.

## 4.3 Schedule for Train Path Requests and Allocation Capacity Requests

### 4.3.1 Schedule for Working Timetable

The timetable period in railway traffic starts annually at the second weekend of December, at 00.00 hrs on the night between Saturday and Sunday, and ends at the corresponding time the following year. The timetable period 2017 will start on 11.12.2016 and end on 9.12.2017. Correspondingly, the timetable period 2018 will start on 10.12.2017 and end on 8.12.2018. Applicants for capacity shall request capacity no earlier than 12 and no later than 8 months ahead of the timetable period. One request may include all the changes in traffic to be made during the timetable period. In order to attain a well-functioning timetable structure, the rail capacity applicant is asked to give advance notice of any alterations to the existing timetable no later than 12 months before the timetable period begins, so that the Finnish Transport Agency, if required, may initiate the procedure of coordinating the timetable structure about 11 months before the start of the timetable period. Applicants for rail capacity are required to participate in the coordination negotiations, which aim at attaining a timetable structure that is sensible for society as a whole.

Decisions on the allocation of capacity for regular services may be changed for the rest of the timetable period during the timetable period concerned at specified dates, provided that these changes do not affect the capacity allocated to other Railway Undertakings or to international traffic within the European Economic Area. The change dates take place the beginning of the timetable period on the night between Saturday and Sunday at 00:00 hours and on the second weekend after the end of the school year on the night between Sunday and Monday at 00:00, i.e. between weeks 24 and 25. In addition to the above dates, the Finnish Transport Agency may for special reasons decide on other dates on which changes can take place. The preliminary dates on which changes can take place during the timetable period 2017 are the following:

11.12.2016  
26.3.2017  
19.6.2017  
14.8.2017 (at present the established change is at the beginning of week 33)  
29.10.2017




Figure 7. *Dates on which the capacity for regular services may be changed during the timetable period 2017.*

The Finnish Transport Agency shall inform all Railway Undertakings of the new dates on which the capacity for regular services may be changed. The decision on the dates for applying changes will also be published on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>75</sup>.

#### **4.3.2 Requesting Rail Capacity for Temporary Traffic**

Information about requesting ad hoc capacity can be found in the instruction for requesting rail capacity.

## **4.4 Allocation Process**

### **4.4.1 Coordination Process**

Based on the applications, the Finnish Transport Agency's Traffic Services Department draws up the rail capacity allocation proposal (called "draft working timetable" in the Railway Act) for the next timetable period no later than four months after the deadline for the submission of requests for capacity. It has, however, been agreed by European railway Infrastructure Managers that no more than 2.5 months shall be used for the coordination of requests.

The rail capacity allocation proposal is primarily based on the assumption that the requested rail capacity will be allocated, provided that the different train paths enable railway traffic to be operated in accordance with the technical and safety requirements. In order to improve the use of rail capacity, the Finnish Transport Agency may, however, offer applicant's capacity that does not essentially differ from the capacity they have requested. The Finnish Transport Agency may also decide not to allocate capacity, provided that reserve capacity is needed for the timetable period as a result of the priority order applied to railway traffic.

The Finnish Transport Agency sends the rail capacity allocation proposal to applicants for information within the prescribed period of time. Customers purchasing freight transport services and associations representing purchasers of rail transport services also have the right to present comments on the capacity allocation proposal within 30 days, counted from the date on which the Finnish Transport Agency publishes an announcement on its website that the capacity allocation proposal has been prepared. In addition to the allocation suggestions, there is more detailed information about the comment procedure.

Based on the rail capacity allocation proposal and the comments presented by the parties involved, the Finnish Transport Agency shall decide on the allocation of rail capacity on a fair and non-discriminatory basis. In deciding, the Finnish Transport Agency shall pay particular attention to the needs of passenger and freight traffic and infrastructure management, as well as to efficient use of the railway network. The priority order determined for specialised and congested infrastructure shall also be taken into account, unless otherwise provided in this chapter.

---

<sup>75</sup> <http://www.liikennevirasto.fi/ammattiliikenne-raiteilla/liikennesuunnittelu/saannollisen-liikenteen-muutokset>

More information about requesting, allocating and cancelling rail capacity can be found in the instruction for requesting rail capacity.

#### **4.4.2 Dispute Resolution**

Railway Undertakings may appeal against a capacity allocation decision by the Finnish Transport Agency by filing a claim for rectification with the Finnish Transport Safety Agency's Regulatory Body. For further information, see 1.4.3.

#### **4.4.3 Congested Infrastructure Capacity**

If the coordination of capacity requests does not lead to a satisfactory result, despite negotiations and compromises (see instruction for requesting rail capacity), the Finnish Transport Agency will declare that element of infrastructure to be congested. This must also be done for infrastructure which can be predicted to suffer from insufficient capacity in the near future. When infrastructure capacity has been declared to be congested, the Finnish Transport Agency will carry out a capacity analysis which includes consultation of the infrastructure users. Traffic management, timetable structures, speed alterations and potential infrastructure improvements will be taken into account when making the analysis. The Finnish Transport Agency will compile a capacity enhancement plan within six months of the completion of the capacity analysis.

#### **Priority order in Finland**

The Finnish Transport Agency declares an element of infrastructure capacity or a part of it to be congested infrastructure capacity if the coordination of several requests for the same infrastructure capacity has not led to a satisfactory result. The Finnish Transport Agency may also designate an element of infrastructure capacity as congested if it is evident that it will become congested during the timetable period.

If there are several applications for the same infrastructure capacity, the priority order is as presented in Table 1. Application of this priority order is based on the assumption that each train can be defined during its whole journey by one of the terms listed in the table. The term by which the train is defined may change during the journey of the train.

If there is a need to prioritise trains within a particular priority group in the table, priority will be given, on the basis of the length of the journey and the number of operating days, especially in freight traffic. In this way higher priority is given to a longer and more regular transport need.

*Table 1. Priority order on congested infrastructure capacity.*

Priority	Traffic
1.	Synergic traffic entity <sup>76</sup>
2.a	Express train traffic <sup>77</sup>
2.b	Transport for the processing industry <sup>78</sup>
3.a	Local and other passenger traffic
3.b	Other regular freight traffic (including international traffic)
4.	Freight traffic not requiring strict transport times
5.	Other traffic <sup>79</sup>

### **Derogation from the priority order laid down in the Network Statement**

The Finnish Transport Agency may by a separate decision make derogation from the general priority order laid down in the Railway Act and the Network Statement in favour of an applicant operating international traffic or such traffic as otherwise maintains or improves the functioning of the rail transport system or public transport. The same applies to cases where the rejection of the application would cause unreasonable damage to applicants or to the business activities of their customers.

#### **4.4.4 Allocating Marshalling Yard Capacity**

The Finnish Transport Agency uses railway network access agreements and, if necessary, the enclosed marshalling yard agreement to allocate marshalling yard capacity between railway operators. The railway operators shall report and specify their marshalling yard access needs when entering the access agreement.

Access to tracks in freight yards situated within traffic operating points is separately agreed upon in the railway network access agreement and, if necessary, in the enclosed marshalling yard agreement. The main order of priority for the traffic at the traffic operating point is the following:

1. Train traffic (passenger and freight traffic, including border traffic and track work units using the line)
2. Shunting operations between traffic operating points

<sup>76</sup> The term "synergic passenger traffic entity" refers in passenger traffic to the whole of trains which form a transport system producing clear added value for customers. Such a system could be, for example, the Basic Interval Timetable, officially approved by the FTA's Railway Network Usage Unit in advance.

<sup>77</sup> The term "express train traffic" refers to traffic which in some respect does not belong within the scope of the synergy-producing traffic system. International passenger traffic may belong in this category.

<sup>78</sup> The term "transport for the processing industry" mainly refers to transport whose immediate place of destination or origin is a port or a private siding. This transport is essentially connected with total logistics management. This group includes, in particular, combined transport, transport for the wood-processing industry and transport to ports.

<sup>79</sup> Other traffic refers to e.g. traffic in connection with track work, museum traffic or shunting operations on the line sections.

3. Traffic between the parts of the traffic operating point due to shunting operations
4. Waggon sorting operations (formation/splitting-up of trains)
5. Moving of rolling stock to storage siding

Railway Undertakings shall contact the Infrastructure Manager about their needs for storage of rolling stock that have arisen during the timetable period. The Infrastructure Manager's Rail Management Centre decides on the rail capacity of marshalling yards and gives an operative solution to track usage in demanding situations, including urgent, short-term storage needs. The Infrastructure Manager's Railway Network Usage Unit approves storage requests exceeding one week.

If the tracks of marshalling yards are needed for, for example, vintage trains or track construction and maintenance machines, during the daily train services, the Railway Undertakings shall give access to the tracks in accordance with the Infrastructure Manager's instructions. Railway Undertakings shall also ensure that the winter maintenance of tracks can be performed and, for example, move rolling stock as required.

Operations on the marshalling yard may not intentionally obstruct the operations of another party. Rolling stock may not be unnecessarily stored at turnouts or single cross-overs (for example during breaks). It must be possible to operate between the parts of the marshalling yards at all times.

#### **4.4.5 Impact of the Framework Agreements**

At present, the Finnish Transport Agency does not enter into framework agreements. Framework agreements help to define the rights and obligations of the applicant and the Finnish Transport Agency for a period of time exceeding that of one timetable period. Framework agreements must not, however, hinder other applicants from using the infrastructure in question and do not bind the Finnish Transport Agency to grant the capacity defined in the agreement to the Railway Undertaking in question.

## **4.5 Allocation of Capacity for Maintenance, Renewal and Enhancements**

The railway network may also be used for transferring track machines from depots to worksites, between worksites, and for maintenance purposes. Certain tracks are mainly used for infrastructure management purposes. Under the Railway Act, a safety certificate granted by the Finnish Transport Safety Agency is required for traffic operation, if it is a train movement or shunting movement, outside the area reserved for infrastructure management. The safety certificate is granted upon application for a maximum of five years at a time. The requirements for obtaining a safety certificate are that the traffic operator engaged in infrastructure management has sufficient liability insurance and an adequate risk management system, its stock has been approved by the Finnish Transport Safety Agency and that the persons conducting the traffic operations are competent to do so.

Requests for the rail capacity required to operate traffic must be submitted in the LIIKE system. The [TURO publication<sup>80</sup>](#) contains detailed instructions on the infrastructure management machinery used on the track as well as on the persons and undertakings charged with traffic safety duties.

The party performing the work must have been allocated rail capacity, granted permission for track works, and if necessary, a voltage cut-off prior to starting the work during the allocated track possessions.

### **Track Work**

At the time of publication, Table 1 in Appendix 13 contains the best estimate of the track works during timetable period 2017, which will impact operations and, consequently, the rail capacity needs for railway infrastructure management. The schedule, timing of tasks, and track possessions required for the work will change as the funding and plans are specified and thus the Finnish Transport Agency is not bound by Table 1 Appendix 13. Once the Network Statement is published, the Finnish Transport Agency will maintain up-to-date information on the working programme for the upcoming timetable period on its website <http://www.liikennevirasto.fi><sup>81</sup>, and regularly inform the rail capacity applicants about the programme.

The Finnish Transport Agency will decide separately on all track work and track possessions required for their completion. The decision will be made prior to the upcoming timetable period that is in December 2016 for the timetable period 2017.

Any required track possessions or changes to an earlier decision, arising after the decision has been made, can be discussed separately, if necessary. The basic rule is that track possessions requiring traffic arrangements are no longer arranged at this stage, but instead the work requested after the decision will be carried out according to (or in between) the traffic.

In addition to the aforementioned, the person or group applying for track possession must contact the Finnish Transport Agency's traffic planner separately for each request and agree on track possession and its details in accordance with the Finnish Transport Agency's track possession decision no later than two months before the work is scheduled to start.

More information about track work, the traffic arrangements as a result of these and compensation can be found in Appendix 13 (Track Work).

## **4.6 Non-Usage Rules**

The degree of previous capacity usage does not influence how capacity is allocated in the application process of the timetable period. The Finnish Transport Agency has the right to cancel all or part of the capacity allocated to an applicant for the rest of the valid timetable period, if the applicant has used less than the required threshold quota over a period of at least 30 days. Currently, in Finland, the threshold quota for

---

<sup>80</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/lo\\_2012-01\\_turo\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf)

<sup>81</sup> <http://www.liikennevirasto.fi/ratatyot>

the minimum use of capacity is 95 % for passenger trains and 50 % for freight trains. The threshold quotas refer to rail capacity for regular services, which are followed up on a monthly basis. If threshold quotas have not been reached, the Finnish Transport Agency will ask the capacity manager to explain the reasons for not having used the capacity. However, action will not be taken unless the train service has been cancelled more than three times in 30 days.

The Finnish Transport Agency may not, however, cancel the rail capacity if the failure to use it is due to non-economic reasons beyond the applicant or the railway operator's control. The Finnish Transport Agency always cancels the capacity for such a period during which the Railway Undertaking does not have a safety certificate for operating rail services.

## 4.7 Exceptional Transport and Dangerous Goods

For information on the transport of dangerous goods, see section 3.4.3, Dangerous Goods. Regulations concerning railway traffic and rolling stock are available on the Internet pages of the Finlex website at <http://www.finlex.fi><sup>82</sup> and other instructions on the Finnish Transport Safety Agency's website at <http://www.trafi.fi><sup>83</sup>.

At the moment all special permits are granted by the VR Transpoint.

## 4.8 Special Measures to be taken in the Event of Disturbance

### 4.8.1 Principles

The Finnish Transport Agency has the right to cancel the rail capacity completely or partially on a train path provisionally out of service due to a technical failure in the railway network, an accident or other incident.

In such case, the Finnish Transport Agency offers the operator alternative train paths, as far as possible. The Finnish Transport Agency is, however, not obliged to compensate for damage that may be caused to the operator, unless otherwise is agreed upon with the operator in conformity with the Railway Act.

Compensations due to disruptions are dealt with in chapter 6.4 (Performance Scheme).

---

<sup>82</sup> <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

<sup>83</sup> [http://www.trafi.fi/rautatiet/saadokset/kansalliset\\_maaraykset](http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset)



### **Disruption card**

The Finnish Transport Agency has collaborated with all parties operating in the railway network to prepare instruction cards for action to be taken in case of traffic disruptions, e.g. broken track, and to be followed where applicable under the supervision of the Rail Traffic Management Centre. Developing and updating the disruption cards is a continuous process.

#### **4.8.2 Operational Regulation**

The Finnish Transport Agency determines the rules on the management of disturbances between Railway Undertakings. Railway Undertakings have the right to present their own proposals for instructions how to handle disturbances affecting their own trains.

The Rail Traffic Management Centre of the Finnish Transport Agency resolves instances of disruption and provides guidelines on the correct action to take in such situations.

In its guidelines on railway accident preparedness (OVRO), the Finnish Transport Agency specifies the measures to be taken in case of an accident and how to prepare for accidents in advance. The guidelines can be found on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>84</sup>.

### ***Safety Issues***

Safety issues are dealt with in the access agreement and in Appendix 20.

#### **4.8.3 Foreseen Problems**

In cases of disruption the guidelines issued by the Finnish Transport Agency's Traffic Management Centre shall apply.

#### **4.8.4 Unforeseen Problems**

The Finnish Transport Agency and the railway operators shall be prepared for railway accidents in their fields of activity and follow the Finnish Transport Agency's guidelines (OVRO) on how to prepare for railway accidents.

Under the Rescue Act and the Railway Act, the Finnish Transport Agency is responsible for clearing and restoring the railway infrastructure in its possession. The railway operators shall be prepared to assist the Finnish Transport Agency with the clearance work regarding the railway operator's rolling stock and transported goods. Liability in cases of accident is determined in line with the Act on liability in rail traffic and the Tort Liability Act. According to article 54 in Directive 2012/34/EU of the European Parliament and of the Council, the Finnish Transport Agency may require Railway Undertakings to make available the clearing and rescue equipment and personnel that it feels are the most appropriate for restoring the situation to normal. The Finnish Transport Agency will pay for the use of equipment and resources when the costs incurred are deemed reasonable.

---

<sup>84</sup> [http://www2.liikennevirasto.fi/julkaisut/pdf3/lo\\_2011-16\\_ohje\\_varautumisesta\\_web.pdf](http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2011-16_ohje_varautumisesta_web.pdf)

The Finnish Transport Agency is prepared to quickly restore the track to an operable condition and then, within a reasonable time, to the condition it was in before the accident. The Finnish Transport Agency agrees thereupon when making the rail network maintenance agreements.

If any safety deficiencies affecting traffic are detected in the railway network, the Finnish Transport Agency may have to reduce the applicable axle load or speed limit.

The Ministry of Transport and Communications provides guidelines for and oversees the different rail sector operators' preparedness for accidents and exceptional circumstances.

## 5 Services

### 5.1 Introduction

The legal framework of capacity allocation is described in the Railway Act (304/2011)<sup>85</sup>. At the time of publication, the Railway Act and the provisions issued under it are awaiting government approval. Amendments to acts and statutes will be updated in the Finnish Railway Network, as soon as they come into effect.

Services concerning the usability of the railway network are described in Chapter 5 and Appendix 2 (Rail Traffic Operating Points) of the Network Statement. These services may be supplied by the Finnish Transport Agency or other parties.

The Finnish Transport Agency continues to develop the network services in 2016 and chapter 5 of the Network Statement will be expanded. The charges for services provided by the Finnish Transport Agency may also be changed. Information about changes updated on the Finnish Transport Agency's website <http://www.fta.fi><sup>86</sup>.

### 5.2 Services Offered by the Finnish Transport Agency

#### 5.2.1 Services in Return for the Infrastructure Charge

Finnish Transport Agency offers railway operators on the state-owned railway network the right against payment to utilise the train paths in accordance with the capacity granted to it by the Finnish Transport Agency, marshalling yards, storage sidings, loading tracks and other tracks and passenger platforms. The Finnish Transport Agency also offers train traffic control, passenger information and public address systems at the railway stations specified in the Network Statement (Appendix 14).

Use of rail capacity includes the traffic operator's right to use the Finnish Transport Agency's electricity supply network for tractive stock on the electrified line sections specified in the Network Statement.

#### Train Formation Yards

Train formation yards are marshalling yards in which the layout and size of the track system make it possible to form trains. The train formation yards are indicated by the marking "K" in column "Shunting" in Appendix 2.

---

<sup>85</sup> <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

<sup>86</sup> <http://www.liikennevirasto.fi/network-statement>

All train formation yard tracks have not been electrified. If necessary, the Finnish Transport Agency's division Infrastructure Management provides more information about the electrified tracks.

The use of train formation yards may become chargeable. All possible changes are updated on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>87</sup>.

A list of the contact persons of the marshalling yards is available on the Finnish Transport Agency's Extranet <http://www.liikennevirasto.fi><sup>88</sup>.

### **Storage Sidings**

Storage sidings are yard tracks primarily intended for the parking of wagons and coaches waiting for a transport task. Wagons can only be stored temporarily on these tracks. Storage sidings can also be used for other purposes required by traffic operating. Only railway operators and contractors are allowed to let wagons stand on the storage sidings. The Finnish Transport Agency determines which tracks are used as storage sidings. A list of the tracks, which can be used for temporary storage of rolling stock in exceptional situations, is available at the Finnish Transport Agency's unit Railway Network Usage.

If a railway operator's rolling stock has to be temporarily stored on a storage siding, this information shall immediately be forwarded to the Rail Traffic Management Centre. The Rail Traffic Management Centre is authorized to approve short-term, acute storage requests, while the Finnish Transport Agency's unit Railway Network Usage deals with storage requested for more than one week. Storage requests are also registered in the LIIKE system via the advance reports. Therefore the railway operator shall enter the information in the JETI system and make sure that the report is removed from the JETI system, as soon as the length of the required storage time has been determined.

When storing wagons loaded with dangerous goods, the railway operator is responsible for reporting the storage location of the wagons and the type of substances in them to the local fire and rescue authorities.

For long-term storage of rolling stock on marshalling yards: see section 2.3.3 Agreement on track access to the state-owned railway network for rolling stock storage.

### **Inclines and their use**

At the traffic operating points in Kouvola and Tampere the rail operators have access to inclines for the recomposing of train wagons. Train operators needing access to the incline shall contact the Finnish Transport Agency in good time (at least six weeks in advance) to reserve marshalling yard capacity and initiate the practical arrangements.

---

<sup>87</sup> <http://www.liikennevirasto.fi/network-statement>

<sup>88</sup> <http://www.liikennevirasto.fi/ratatiedon-extranet>

## **Traffic control**

The Finnish Transport Agency is responsible for traffic control in the state-owned railway network. More detailed information about traffic control at specific traffic operating points can be found on the Finnish Transport Agency's Extranet.

### **Rail Traffic Management Centre**

The Infrastructure Manager's Rail Traffic Management Centre monitors railway traffic throughout the day, resolves possible disruptions and reports the disruptions. The Rail Traffic Management Centre gives the required instructions to the railway operators and to traffic control, after having heard from all parties involved, if necessary. In conflict situations, the Rail Traffic Management Centre determines the order of train services and capacity usage taking the whole transport system situation into account. Moreover, the Rail Traffic Management Centre is responsible for cooperating with investigating authorities in high-risk and exceptional situations and for cooperating with police and rescue authorities. The Infrastructure Manager keeps the Ministry of Transport and Communications updated on separately specified situations, such as accidents.

The Rail Traffic Management Centre is the point of contact for the rail operators' production management when traffic control instructions or conflict resolution help is needed. The Rail Traffic Management Centre monitors the state of the railway infrastructure and traffic and intervenes when defects are detected.

### **5.2.2 Chargeable Services**

In addition to the basic services, the Infrastructure Manager may offer railway operators additional and auxiliary services which are not included in the basic infrastructure charge. The provision of these services is agreed upon in the access agreement. Possible amendments to the agreement after signing are separately agreed upon with the railway operator(s) and the agreement sections concerned are updated and enclosed in the access agreement in the form of appendices.

Possible other services are priced and laid down in the Act on Criteria for Charges Payable to the State and in the Decree of the Ministry of Transport and Communications on chargeable performances at the Finnish Transport Agency. Used services are invoiced each month, unless otherwise specified in the access agreement.

If several railway operators need to use the same service (for example marshalling yard guiding devices and systems), the principles for using the services are reviewed by a group led by the Infrastructure Manager.

Possible new chargeable services are invoiced from the time when the service was taken into use, unless otherwise agreed.

### **Traffic control service for shunting operations**

The traffic control service for shunting operations is a chargeable additional service. The service contents and price are explained in Appendix 15.

---

**Use of service equipment at Ilmala railway yard**

The Infrastructure Manager stores service equipment and other technical devices at the Helsinki depot in Ilmala. The use of this equipment is a chargeable additional service. More information can be obtained from the Infrastructure Manager's Railway Network Usage Unit.

**Other chargeable services provided by the Infrastructure Manager**

The Finnish Transport Agency can offer services on a commercial basis for the use of railway operators. The additional services could comprise, for example, the use of buildings and land areas owned by the Finnish Transport Agency.

Trial runs of rolling stock can be made at the Finnish Transport Agency's centre for trial runs in Laajakangas. This service is not included in the infrastructure charge.

The cost for electric power transmission in the state-owned railway network will be divided between all electricity consumers according to the amount consumed.

The use of services provided by the Finnish Transport Agency is agreed upon between the parties in the access agreement or in a separate lease agreement.

## 5.3 Services Offered by Others

### 5.3.1 Obligation to Provide Services

In accordance with the Railway Act [\(304/2011/34§\)](#)<sup>89</sup> Railway Undertakings, companies or other organisations providing rail services (service providers) are obliged to provide railway operators with the services and track access to service facilities referred to in Annex II(2) to Directive [2012/34/EU](#)<sup>90</sup> of the European Parliament and of the Council.

The availability of services shall be negotiated and an agreement shall be concluded with the service provider. The service provider has the right to charge a payment for its services. The payment shall be equitable for all Railway Undertakings and reasonable with respect to the costs incurred from providing the service.

Services supplied by others may include, for example:

- use of electrical supply equipment
- use of refuelling equipment
- use of passenger stations
- use of freight terminals
- use of train formation yards
- use of train formation equipment
- use of depot sidings

---

<sup>89</sup> <http://www.finlex.fi/fi/laki/alkup/2011/20110304>

<sup>90</sup> <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2012:343:0032:0077:EN:PDF>

- premises and equipment needed for the servicing and maintenance of rolling stock
- use of other technical devices (e.g. sand distributors, water and electrical connections for rolling stock, radiation measurement devices, tank wagon filling gauges, wagon scales, and brake testing equipment), and
- training services for those involved in traffic safety tasks

### **5.3.2 Power Supply on Electrified Railway Lines**

Use of rail capacity includes the traffic operator's right to use of the Finnish Transport Agency's electricity power supply network for tractive stock on the electrified line sections specified in the Network Statement. The Finnish Transport Agency does not, however, provide electricity, but the traffic operator shall enter into an agreement with a service provider.

The 400 and 1,500 V power supply facilities for rolling stock are indicated in Appendix 2. Also for the 400 V power supply, the maximum current available is indicated in amperes.

### **5.3.3 Maintenance and Service Facilities**

The use of maintenance and service facilities requires an agreement with their provider.

### **5.3.4 Refuelling Facilities**

The Finnish Transport Agency does not own refuelling equipment or provide refuelling services. The Appendix 2 shows the refuelling facilities on traffic operating points. The use of refuelling facilities requires an agreement with their owner.

### **5.3.5 Technical Equipment**

The use of other technical equipment (e.g. scales, cranes, etc.) must be agreed with their respective owners. The Finnish Transport Agency does not provide railway operators with access to this equipment. Appendix 2 shows the cranes located at traffic operating points.

## 6 Charges

### 6.1 Charging Principles and Services Included in the Infrastructure Charge

The legal framework of the basic infrastructure charge is described in the Railway Act (304/2011)<sup>91</sup>, the Railway Infrastructure Tax (605/2003)<sup>92</sup> and the Ministry of Transport and Communications Decree on the basic infrastructure charge (1084/2009)<sup>93</sup>.

The basic infrastructure charge covers the minimum access package (the minimum access package is described under 5.2.), including track access to service facilities on the state-owned railway network.

### 6.2 Charging System

The infrastructure charge comprises the basic infrastructure charge, track tax and the investment tax levied for the railway line section Kerava–Lahti. The basic infrastructure charge is levied for railway traffic operations based on the Finnish Transport Agency's immediate infrastructure management expenses. The track tax covers the environmental costs caused by train traffic and the fixed infrastructure expenditures of the infrastructure management. The investment tax for the line section Kerava–Lahti is levied over a period of 15 years to cover the investment costs for the railway line from the inauguration in autumn 2006 to August 2021.

The amended statutes in the First Railway Package will lead to changes in the charging system. The revised statutes will come into effect when the parliament has approved the new Railway Act as well as the decrees to be issued under the Act. The government has proposed that the new charging system include the basic infrastructure charge and related reductions and hikes, additional charges as well as charges levied on access services and additional and auxiliary services.

Track tax will not be levied for freight traffic in 2015–2017. The aim of this measure is to reduce the cost burden on the business sector, particularly where industry is concerned.

All changes in the charging system will be posted on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>94</sup>.

---

<sup>91</sup> <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

<sup>92</sup> <http://www.finlex.fi/fi/laki/ajantasa/2003/20030605>

<sup>93</sup> <http://www.finlex.fi/fi/laki/alkup/2009/20091084>

<sup>94</sup> <http://www.liikennevirasto.fi/network-statement>



## 6.3 Tariffs

The infrastructure charge consists of the charges mentioned in Table 2.

*Table 2. Infrastructure charge*

<b>Basic charge</b>	Freight traffic 0,1350 cent/ gross tonne-kilometre Passenger traffic 0,1308 cent/ gross tonne-kilometre
<b>Infrastructure tax</b>	Freight traffic - electric 0.05 cent/ gross tonne-kilometre - diesel 0.1 cent/ gross tonne-kilometre Passenger traffic 0.01 cent/ gross tonne-kilometre
<b>Investment tax (for line section Kerava-Lahti)</b>	Freight traffic 0.5 cent/ gross tonne-kilometre Passenger traffic 0.5 cent/ gross tonne-kilometre

## 6.4 Performance Scheme

In order to promote the effective use of the railway network and improve the timeliness of rail services and to minimise operational disruptions to the railway network caused by railway traffic and track maintenance, railway operators and the Finnish Transport Agency are encouraged to limit disruptions arising from their activities and increase the effective use of the railway network by means of performance incentive schemes.

A railway operator shall compensate the Finnish Transport Agency if the operation of the railway operator essentially differs from the rail capacity allocated to it for a reason due to the operator, and such a deviation impedes the functioning of the rail system. The Finnish Transport Agency shall compensate a railway operator if, for reasons due to the Finnish Transport Agency, the availability of the railway network essentially differs from the rail capacity allocated to the operator, and such a deviation impedes the functioning of the rail system.

The performance system only applies to train traffic, not to traffic in relation to shunting operations.

## 6.5 Changes to Charges

Infrastructure charge system is about to change. The principles of the valid infrastructure charge system and the amount of infrastructure charge are published on the Finnish Transport Agency website.

## 6.6 Billing Arrangements

The Finnish Transport Agency invoices the infrastructure charge each calendar month based on the realised performances of the previous month.

When this Network Statement is published the infrastructure charge is levied as follows: For invoicing, railway operators shall provide the Finnish Transport Agency contact person with information each month on the rail services operated by them. The reports shall be sent to the address [kirjaamo\(at\)liikennevirasto.fi](mailto:kirjaamo@liikennevirasto.fi) and for the attention of [tiina.taivainen\(at\)liikennevirasto.fi](mailto:tiina.taivainen@liikennevirasto.fi).

The Finnish Transport Agency aims at changing the practice, so that in the future the infrastructure charge is levied based on information obtained from the Finnish Transport Agency's LIIKE system. The railway operators will be given written notice about this reform. In addition, there will be information about the new practice on the Finnish Transport Agency's website <http://www.liikennevirasto.fi><sup>95</sup>.

The Finnish Transport Agency does not require any guarantee for the payment of the infrastructure charge. The infrastructure charge and other charges connected with it are, however, subject to distraint without sentence or decision.

---

<sup>95</sup> [http://portal.liikennevirasto.fi/sivu/www/e/professionals/network\\_statement](http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement)

## Basic Information on Railway Sections

### Markings:

On	"yes"
—	"no"
AC2	electrification voltage 25 kV / 50 Hz
ATP	Automatic train protection

### Chart columns:

**Traffic operating points** (Node of the network) indicates all traffic operating points where the route of the train can be changed.

**Length of line** is the distance between traffic operating points (Nodes of the network).

**Max gradient** is the maximum gradient measured in a distance of 1,200 m.

**Electrification system** indicates that the section of line is electrified.

**Section blocking or radio-controlled section** indicates that on the section of line there is an automatic safety device system in use in order to protect the railway traffic.

**ATP** indicates that the section of line is equipped with pan-European safety device system and GSM-R radio network.

**ERTMS** indicates that the section of line is equipped with pan-European safety device system and GSM-R radio network.

**ATP coding for tilting trains** indicates the sections on which ATP allows higher speeds for tilting trains.

**Radio system** indicates that the digital (GSM-R) communication equipment is in use between the driver and traffic control in mention traffic operating points.

Liikennepaikka (verkon solmupiste)	Liikennepaikka (verkon solmupiste)	Radan pituus	Määrävä kaltevuus	Sähköistys-järjestelmä	Suojastettu tai radio-ohjattu osuus	Junan kulunvalvontajärjestelmä	ERTMS	Kallistuvakoristen junien JKV-koodaus	Radiojärjestelmä
Trafikplats (bannätets knutpunkt)	Trafikplats (bannätets knutpunkt)	Banans längd	Största lutningen	Elektrifierings-systemet	Linje-blockerad eller radiostvrd sträcka	Automatisk tågkontrol		ATC-kodning av lutande tåg	Radio system
Traffic operating point (Node of the network)	Traffic operating point (Node of the network)	Length of line	Max gradient	Electrification system	Section blocking or radio controlled section	ATP		ATP-coding for tilting trains	
Helsinki asema	Havukoski	18	10,0	AC2	On	ATP	—	On	GSM-R
Havukoski	Kerava asema	11	7,0	AC2	On	ATP	—	On	GSM-R
Kerava asema	Hyvinkää	29	7,5	AC2	On	ATP	—	On	GSM-R
Hyvinkää	Riihimäki asema	12	7,5	AC2	On	ATP	—	On	GSM-R
Kerava asema	Vuosaari	19	10,0	AC2	On	ATP	—	—	GSM-R
Kerava asema	Sköldvik	27	10,0	AC2	On	ATP	—	—	GSM-R
Kerava asema	Hakosilta	65	10,0	AC2	On	ATP	—	On	GSM-R
Hyvinkää	Karjaa	99	10,5	—	On	ATP	—	—	GSM-R
Helsinki asema	Huopalahti	6	10,0	AC2	On	ATP	—	—	GSM-R
Huopalahti	Havukoski	27	40,0	AC2	On	ATP	—	—	GSM-R
Huopalahti	Kirkkonummi	31	10,5	AC2	On	ATP	—	—	GSM-R
Kirkkonummi	Karjaa	49	12,0	AC2	On	ATP	—	On	GSM-R
Karjaa	Hanko asema	50	10,5	—	On	ATP	—	—	GSM-R
Karjaa	Turku asema	107	12,7	AC2	On	ATP	—	On	GSM-R
Turku asema	Turku satama	3	7,0	AC2	On	ATP	—	—	GSM-R
Riihimäki asema	Toijala	76	10,0	AC2	On	ATP	—	On	GSM-R
Toijala	Turku asema	128	10,5	AC2	On	ATP	—	On	GSM-R
Toijala	Tampere asema	40	10,0	AC2	On	ATP	—	On	GSM-R
Toijala	Valkeakoski	18	8,0	—	—	—	—	—	GSM-R
Turku asema	Raisio	8	7,0	—	On	ATP	—	—	GSM-R
Raisio	Naantali	6	9,0	—	—	—	—	—	GSM-R
Raisio	Uusikaupunki	57	9,0	—	On	ATP	—	—	GSM-R
Uusikaupunki	Hangonsaari	3	11,5	—	—	—	—	—	GSM-R
Tampere asema	Lielähti	6	9,0	AC2	On	ATP	—	On	GSM-R
Lielähti	Kokemäki	91	12,5	AC2	On	ATP	—	On	GSM-R
Kokemäki	Rauma	47	9,0	AC2	On	ATP	—	—	GSM-R
Kokemäki	Pori	38	9,5	AC2	On	ATP	—	—	GSM-R
Pori	Mäntyluoto	21	5,5	—	On	ATP	—	—	GSM-R
Pori	Aittaluoto	6	10,0	—	—	—	—	—	GSM-R
Mäntyluoto	Tahkoluoto	11	5,5	—	On	ATP	—	—	GSM-R
Lielähti	Parkano	69	10,5	AC2	On	ATP	—	On	GSM-R
Niinisalo	Parkano	42	10,0	—	—	—	—	—	—
Parkano	Seinäjoen asema	84	10,0	AC2	On	ATP	—	On	GSM-R
Riihimäki asema	Hakosilta	48	8,0	AC2	On	ATP	—	—	GSM-R
Hakosilta	Lahti	11	10,0	AC2	On	ATP	—	On	GSM-R
Lahti	Loviisan satama	77	12,0	—	—	—	—	—	—
Lahti	Heinola	38	12,0	—	—	—	—	—	—
Lahti	Mukkula	7	15,0	—	—	—	—	—	GSM-R
Lahti	Kouvola asema	61	10,0	AC2	On	ATP	—	—	GSM-R
Kouvola asema	Luumäki	59	10,0	AC2	On	ATP	—	—	GSM-R
Kouvola asema	Juurikorpi	33	10,0	AC2	On	ATP	—	—	GSM-R
Juurikorpi	Kotka asema	18	8,5	AC2	On	ATP	—	—	GSM-R
Kotka asema	Kotkan satama	1	0,0	AC2	On	ATP	—	—	GSM-R
Kotka Hovinsaari	Kotka Mussalo	5	6,0	AC2	—	ATP	—	—	GSM-R
Juurikorpi	Hamina	19	10,0	AC2	On	ATP	—	—	GSM-R
Kouvola asema	Kuusankoski	10	9,0	AC2	—	—	—	—	GSM-R
Kouvola asema	Mynttilä	86	12,0	AC2	On	ATP	—	On	GSM-R
Mynttilä	Ristiina	21	12,5	—	—	—	—	—	—

Liikennepaikka (verkon solmupiste)	Liikennepaikka (verkon solmupiste)	Radan pituus	Määräva kaltevuus	Sähköistys- järjestelmä	Suojastettu tai radio- ohjattu osuus	Junan kulunvalvontajärjestelmä	ERTMS	Kallistuvakoristen junien JKV-koodaus ATC-kodning av lutande tåg	Radiojärjestelmä
Trafikplats (bannätets knutpunkt)	Trafikplats (bannätets knutpunkt)	Banans längd	Största lutningen	Elektrifierings- systemet	Linje-blockerad eller radiostvrd sträcka	Automatisk tågkontrol			
Traffic operating point (Node of the network)	Traffic operating point (Node of the network)	Length of line	Max gradient	Electrification system	Section blocking or radio controlled section	ATP			
Mynttilä	Pieksämäki asema	105	11,0	AC2	On	ATP	—	On	GSM-R
Luumäki	Vainikkala asema	33	8,0	AC2	On	ATP	—	—	GSM-R
Luumäki	Lappeenranta	27	9,5	AC2	On	ATP	—	—	GSM-R
Lappeenranta	Mustolan satama	18	10,0	—	—	—	—	—	GSM-R
Lappeenranta	Imatra tavara	39	9,0	AC2	On	ATP	—	On	GSM-R
Imatra tavara	Imatrankoski-raja	10	11,0	—	—	—	—	—	GSM-R
Imatra tavara	Parikkala	60	10,0	AC2	On	ATP	—	On	GSM-R
Pieksämäki asema	Huutokoski	31	11,0	—	On	ATP	—	—	GSM-R
Huutokoski	Savonlinna	75	12,0	—	On	ATP	—	—	—
Savonlinna	Parikkala	59	12,0	—	On	ATP	—	—	GSM-R
Parikkala	Säkäniemi	93	10,0	AC2	On	ATP	—	—	GSM-R
Niirala-raja	Säkäniemi	33	10,5	—	On	ATP	—	—	GSM-R
Säkäniemi	Joensuu asema	37	10,5	AC2	On	ATP	—	—	GSM-R
Joensuu asema	Ilomantsi	71	12,0	—	—	—	—	—	—
Joensuu asema	Viinijärvi	32	9,0	—	On	ATP	—	—	GSM-R
Huutokoski	Varkaus	18	10,0	—	On	ATP	—	—	GSM-R
Varkaus	Kommila	6	10,0	—	—	—	—	—	GSM-R
Varkaus	Viinijärvi	101	11,0	—	On	ATP	—	—	GSM-R
Joensuu asema	Uimaharju	50	17,6	—	On	ATP	—	—	GSM-R
Uimaharju	Liekka	54	11,5	—	On	ATP	—	—	GSM-R
Liekka	Pankakoski	6	10,0	—	—	—	—	—	GSM-R
Liekka	Nurmes	56	12,5	—	On	ATP	—	—	GSM-R
Nurmes	Vuokatti	85	11,5	—	—	—	—	—	—
Vuokatti	Lahnaslampi	12	10,0	—	—	—	—	—	—
Vuokatti	Kontiomäki	24	10,5	—	—	—	—	—	GSM-R
Pieksämäki asema	Suonenjoki	38	9,0	AC2	On	ATP	—	—	GSM-R
Suonenjoki	Yläkoski	3	10,0	—	—	—	—	—	—
Suonenjoki	Siilinjärvi	76	12,0	AC2	On	ATP	—	—	GSM-R
Siilinjärvi	Sysmäjärvi	99	10,5	—	On	ATP	—	—	GSM-R
Siilinjärvi	Iisalmi	60	12,0	AC2	On	ATP	—	—	GSM-R
Iisalmi	Murtomäki	62	12,7	AC2	On	ATP	—	On	GSM-R
Murtomäki	Otanmäki	25	11,0	—	—	—	—	—	—
Murtomäki	Kajaani	20	12,0	AC2	On	ATP	—	On	GSM-R
Kontiomäki	Vartius	95	11,0	AC2	On	ATP	—	—	GSM-R
Vartius	Vartius-raja	2	10,0	AC2	On	ATP	—	—	GSM-R
Kontiomäki	Ämmänsaari	92	12,0	—	—	—	—	—	—
Tampere asema	Orivesi	40	12,0	AC2	On	ATP	—	On	GSM-R
Orivesi	Vilppula	47	12,5	—	On	ATP	—	—	GSM-R
Vilppula	Mänttä	8	5,0	—	—	—	—	—	GSM-R
Vilppula	Haapamäki	26	12,5	—	On	ATP	—	—	GSM-R
Haapamäki	Seinäjäki asema	118	12,0	—	On	ATP	—	—	GSM-R
Haapamäki	Jyväskylä	77	12,0	—	On	ATP	—	—	GSM-R
Orivesi	Jämsä	56	12,5	AC2	On	ATP	—	On	GSM-R
Jämsä	Kaipola	7	12,0	—	—	—	—	—	GSM-R
Jämsä	Jämsänkoski	4	10,0	AC2	On	ATP	—	On	GSM-R
Jämsänkoski	Jyväskylä	52	10,5	AC2	On	ATP	—	—	GSM-R
Jyväskylä	Äänekoski	47	10,5	—	On	ATP	—	—	GSM-R
Äänekoski	Haapajärvi	164	10,5	—	—	—	—	—	—

Liikennepaikka (verkon solmupiste)	Liikennepaikka (verkon solmupiste)	Radan pituus	Määrävä kaltevuus	Sähköistys-järjestelmä	Suojastettu tai radio-ohjattu osuus	Junan kulunvalvontajärjestelmä	ERTMS	Kallistuvakoristen junien JKV-koodaus ATC-kodning av lutande tåg	Radiojärjestelmä Radio system
Trafikplats (bannätets knutpunkt)	Trafikplats (bannätets knutpunkt)	Banans längd	Största lutningen	Elektrifierings-systemet	Linje-blockerad eller radiostvrd sträcka	Automatisk tågkontrol			
Traffic operating point (Node of the network)	Traffic operating point (Node of the network)	Length of line	Max gradient	Electrification system	Section blocking or radio controlled section	ATP		ATP-coding for tilting trains	
Jyväskylä	Pieksämäki asema	80	12,5	AC2	On	ATP	—	On	GSM-R
Seinäjoen asema	Kaskinen	112	10,0	—	On	ATP	—	—	GSM-R
Seinäjoen asema	Vaasa	75	12,0	AC2	On	ATP	—	—	GSM-R
Vaasa	Vaskiluoto	5	1,0	—	—	—	—	—	GSM-R
Iisalmi	Pyhäkumpu erkanemisvaihde	63	10,0	—	On	ATP	—	—	GSM-R
Pyhäkumpu erkanemisvaihde	Pyhäkumpu	3	3,0	—	—	—	—	—	GSM-R
Pyhäkumpu erkanemisvaihde	Haapajärvi	36	9,5	—	On	ATP	—	—	GSM-R
Haapajärvi	Ylivieska	55	8,0	—	On	ATP	—	—	GSM-R
Seinäjoen asema	Pännäinen	101	10,0	AC2	On	ATP	—	On	GSM-R
Pännäinen	Pietarsaari	10	6,0	AC2	—	—	—	—	GSM-R
Pietarsaari	Alholm	4	3,0	AC2	—	—	—	—	GSM-R
Pännäinen	Kokkola	33	7,0	AC2	On	ATP	—	On	GSM-R
Kokkola	Ykspihlaja	5	10,0	AC2	—	—	—	—	GSM-R
Kokkola	Ylivieska	79	10,0	AC2	On	ATP	—	On	GSM-R
Ylivieska	Tuomioja	68	10,0	AC2	On	ATP	—	On	GSM-R
Tuomioja	Raah	28	10,0	AC2	On	ATP	—	—	GSM-R
Raah	Rautaruukki	9	10,0	AC2	—	—	—	—	GSM-R
Tuomioja	Oulu asema	54	10,0	AC2	On	ATP	—	On	GSM-R
Oulu asema	Kontiomäki	166	10,0	AC2	On	ATP	—	—	GSM-R
Oulu asema	Kemi	105	10,0	AC2	On	ATP	—	—	GSM-R
Kemi	Ajos	9	10,0	—	—	—	—	—	GSM-R
Kemi	Laurila	7	10,0	AC2	On	ATP	—	—	GSM-R
Laurila	Tornio asema	19	7,5	—	On	ATP	—	—	GSM-R
Laurila	Rovaniemi	106	10,0	AC2	On	ATP	—	—	GSM-R
Rovaniemi	Kemijärvi	85	12,0	AC2	On	ATP	—	—	GSM-R
Kemijärvi	Patokangas	9	12,0	AC2	On	ATP	—	—	—
Tornio asema	Tornio-raja	3	4,0	—	On	ATP	—	—	GSM-R
Tornio asema	Röyttä	8	8,0	—	—	—	—	—	GSM-R
Tornio asema	Kolari	183	10,5	—	On	ATP	—	—	GSM-R
Sysmäjärvi	Vuonos	7	10,0	—	—	—	—	—	GSM-R
Viinijärvi	Sysmäjärvi	13	7,5	—	On	ATP	—	—	GSM-R
Murtomäki	Talvivaara	24	12,5	AC2	On	ATP	—	—	GSM-R
Kajaani	Lamminniemi	3	10,0	—	—	—	—	—	GSM-R
Kajaani	Kontiomäki	26	12,0	AC2	On	ATP	—	—	GSM-R

## Rail Traffic Operating Points

### Legend:

( ) in columns regarding platforms	platform not maintained by the Finnish Transport Agency
K	yes
Y	private
K in columns regarding traffic control	remote control
M in columns regarding traffic control	manual

### Chart columns:

**Name** refers the official name of the station and is used in traffic safety work.

**Another name** is the name of a traffic operating point in Finland's second official language. Another name is usually a Swedish name and only in Sköldvik is the Finnish name Kilpilahti used as another name, contrary to what the present language situation in the municipality would imply.

**Abbreviation** indicates the abbreviation used of the official name of the station.

**Commercial name** is mentioned in those cases where it differs from the official name of the stations, used in traffic safety work.

**Km Hki** describes the distance of a traffic operating point to the old station hall of Helsinki (already torn down), measured by a track kilometre system. According to the system, the location of all elements on tracks is fixed to landmarks.

**Municipality** refers to the municipality in which the traffic operating point is located.

**Traffic control** describes whether the traffic operating point has the technical equipment to control the train traffic manually or remote. It does not mean that traffic control services are regularly provided.

**Private sidings** indicates that the traffic operating point has at least one connection to a siding, owned or managed by a private owner (includes everyone except the Finnish Transport Agency).

**Shunting** indicates that the form of the tracks at a traffic operating point is such that it is possible to move at least a locomotive to the other end of a line of rolling stock without having to go through the main line of the traffic operating point.

**Minimum and maximum platform length** indicates the minimum and maximum length of platforms used by passenger trains at the traffic operating point. A passenger train should not be longer than the platform at which it stops. If the platform length is in brackets ( ), the platform is not maintained by the Finnish Transport Agency and services are operated at the responsibility of the railway undertaking.

**Platform height** indicates the nominal height of platforms used by passenger trains, calculated from the surface of the rail.

**Design train length** indicates the longest track of a traffic operating point, other than the main line going through it. The length is measured in such a way that it is usable in both directions.

**Power supply** indicates at which traffic operating point it is possible to get 400 V or 1500 V electric current mainly for rolling stock or track machinery power supply purposes.

**Side loading platform** indicates at which traffic operating point it is possible to load freight cars from the side, and shows the maximum platform length at the traffic operating point.

**End loading platform** indicates at which traffic operating point it is possible load freight rolling stock from the end of the platform (combined transports).

**Loading site** indicates at which traffic operating point it is possible to load freight rolling stock at rail level. A typical example is loading of raw timber from a vehicle or an intermediate depot at a rail yard onto flatcars.

**Crane** indicates at which traffic operating point it is possible to use a crane to load wagons, and states the maximum capacity of the crane. This service is not provided by the Finnish Transport Agency.

**Fuel** indicates at which traffic operating point there is a fuel distribution point. This service is not provided by the Finnish Transport Agency.

**Passenger traffic** shows the operating points where passenger traffic can be operated.

**Freight transport** indicates the operating points where freight transport can be operated.

**Turntables** indicates the traffic operating points where turntables can be used. If turntable is privately owned it is marked with Y. If it is owned by Finnish Transport Agency, length of turntable is marked.

**Marshalling yards for dangerous goods** shows the traffic operating points where it is possible to handle wagons loaded with dangerous goods.



Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Ahonpää	Alholmen	Aho		Liikennepaikka	690+468	Seinäjoki-Oulu	Siikajoki	K		K
Ahvenus		Ahv		Liikennepaikka	270+960	Lielähti-Kokemäki	Kokemäki	K		
Ainola		Ain		Seisake	34+784	Helsinki-Riihimäki	Järvenpää			
Airaksela		Arl		Liikennepaikka	436+985	Pieksämäki-Kontiomäki	Kuopio	K	K	K
Aittaluoto		Atl		Liikennepaikka	328+220	Pori-Aittaluoto	Pori		K	K
Ajos		Ajo		Liikennepaikka	867+100	Kemi-Ajos	Kemi		K	K
Alapitkä		Apt		Liikennepaikka	505+840	Pieksämäki-Kontiomäki	Lapinlahti	K		K
Alavus		Alv		Liikennepaikka	373+445	Orivesi-Seinäjoki	Alavus	K		K
Alholma		Alh		Liikennepaikka	532+570	Pietarsaari-Alholma	Pietarsaari		K	K
Arola		Aro		Liikennepaikka	707+668	Kontiomäki-Vartius-rala	Hyrnsalmi	K		K
Asola		Aso		Liikennepaikka	31+596	Huopalahti-Havukoski	Vantaa	K		
Aviapolis		Avp		Seisake	25+135	Huopalahti-Havukoski	Vantaa			
Dragsvik		Dra		Liikennepaikka	171+180	Karjaa-Hanko	Rasepori	K		
Dynamiittivaihe		Dmv		Linjavaihe	199+185	Karjaa-Hanko	Hanko		K	K
Eläinpuisto-Zoo		Epz		Seisake	338+751	Orivesi-Seinäjoki	Ähtäri			
Eno		Eno		Liikennepaikka	660+170	Joensuu-Nurmes	Joensuu	K		K
Ervelä		Erv		Liikennepaikka	119+816	Helsinki-Turku satama	Salo	K		
Eskola		Ela		Liikennepaikka	603+762	Seinäjoki-Oulu	Kannus	K		K
Espoo	Esbo	Epo		Liikennepaikka	20+600	Helsinki-Turku satama	Espoo	K		
Haapajärvi		Hpj		Liikennepaikka	649+205	Iisalmi-Ylivieska, Äänekoski-Haapajärvi	Haapajärvi	K		K
Haapakoski		Hps		Liikennepaikka	393+454	Pieksämäki-Kontiomäki	Pieksämäki	K		K
Haapamäen kyllästämö		Hmk		Linjavaihe	304+940	Orivesi-Seinäjoki	Keuruu		K	
Haapamäki		Hpk		Liikennepaikka	300+235	Haapamäki-Jyväskylä, Orivesi-Seinäjoki	Keuruu	K	K	K
Haarajoki		Haa		Liikennepaikka	39+567	Kerava-Hakosilta	Järvenpää	K		
Hakosilta		Hlt		Liikennepaikka	119+540	Kerava-Hakosilta, Riihimäki-Kouvola	Hollola	K		
Haksi		Hsi		Seisake	56+737	Olli-Porvoo	Porvoo			
Hamina		Hma		Liikennepaikka	243+646	Juurikorpi-Hamina	Hamina	M	K	K
Hammasslahti		Hsl		Liikennepaikka	602+199	Kouvola-Joensuu	Joensuu	K		K
Hanala	Hanaböle	Hna		Liikennepaikka	21+394	Helsinki-Riihimäki	Vantaa	K		
Hangonsaari		Hgs		Liikennepaikka	269+655	Uusikaupunki-Hangonsaari	Uusikaupunki		K	K
Hanhikoski		Hnh		Linjavaihe	1047+083	Laurila-Kemijärvi	Kemijärvi			K
Hankasalmi		Hks		Liikennepaikka	418+089	Jyväskylä-Pieksämäki	Hankasalmi	K	K	K
<b>HANKO</b>		<b>Han</b>		<b>Ostin jaettu liikennepaikka</b>	<b>–</b>	<b>Karjaa-Hanko</b>		<b>K</b>		
Hanko asema	Hangö	Hnk	Hanko	Liikennepaikan osa (Hanko)	207+119		Hanko		K	K
Hanko tavara		Hnkt		Liikennepaikan osa (Hanko)	206+350		Hanko			K
Hanko-Pohjoinen	Hangö Norra	Hkp		Liikennepaikan osa (Hanko)	205+935		Hanko			
Harjavalta		Hva		Liikennepaikka	295+542	Kokemäki-Pori	Harjavalta	K	K	K
Harju		Hj		Liikennepaikka	201+643	Kouvola-Pieksämäki	Kouvola	K		K
Harviala		Hrv		Liikennepaikka	99+456	Riihimäki-Tampere	Janakkala	K		
Haukipudas		Hd		Liikennepaikka	775+159	Oulu-Laurila	Oulu	K		K
Haukivuori		Hau		Liikennepaikka	344+442	Kouvola-Pieksämäki	Mikkeli	K		K
<b>HAUSJÄRVI</b>		<b>Hjr</b>		<b>Ostin jaettu liikennepaikka</b>	<b>–</b>	<b>Riihimäki-Kouvola</b>		<b>K</b>		
Hausjärvi tavara		Has		Liikennepaikan osa (Hausjärvi)	86+210		Hausjärvi			K
Oitti		Oi		Liikennepaikan osa (Hausjärvi)	86+809		Hausjärvi			

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö- mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår- anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Haviseva		Hvs		Liikennepaikka	208+135	Tampere–Jyväskylä	Kangasala	K		
Heikkilä		Hek		Liikennepaikka	34+856	Helsinki–Turku satama	Kirkkonummi	K		
Heinola		Ha		Liikennepaikka	167+607	Lahti–Heinola	Heinola	M	K	K
Heinoo		Hno		Liikennepaikka	237+965	Lielähti–Kokemäki	Sastamala	K		
Heinävaara		Häv		Liikennepaikka	648+408	Joensuu–Ilomantsi	Joensuu			K
Heinävesi		Hnv		Liikennepaikka	468+135	Pieksämäki–Joensuu	Heinävesi	K		K
<b>HELSINKI</b>		<b>Hel</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Helsinki–Turku satama, Helsinki–Riihimäki</b>		<b>M</b>		
<i>Helsinki asema</i>	<i>Helsingfors</i>	<i>Hki</i>	<i>Helsinki päärautatieasema</i>	<i>Liikennepaikan osa (Helsinki)</i>	<i>0+159</i>		<i>Helsinki</i>			<i>K</i>
<i>Pasila asema</i>	<i>Böle</i>	<i>Psl</i>	<i>Pasila</i>	<i>Liikennepaikan osa (Helsinki)</i>	<i>3+230</i>		<i>Helsinki</i>			
<i>Pasila autojuna-asema</i>	<i>Böle biltågstation</i>	<i>Pau</i>		<i>Liikennepaikan osa (Helsinki)</i>	<i>4+319</i>		<i>Helsinki</i>			
<i>Ilmala asema</i>		<i>Ila</i>	<i>Ilmala</i>	<i>Liikennepaikan osa (Helsinki)</i>	<i>4+434</i>		<i>Helsinki</i>			
<i>Helsinki Kivihaka</i>	<i>Stenhagen</i>	<i>Khk</i>		<i>Liikennepaikan osa (Helsinki)</i>	<i>4+701</i>		<i>Helsinki</i>			
<i>Pasila tavara</i>		<i>Pslt</i>		<i>Liikennepaikan osa (Helsinki)</i>	<i>4+748</i>		<i>Helsinki</i>		<i>K</i>	<i>K</i>
<i>Ilmala ratapiha</i>		<i>Ilr</i>		<i>Liikennepaikan osa (Helsinki)</i>	<i>4+950</i>		<i>Helsinki</i>		<i>K</i>	<i>K</i>
<i>Käpylä</i>	<i>Kottby</i>	<i>Käp</i>		<i>Liikennepaikan osa (Helsinki)</i>	<i>5+840</i>		<i>Helsinki</i>			
<i>Oulunkylä</i>	<i>Äggelby</i>	<i>Ölk</i>		<i>Liikennepaikan osa (Helsinki)</i>	<i>7+399</i>		<i>Helsinki</i>		<i>K</i>	
Herrala		Hr		Seisake	115+790	Riihimäki–Kouvola	Hollola			
Hiirola		Hir		Liikennepaikka	318+957	Kouvola–Pieksämäki	Mikkeli	K		
Hikiä		Hk		Seisake	79+743	Riihimäki–Kouvola	Hausjärvi		K	
Hillosensalmi		Hls		Liikennepaikka	233+344	Kouvola–Pieksämäki	Kouvola	K		
Hinthaara	Hindhår	Hh		Seisake	52+150	Olli–Porvoo	Porvoo			
Hirvineva		Hvn		Liikennepaikka	715+500	Seinäjoki–Oulu	Liminka	K		K
Humppila		Hp		Liikennepaikka	188+778	Toijala–Turku	Humppila	K	K	K
Huopalahti	Hoplax	Hpl		Liikennepaikka	6+375	Helsinki–Turku satama, Huopalahti–Havukoski	Helsinki	K		
Huutokoski		Hko		Liikennepaikka	406+988	Pieksämäki–Joensuu, Huutokoski–Savonlinna	Joroinen	K	K	
Hyrnsalmi		Hys		Liikennepaikka	704+601	Kontiomäki–Ämmänsaari	Hyrnsalmi	M		K
Hyvinkää	Hyvinge	Hy		Liikennepaikka	58+792	Helsinki–Riihimäki, Hyvinkää–Karjaa	Hyvinkää	K	K	K
Hämeenlinna	Tavastehus	Hl		Liikennepaikka	107+559	Riihimäki–Tampere	Hämeenlinna	K	K	K
Härmä		Hm		Liikennepaikka	472+940	Seinäjoki–Oulu	Kauhava	K		K
Höljäkkä		Höl		Seisake	765+261	Joensuu–Nurmes	Nurmes		K	K
Ii		Ii		Liikennepaikka	789+165	Oulu–Laurila	Ii	K		K
Iisalmen teollisuusraiteet	Keveli	Itr		Linjavaihde	548+611	Pieksämäki–Kontiomäki	Iisalmi		K	K
Iisalmi	Idensalmi	Ilm		Liikennepaikka	550+360	Iisalmi–Ylivieska, Pieksämäki–Kontiomäki	Iisalmi	K	K	K
Iittala		Ita		Seisake	129+286	Riihimäki–Tampere	Hämeenlinna			
Ilola		Ioa		Seisake	155+100	Toijala–Valkeakoski	Valkeakoski			
Ilomantsi	Ilomants	Ilo		Liikennepaikka	695+203	Joensuu–Ilomantsi	Ilomantsi	M	K	K
<b>IMATRA</b>		<b>Ima</b>		<b>Osiin jaettu liikennepaikka</b>	<b>326+542</b>	<b>Kouvola–Joensuu, Imatra tavara–Imatrankoski-raja</b>	<b>Imatra</b>	<b>K</b>		
<i>Imatra asema</i>		<i>Imr</i>	<i>Imatra</i>	<i>Liikennepaikan osa (Imatra)</i>	<i>323+977</i>		<i>Imatra</i>			

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
<i>Imatra tavana</i>		<i>Imt</i>		<i>Liikennepaikan osa (Imatra)</i>	326+542		<i>Imatra</i>		<i>K</i>	<i>K</i>
<i>Imatrankoski</i>		<i>Imk</i>		<i>Liikennepaikan osa (Imatra)</i>	331+267		<i>Imatra</i>		<i>K</i>	<i>K</i>
<i>Pelkola</i>		<i>Pa</i>		<i>Liikennepaikan osa (Imatra)</i>	335+672		<i>Imatra</i>		<i>K</i>	<i>K</i>
Imatrankoski-raja		Imkr		Liikennepaikka	337+095	Imatra tavana–Imatrankoski-raja	Imatra			
Inha		In		Linjavaihde	341+367	Orivesi–Seinäjoki	Ähtäri			K
Inkeroinen		Ikr		Liikennepaikka	212+781	Kouvola–Kotka	Kouvola	K	K	K
Inkoo	Ingå	Iko		Liikennepaikka	70+620	Helsinki–Turku satama	Inkoo	K		K
Isokyrö	Storkyro	Iky		Liikennepaikka	447+488	Seinäjoki–Vaasa	Isokyrö	K		K
Jalasjärvi		Jal		Liikennepaikka	309+871	Tampere–Seinäjoki	Kurikka	K		K
Jepua	Jeppo	Jpa		Liikennepaikka	495+784	Seinäjoki–Oulu	Uusikaarlepyy	K		K
<b>JOENSUU</b>		<b>Joe</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Pieksämäki–Joensuu, Kouvola–Joensuu, Joensuu–Ilomantsi, Joensuu–Nurmes</b>		<b>M</b>		
<i>Joensuu Sulkolahti</i>		<i>Sul</i>		<i>Liikennepaikan osa (Joensuu)</i>	622+650		<i>Joensuu</i>			<i>K</i>
<i>Joensuu Peltola</i>		<i>Plt</i>		<i>Liikennepaikan osa (Joensuu)</i>	623+540		<i>Joensuu</i>		<i>K</i>	<i>K</i>
<i>Joensuu asema</i>		<i>Jns</i>	<i>Joensuu</i>	<i>Liikennepaikan osa (Joensuu)</i>	624+313		<i>Joensuu</i>			<i>K</i>
Jokela		Jk		Liikennepaikka	47+937	Helsinki–Riihimäki	Tuusula	K		K
Joroinen	Jorois	Jor		Linjavaihde	414+617	Huutokoski–Savonlinna	Joroinen			K
Jorvas		Jrs		Seisake	32+322	Helsinki–Turku satama	Kirkkonummi			
Joutseno		Jts		Liikennepaikka	305+826	Kouvola–Joensuu	Lappeenranta	K	K	K
Juankoski		Jki		Liikennepaikka	531+995	Siilinjärvi–Viinijärvi	Juankoski	K		K
Jutila		Jut		Liikennepaikka	94+620	Riihimäki–Kouvola	Kärkölä	K		
Juupajoki		Jj		Seisake	246+580	Orivesi–Seinäjoki	Juupajoki			
Juurikorpi		Jri		Liikennepaikka	224+898	Kouvola–Kotka, Juurikorpi–Hamina	Kotka	K		
Jyväskylä		Jy		Liikennepaikka	340+370	Jyväskylä–Pieksämäki, Haapamäki–Jyväskylä, Jyväskylä–Äänekoski, Tampere–Jyväskylä	Jyväskylä	K	K	K
Jämsä		Jäs		Liikennepaikka	284+084	Jämsä–Kaipola, Tampere–Jyväskylä	Jämsä	K		K
Jämsänkoski		Jsk		Liikennepaikka	287+917	Tampere–Jyväskylä	Jämsä	K	K	K
Järvelä		Jr		Liikennepaikka	103+596	Riihimäki–Kouvola	Kärkölä	K	K	K
<b>JÄRVENPÄÄ</b>		<b>Jvp</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Helsinki–Riihimäki</b>		<b>K</b>		
<i>Järvenpää asema</i>	<i>Träskända</i>	<i>Jp</i>	<i>Järvenpää</i>	<i>Liikennepaikan osa (Järvenpää)</i>	36+786		<i>Järvenpää</i>			
<i>Saunakallio</i>		<i>Sau</i>		<i>Liikennepaikan osa (Järvenpää)</i>	38+846		<i>Järvenpää</i>		<i>K</i>	<i>K</i>
<i>Purola</i>		<i>Pur</i>		<i>Liikennepaikan osa (Järvenpää)</i>	40+533		<i>Järvenpää</i>	<i>K</i>		
Kaipiainen		Kpa		Liikennepaikka	214+451	Kouvola–Joensuu	Kouvola	K	K	K
Kaipola		Kla		Liikennepaikka	290+303	Jämsä–Kaipola	Jämsä		K	K
Kairokoski		Kko		Linjavaihde	423+184	Niinisalo–Parkano	Parkano			K
Kaitjärvi		Kjr		Liikennepaikka	226+912	Kouvola–Joensuu	Luumäki	K		
Kajaani	Kajana	Kaj		Liikennepaikka	633+491	Pieksämäki–Kontiomäki, Kajaani–Lamminniemi	Kajaani	K		K
Kaleton		Ktn		Linjavaihde	320+875	Haapamäki–Jyväskylä	Keuruu			
Kalkku		Kau		Liikennepaikka	199+471	Lielähti–Kokemäki	Tampere	K	K	
Kalliovarasto		Kao		Linjavaihde	644+770	Pieksämäki–Kontiomäki	Kajaani		K	
Kallislahti		Kll		Linjavaihde	465+822	Huutokoski–Savonlinna	Savonlinna			K

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Kalviitsa	Gamlas	Ksa		Liikennepaikka	330+634	Kouvola–Pieksämäki	Mikkeli	K		K
Kangas		Kgs		Liikennepaikka	642+464	Seinäjoki–Oulu	Ylivieska	K		K
Kannelmäki		Kan		Liikennepaikka	9+300	Huopalahti–Havukoski	Helsinki	K		
Kannonkoski		Ksi		Liikennepaikka	488+694	Äänekoski–Haapajärvi	Kannonkoski	M		K
Kannus	Karis	Kns		Liikennepaikka	570+273	Seinäjoki–Oulu	Kannus	K		K
Karhejärvi		Krr		Liikennepaikka	224+902	Tampere–Seinäjoki	Ylöjärvi	K		K
Karhukangas		Khg		Liikennepaikka	622+902	Seinäjoki–Oulu	Ylivieska	K		
Karjaa		Kr		Liikennepaikka	157+817	Helsinki–Turku satama, Hyvinkää–Karjaa, Karjaa–Hanko	Raasepori	K	K	K
Karkku	Kaskö	Kru		Liikennepaikka	230+733	Lielähti–Kokemäki	Sastamala	K		K
Karviainen		Kar		Liikennepaikka	247+320	Toijala–Turku	Aura	K		
Kaskinen		Ksk		Liikennepaikka	530+522	Seinäjoki–Kaskinen	Kaskinen	K	K	K
Kattilaharju		Kth		Liikennepaikka	205+556	Kouvola–Joensuu	Kouvola	K		
Kauhajoki		Kji		Liikennepaikka	472+720	Seinäjoki–Kaskinen	Kauhajoki	K		
Kauhava		Kha		Liikennepaikka	455+728	Seinäjoki–Oulu	Kauhava	K	K	K
<b>KAUKLAHTI</b>		<b>Kal</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Helsinki–Turku satama</b>		<b>K</b>		
<i>Kauklahti asema</i>	<i>Köklax</i>	<i>Klh</i>	<i>Kauklahti</i>	<i>Liikennepaikan osa (Kauklahti)</i>	24+277		<i>Espoo</i>			<i>K</i>
<i>Mankki</i>	<i>Mankby</i>	<i>Mnk</i>		<i>Liikennepaikan osa (Kauklahti)</i>	25+401		<i>Kirkkonummi</i>		<i>K</i>	
Kaulinranta	Grankulla	Klr		Liikennepaikka	963+350	Tornio–Kolari	Ylitornio	K		
Kauniainen		Kni		Liikennepaikka	16+054	Helsinki–Turku satama	Kauniainen	K		K
Kauppiänmäki		Kpl		Liikennepaikka	568+751	Pieksämäki–Kontiomäki	Iisalmi	K		K
Kausala		Ka		Seisake	169+425	Riihimäki–Kouvola	Iitti			
Keitelepuhja		Ktp		Liikennepaikka	519+256	Äänekoski–Haapajärvi	Viitasaari	M		K
Kekomäki		Kek		Liikennepaikka	79+288	Riihimäki–Kouvola	Hausjärvi	K		
Kelkkämäki		Klk		Linjavaihde	399+992	Jyväskylä–Pieksämäki	Laukaa			
Kemi		Kem		Liikennepaikka	858+300	Oulu–Laurila, Kemi–Ajos	Kemi	K	K	K
Kemijärvi		Kjä		Liikennepaikka	1056+399	Kemijärvi–Kellosele, Laurila–Kemijärvi	Kemijärvi	K	K	K
Kempele		Kml		Liikennepaikka	741+075	Seinäjoki–Oulu	Kempele	K		K
Kera		Kea		Seisake	14+536	Helsinki–Turku satama	Espoo			
<b>KERAVA</b>		<b>Kev</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Helsinki–Riihimäki, Kerava–Hakosilta, Kerava–Sköldvik, Kerava–Vuosaari</b>		<b>K</b>		
<i>Kerava asema</i>	<i>Kervo</i>	<i>Ke</i>	<i>Kerava</i>	<i>Liikennepaikan osa (Kerava)</i>	28+869		<i>Kerava</i>		<i>K</i>	<i>K</i>
<i>Kytömaa</i>		<i>Kyt</i>		<i>Liikennepaikan osa (Kerava)</i>	31+274		<i>Kerava</i>			
Kerimäki		Kiä		Liikennepaikka	495+531	Savonlinna–Parikkala	Savonlinna	K		K
Kesälahti		Kti		Liikennepaikka	428+003	Kouvola–Joensuu	Kitee	K		
Keuruu	Kiala	Keu		Liikennepaikka	316+041	Haapamäki–Jyväskylä	Keuruu	K		K
Kiiala		Kia		Seisake	60+013	Olli–Porvoo	Porvoo			
Kilo		Kil		Seisake	13+035	Helsinki–Turku satama	Espoo			
Kilpua		Kua		Liikennepaikka	668+910	Seinäjoki–Oulu	Oulainen	K		K
Kinahmi		Knh		Linjavaihde	508+922	Siilinjärvi–Viinijärvi	Kuopio		K	
Kinni		Kii		Liikennepaikka	247+982	Kouvola–Pieksämäki	Mäntyläharju	K		
Kirjola		Kij		Linjavaihde	384+475	Kouvola–Joensuu	Parikkala		K	
Kirkkonummi		Kkn		Liikennepaikka	37+503	Helsinki–Turku satama	Kirkkonummi	K		K
Kirkniemi	Gerknäs	Krn		Liikennepaikka	136+261	Hyvinkää–Karjaa	Lohja	K	K	K
Kitee		Kit		Liikennepaikka	460+016	Kouvola–Joensuu	Kitee	K		K
Kiukainen		Kn		Liikennepaikka	297+395	Kokemäki–Rauma	Eura	K		K
Kiuruvesi		Krv		Liikennepaikka	583+985	Iisalmi–Ylivieska	Kiuruvesi	K	K	K
Kivesjärvi		Kvj		Liikennepaikka	878+146	Oulu–Kontiomäki	Paltamo	K		

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Kivistö		Ktö		Seisake	12+281	Huopalahti–Havukoski	Vantaa			
Kohtavaara		Koh		Seisake	775+927	Joensuu–Nurmes	Nurmes			
Koivu		Kvu		Liikennepaikka	923+373	Laurila–Kemijärvi	Tervola	K		K
Koivuhovi	Björkgård	Kvh		Seisake	17+861	Helsinki–Turku satama	Espoo			
Koivukylä	Björkby	Kvy		Seisake	19+440	Helsinki–Riihimäki	Vantaa			
Kokemäki	Kumo	Kki		Liikennepaikka	284+442	Lielähti–Kokemäki, Kokemäki–Rauma, Kokemäki–Pori	Kokemäki	K		K
Kokkola	Karleby	Kok		Liikennepaikka	551+441	Kokkola–Ykspihlaja, Seinäjoki–Oulu	Kokkola	K	K	K
Kolari		Kli		Liikennepaikka	1067+206	Tornio–Kolari	Kolari	K		K
Kolho		Klo		Seisake	286+265	Orivesi–Seinäjoki	Mänttä–Vilppula			K
Kolppi	Källby	Kpi		Liikennepaikka	525+100	Seinäjoki–Oulu	Pedersöre	K		K
Kommila		Kmm		Liikennepaikka	429+700	Varkaus–Kommila	Varkaus		K	K
Komu		Kom		Linjavaihde	607+174	Iisalmi–Ylivieska	Pyhäjärvi		K	
Kontiolahti		Khi		Liikennepaikka	640+295	Joensuu–Nurmes	Kontiolahti	K		K
						Nurmes–Kontiomäki, Oulu–Kontiomäki,				
Kontiomäki		Kon		Liikennepaikka	658+786	Kontiomäki–Ämmänsaari, Pieksämäki–Kontiomäki,	Paltamo	K	K	K
						Kontiomäki–Vartius-rajaa				
Koria		Kra		Seisake	185+374	Riihimäki–Kouvola	Kouvola			
Korkeakoski		Kas		Liikennepaikka	247+910	Orivesi–Seinäjoki	Juupajoki	K	K	K
Korso		Krs		Seisake	22+669	Helsinki–Riihimäki	Vantaa			
Korvensuo		Ksu		Liikennepaikka	50+500	Kerava–Hakosilta	Mäntsälä	K		
Koskenkorva		Kos		Liikennepaikka	442+447	Seinäjoki–Kaskinen	Ilmajoki	M		K
<b>KOTKA</b>		<b>Kot</b>		<b>Osiin jaettu liikennepaikka</b>	<b>–</b>	<b>Kouvola–Kotka, Kotka Hovinsaari–Kotka Mussalo</b>		<b>M</b>		
<i>Kotka Hovinsaari</i>		<i>Hos</i>		<i>Liikennepaikan osa (Kotka)</i>	<i>240+400</i>		<i>Kotka</i>		<i>K</i>	<i>K</i>
<i>Kotka tavara</i>		<i>Ktt</i>		<i>Liikennepaikan osa (Kotka)</i>	<i>240+870</i>		<i>Kotka</i>			<i>K</i>
<i>Paimenportti</i>		<i>Pti</i>		<i>Liikennepaikan osa (Kotka)</i>	<i>241+190</i>		<i>Kotka</i>			
<i>Kotka asema</i>		<i>Kta</i>	<i>Kotka</i>	<i>Liikennepaikan osa (Kotka)</i>	<i>242+775</i>		<i>Kotka</i>		<i>K</i>	<i>K</i>
<i>Kotkan satama</i>		<i>Kts</i>		<i>Liikennepaikan osa (Kotka)</i>	<i>243+579</i>		<i>Kotka</i>		<i>K</i>	<i>K</i>
<i>Kotolahti</i>		<i>Koo</i>		<i>Liikennepaikan osa (Kotka)</i>	<i>245+203</i>		<i>Kotka</i>		<i>K</i>	<i>K</i>
<i>Kotka Mussalo</i>		<i>Mss</i>		<i>Liikennepaikan osa (Kotka)</i>	<i>247+057</i>		<i>Kotka</i>		<i>K</i>	<i>K</i>
<b>KOUVOLA</b>		<b>Kvl</b>		<b>Osiin jaettu liikennepaikka</b>	<b>–</b>	<b>Riihimäki–Kouvola, Kouvola–Pieksämäki, Kouvola–Kotka, Kouvola–Joensuu, Kouvola–Kuusankoski</b>		<b>M</b>		
<i>Kouvola asema</i>		<i>Kv</i>	<i>Kouvola</i>	<i>Liikennepaikan osa (Kouvola)</i>	<i>191+540</i>		<i>Kouvola</i>		<i>K</i>	<i>K</i>
<i>Kouvola lajittelu</i>		<i>Kvla</i>		<i>Liikennepaikan osa (Kouvola)</i>	<i>192+570</i>		<i>Kouvola</i>		<i>K</i>	<i>K</i>
<i>Kouvola tavara</i>		<i>Kvt</i>		<i>Liikennepaikan osa (Kouvola)</i>	<i>194+050</i>		<i>Kouvola</i>		<i>K</i>	<i>K</i>
<i>Kouvola Oikoraide</i>		<i>Oik</i>		<i>Liikennepaikan osa (Kouvola)</i>	<i>194+460</i>		<i>Kouvola</i>			
<i>Kullasvaara</i>		<i>Kuv</i>		<i>Liikennepaikan osa (Kouvola)</i>	<i>197+300</i>		<i>Kouvola</i>			
Kovjoki		Koi		Liikennepaikka	508+925	Seinäjoki–Oulu	Uusikaarlepyy	K		
Kruunupyy	Kronoby	Kpy		Liikennepaikka	537+585	Seinäjoki–Oulu	Kruunupyy	K	K	K
Kuivasjärvi		Kis		Liikennepaikka	276+327	Tampere–Seinäjoki	Parkano	K		K

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
<b>KUOPIO</b>		<b>Kpo</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Pieksämäki–Kontiomäki</b>		<b>M</b>		
<i>Kuopio asema</i>		<i>Kuo</i>	<i>Kuopio</i>	<i>Liikennepaikan osa (Kuopio)</i>	464+590		<i>Kuopio</i>			<i>K</i>
<i>Kuopio tavaras</i>		<i>Kuot</i>		<i>Liikennepaikan osa (Kuopio)</i>	465+500		<i>Kuopio</i>		<i>K</i>	<i>K</i>
Kurkimäki		Krm		Liikennepaikka	444+074	Pieksämäki–Kontiomäki	Kuopio	K		K
Kuurila		Ku		Liikennepaikka	138+769	Riihimäki–Tampere	Hämeenlinna	K		K
Kuusankoski		Kuk		Liikennepaikka	199+290	Kouvola–Kuusankoski	Kouvola	M	K	K
Kylänlahti		Kyn		Seisake	742+960	Joensuu–Nurmes	Lieksa			
Kymi	Kymmene	Ky		Liikennepaikka	233+450	Kouvola–Kotka	Kotka	M	K	K
Kymnlinna		Kln		Seisake	237+255	Kouvola–Kotka	Kotka			
Kyrö		Kö		Liikennepaikka	232+875	Toijala–Turku	Karinainen	K		K
Kälviä	Kelviä	Klv		Liikennepaikka	570+273	Seinäjoki–Oulu	Kokkola	K		
Köykkäri		Kök		Liikennepaikka	486+491	Seinäjoki–Oulu	Kauhava	K		
Laajavuori		Lav		Liikennepaikka	14+527	Huopalahti–Havukoski	Vantaa	K		
Lahdenperä		Lpr		Liikennepaikka	267+080	Tampere–Jyväskylä	Jämsä	K		
Lahnaslampi		Lhn		Liikennepaikka	881+053	Vuokatti–Lahnaslampi	Sotkamo		K	K
						Riihimäki–Kouvola, Lahti–Heinola, Lahti–Mukkula,				
Lahti	Lahtis	Lh		Liikennepaikka	130+170	Lahti–Loviisan satama	Lahti	K	K	K
Laihia	Laihela	Lai		Liikennepaikka	468+916	Seinäjoki–Vaasa	Laihia	K		K
Lakiala		Lak		Liikennepaikka	209+214	Tampere–Seinäjoki	Ylöjärvi	K		K
Lamminkoski		Lmk		Liikennepaikka	268+785	Tampere–Seinäjoki	Parkano	K		
Lamminniemi		Lam		Liikennepaikka	636+664	Kajaani–Lamminniemi	Kajaani		K	K
Lapinjärvi	Lappträsk	Lpj		Liikennepaikka	185+432	Lahti–Loviisan satama	Lapinjärvi	M		K
Lapinlahti		Lna		Liikennepaikka	525+604	Pieksämäki–Kontiomäki	Lapinlahti	K		K
Lapinneva				Linjavaihde	415+618	Niinisalo–Parkano	Parkano			
Lappeenranta	Villmanstrand	Lr		Liikennepaikka	287+726	Kouvola–Joensuu, Lappeenranta–Mustolan satama	Lappeenranta	K	K	K
Lappila		Laa		Seisake	97+693	Riihimäki–Kouvola	Kärkölä			
Lappohja	Lappvik	Lpo		Liikennepaikka	189+639	Karjaa–Hanko	Hanko	K	K	K
Lapua	Lappo	Lpa		Liikennepaikka	441+094	Seinäjoki–Oulu	Lapua	K	K	K
Larvakytö		Lyö		Liikennepaikka	333+057	Tampere–Seinäjoki	Seinäjoki	K		
Laukaa		Lau		Liikennepaikka	401+193	Jyväskylä–Äänekoski	Laukaa	K		
Laurila		Lla		Liikennepaikka	865+776	Laurila–Kemijärvi, Oulu–Laurila, Laurila–Tornio-rajaa	Keminmaa	K		K
Lauritsala		Lrs		Liikennepaikka	291+936	Kouvola–Joensuu	Lappeenranta	K	K	K
Lautiosaari		Li		Liikennepaikka	863+064	Lautiosaari–Eläjä, Oulu–Laurila	Kemi	K		
Leinelä	Lejle	Lnä		Seisake	31+146	Huopalahti–Havukoski	Vantaa			
Lentoasema	Flygplatsen	Len		Seisake	26+575	Huopalahti–Havukoski	Vantaa			
Leikola		Lkl		Liikennepaikka	276+011	Kouvola–Pieksämäki	Hirvensalmi	K		
Lempäälä		Lpä		Liikennepaikka	165+928	Riihimäki–Tampere	Lempäälä	K		
Leppäkoski		Lk		Liikennepaikka	87+830	Riihimäki–Tampere	Janakkala	K		
Leppävaara	Alberga	Lpv		Liikennepaikka	11+249	Helsinki–Turku satama	Espoo	K		K
Leteensuo		Lts		Liikennepaikka	123+554	Riihimäki–Tampere	Hattula	K		
Lieksa		Lis		Liikennepaikka	728+121	Joensuu–Nurmes, Lieksa–Pankakoski	Lieksa	K	K	K
Lieksan teollisuuskylä		Ltk		Linjavaihde	728+847	Lieksa–Pankakoski	Lieksa		K	K
Lielähti		Llh		Liikennepaikka	193+393	Tampere–Seinäjoki, Lielähti–Kokemäki	Tampere	K	K	K
Lievestuore		Lvt		Liikennepaikka	402+191	Jyväskylä–Pieksämäki	Laukaa	K	K	K
Liminka	Limingo	Lka		Liikennepaikka	728+483	Seinäjoki–Oulu	Liminka	K		K
Lohiluoma		Luo		Linjavaihde	463+619	Seinäjoki–Kaskinen	Kurikka			
Lohja	Lojo	Lo		Liikennepaikka	122+965	Hyvinkää–Karjaa	Lohja	K		K

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Loimaa		Lm		Liikennepaikka	208+870	Toijala-Turku	Loimaa	K		K
Louhela	Klippsta	Loh		Seisake	13+190	Huopalahti-Havukoski	Vantaa			
Loukolampi		Lol		Liikennepaikka	360+013	Kouvola-Pieksämäki	Pieksämäki	K		
Loviisan satama	Lovisa hamn	Lvs		Liikennepaikka	207+209	Lahti-Loviisan satama	Loviisa	M	K	K
Luikonlahti		Lui		Liikennepaikka	557+061	Siilinjärvi-Viinijärvi	Kaavi	K		K
Luoma	Bobäck	Lma		Seisake	27+807	Helsinki-Turku satama	Kirkkonummi			
Lusto		Lus		Seisake	509+170	Savonlinna-Parikkala	Savonlinna			
Luumäki		Lä		Liikennepaikka	250+540	Kouvola-Joensuu, Luumäki-Vainikkala-raja	Luumäki	K	K	K
Lähdemäki		Läh		Liikennepaikka	79+373	Kerava-Hakosilta	Orimattila	K		
Länskipohja		Läp		Liikennepaikka	256+024	Tampere-Jyväskylä	Jämsä	K		
Maanselkä		MLk		Liikennepaikka	836+049	Nurmes-Kontiomäki	Sotkamo	M		K
Maaria	St Marie	Mri		Liikennepaikka	262+070	Toijala-Turku	Turku	K		
Madesjärvi		Md		Liikennepaikka	291+821	Tampere-Seinäjoki	Kurikka	K		K
Majajärvi		Mjj		Liikennepaikka	216+317	Tampere-Seinäjoki	Ylöjärvi	K		
Malmi	Malm	ML		Liikennepaikka	10+900	Helsinki-Riihimäki	Helsinki	K		
Malminkartano	Malmgård	Mlo		Seisake	10+730	Huopalahti-Havukoski	Helsinki			
Mankala		Mka		Liikennepaikka	160+050	Riihimäki-Kouvola	Iitti	K		
Markkala		Mrk		Liikennepaikka	403+737	Pieksämäki-Kontiomäki	Suonenjoki	K		
Martinlaakso	Mårtensdal	Mrl		Seisake	14+010	Huopalahti-Havukoski	Vantaa	K		
Masala	Masaby	Mas		Seisake	29+561	Helsinki-Turku satama	Kirkkonummi			
Matkaneva		Mtv		Liikennepaikka	562+607	Seinäjoki-Oulu	Kokkola	K		
Mattila		Mat		Liikennepaikka	159+906	Riihimäki-Tampere	Lempäälä	K		
Meltola	Mjölbolsta	Mel		Linjavaihde	149+862	Hyvinkää-Karjaa	Raasepori		K	
Metsäkansa		Msä		Linjavaihde	155+811	Toijala-Valkeakoski	Valkeakoski			K
Mikkeli	St Michel	Mi		Liikennepaikka	305+165	Kouvola-Pieksämäki	Mikkeli	K	K	K
Misi		Mis		Liikennepaikka	1021+255	Laurila-Kemijärvi	Rovaniemi	M		K
Mommila		Mlä		Seisake	91+430	Riihimäki-Kouvola	Hausjärvi			
Muhos		Mh		Liikennepaikka	788+424	Oulu-Kontiomäki	Muhos	K		K
Mukkula		Muk		Liikennepaikka	140+012	Lahti-Mukkula	Lahti		K	K
Murtomäki		Mur		Liikennepaikka	613+165	Pieksämäki-Kontiomäki, Murtomäki-Talvivaara, Murtomäki-Otanmäki	Kajaani	K		K
Mustio	Svartå	Mso		Linjavaihde	143+000	Hyvinkää-Karjaa	Raasepori			K
Mustolan satama		Mst		Liikennepaikka	296+720	Lappeenranta-Mustolan satama	Lappeenranta		K	
Muukko		Mko		Liikennepaikka	297+112	Kouvola-Joensuu	Lappeenranta	K		
Muurame		Muu		Liikennepaikka	324+768	Tampere-Jyväskylä	Muurame	K		K
Muurola		Mul		Liikennepaikka	948+494	Laurila-Kemijärvi	Rovaniemi	K		K
Myllykangas		Mys		Liikennepaikka	815+693	Oulu-Laurila	Ii	K		
Myllykoski		Mki		Seisake	203+742	Kouvola-Kotka	Kouvola	K		
Myllymäki		My		Seisake	333+721	Orivesi-Seinäjoki	Ähtäri			K
Myllyoja		Myl		Liikennepaikka	161+727	Lahti-Heinola	Heinola	K	K	K
Mynttilä		Myt		Liikennepaikka	270+889	Kouvola-Pieksämäki, Mynttilä-Ristiina	Mäntyharju	K		
Mynämäki		Myn		Liikennepaikka	229+607	Turku-Uusikaupunki	Mynämäki	K		
Myyrmäki	Myrbacka	Myr		Liikennepaikka	12+130	Huopalahti-Havukoski	Vantaa	K		
Mäkkylä		Mäk		Seisake	9+511	Helsinki-Turku satama	Espoo			
Mäntsälä		Mlä		Liikennepaikka	59+210	Kerava-Hakosilta	Mäntsälä	K		
Mänttä		Män		Liikennepaikka	282+740	Vilppula-Mänttä	Mänttä-Vilppula		K	K
Mäntyharju		Mr		Liikennepaikka	262+680	Kouvola-Pieksämäki	Mäntyharju	K		K
Mäntyluoto		Mn		Liikennepaikka	342+020	Pori-Mäntyluoto	Pori	K	K	K
Naantali	Nädendal	Nnl		Liikennepaikka	213+193	Raisio-Naantali	Naantali		K	K
Naarajärvi		Nri		Liikennepaikka	449+862	Jyväskylä-Pieksämäki	Pieksämäki	K		K

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Nakkila	Nickby	Nal		Liikennepaikka	308+091	Kokemäki–Pori	Nakkila	K		
Nastola		Nsl		Seisake	146+169	Riihimäki–Kouvola	Nastola			
Niemenpää		Nmp		Liikennepaikka	923+605	Tornio–Kolari	Tornio	K		
Niinimaa		Nii		Linjavaihde	383+155	Orivesi–Seinäjoki	Alavus			
Niinimäki		Nmä		Liikennepaikka	172+534	Riihimäki–Kouvola	Jitti			
Niinisalo		Nns		Liikennepaikka	386+215	Niinisalo–Parkano	Kankaanpää	M	K	K
Niirala		Nrl		Liikennepaikka	555+846	Niirala–raja–Säkäniemi	Tohmajärvi	M	K	K
Niirala–raja		Nrlr		Liikennepaikka	554+080	Niirala–raja–Säkäniemi	Tohmajärvi			
Niittylahti		Nth		Liikennepaikka	613+475	Kouvola–Joensuu	Joensuu	K		
Nikkilä		Nlä		Seisake	39+176	Kerava–Sköldvik	Sipoo			
Nivala		Nvl		Liikennepaikka	676+878	Iisalmi–Ylivieska	Nivala	K		K
Nokia		Noa		Liikennepaikka	204+004	Lielähti–Kokemäki	Nokia	K	K	K
Nummela		Nm		Liikennepaikka	109+368	Hyvinkää–Karjaa	Vihti	K		K
Nuppulinna		Nup		Seisake	44+210	Helsinki–Riihimäki	Tuusula			
Nurmes		Nrm		Liikennepaikka	784+420	Nurmes–Kontiomäki, Joensuu–Nurmes	Nurmes	K	K	K
Närpiö	Närpes	När		Linjavaihde	518+255	Seinäjoki–Kaskinen	Närpiö			
Ohenmäki		Ohm		Linjavaihde	542+264	Pieksämäki–Kontiomäki	Iisalmi			K
Olli		Olli		Linjavaihde	45+734	Kerava–Sköldvik, Olli–Porvoo	Porvoo	K		
Onttola		Ont		Linjavaihde	631+177	Pieksämäki–Joensuu	Joensuu		K	K
Orimattila		Om		Linjavaihde	150+407	Lahti–Loviisan satama	Orimattila			K
Orivesi		Ov		Liikennepaikka	228+276	Tampere–Jyväskylä, Orivesi–Seinäjoki	Orivesi	K		K
Orivesi keskusta		Ovk		Seisake	231+512	Orivesi–Seinäjoki	Orivesi			
Otanmäki		Otm		Liikennepaikka	638+822	Murtomäki–Otanmäki	Kajaani		K	K
Otava		Ot		Liikennepaikka	290+521	Kouvola–Pieksämäki, Otava–Otavan satama	Mikkeli	K		K
Otavan satama		Ots		Liikennepaikka	292+885	Otava–Otavan satama	Mikkeli		K	K
Oulainen		Ou		Liikennepaikka	657+850	Seinäjoki–Oulu	Oulainen	K		K
<b>OULU</b>	Uleåborg	<b>Oul</b>	<i>Oulu</i>	<b>Osiin jaettu liikennepaikka</b>	–	<b>Seinäjoki–Oulu, Oulu–Kontiomäki, Oulu–Laurila</b>		<b>M</b>		
<i>Oulu Nokela</i>		<i>Nok</i>		<i>Liikennepaikan osa (Oulu)</i>	<i>750+030</i>		<i>Oulu</i>		K	K
<i>Oulu Oritkari</i>		<i>Ori</i>		<i>Liikennepaikan osa (Oulu)</i>	<i>751+180</i>		<i>Oulu</i>		K	K
<i>Oulu tavara</i>		<i>Olt</i>		<i>Liikennepaikan osa (Oulu)</i>	<i>751+360</i>		<i>Oulu</i>		K	K
<i>Oulu asema</i>		<i>Ol</i>		<i>Liikennepaikan osa (Oulu)</i>	<i>752+778</i>		<i>Oulu</i>		K	K
<i>Oulu Tuira</i>		<i>Tua</i>		<i>Liikennepaikan osa (Oulu)</i>	<i>755+510</i>		<i>Oulu</i>		K	K
Paimio	Pemar	Po		Liikennepaikka	171+885	Helsinki–Turku satama	Paimio	K		
Palopuro		Plp		Liikennepaikka	54+535	Helsinki–Riihimäki	Hyvinkää	K		
Paltamo		Pto		Liikennepaikka	901+579	Oulu–Kontiomäki	Paltamo	K		K
Pankakoski		Pas		Liikennepaikka	731+865	Lieska–Pankakoski	Lieska		K	K
Parikkala		Par		Liikennepaikka	387+302	Kouvola–Joensuu, Savonlinna–Parikkala	Parikkala	K		K
Parkano		Pko		Liikennepaikka	262+483	Parkano–Kihniö, Tampere–Seinäjoki	Parkano	K	K	K
Parola		Prl		Liikennepaikka	115+764	Riihimäki–Tampere	Hattula	K	K	K
Patokangas		Ptg		Liikennepaikka	1065+000	Kemijärvi–Patokangas	Kemijärvi			K
Pello		Pel		Liikennepaikka	1002+632	Tornio–Kolari	Pello	K	K	
Peltosalmi		Pmi		Liikennepaikka	545+355	Pieksämäki–Kontiomäki	Iisalmi			
Peräseinäjoki	Pieksämäki	Psj	<i>Pieksämäki</i>	Liikennepaikka	318+481	Tampere–Seinäjoki	Seinäjoki	K	K	K
Pesiökylä		Psk		Liikennepaikka	732+752	Kontiomäki–Ämmänsaari	Suomussalmi	M		K
Petäjävesi		Pvi		Liikennepaikka	343+357	Haapamäki–Jyväskylä	Petäjävesi	K		K
<b>PIEKSÄMÄKI</b>		<b>Pie</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Kouvola–Pieksämäki, Pieksämäki–Kontiomäki, Jyväskylä–Pieksämäki, Pieksämäki–Joensuu</b>	<b>Pieksämäki</b>	<b>M</b>		
<i>Pieksämäki asema</i>		<i>Pm</i>		<i>Liikennepaikan osa (Pieksämäki)</i>	<i>376+000</i>		<i>Pieksämäki</i>		K	K
<i>Pieksämäki Temu</i>		<i>Tmu</i>		<i>Liikennepaikan osa (Pieksämäki)</i>	<i>377+340</i>		<i>Pieksämäki</i>		K	K



Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö- mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår- anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Pieksämäki lajittelu		Pmla		Liikennepaikan osa (Pieksämäki)	378+640		Pieksämäki		K	K
Pieksämäki tavara		Pmt		Liikennepaikan osa (Pieksämäki)	379+960		Pieksämäki		K	K
Pietarsaari	Jakobstad	Pts		Liikennepaikka	528+780	Pännäinen–Pietarsaari, Pietarsaari–Alholma	Pietarsaari	M		K
Pihlajavesi		Ph		Liikennepaikka	312+500	Orivesi–Seinäjoki	Keuruu	K		K
Pihtipudas		Pp		Liikennepaikka	540+605	Äänekoski–Haapajärvi	Pihtipudas	M		K
Piikkiö	Pikis	Pik		Liikennepaikka	182+785	Helsinki–Turku satama	Kaarina	K		K
Pikkarala		Pkl		Liikennepaikka	771+765	Oulu–Kontiomäki	Oulu	K	K	
Pitäjänmäki	Sockenbacka	Pjm		Seisake	8+474	Helsinki–Turku satama	Helsinki			
Pohjankuru	Skuru	Pku		Liikennepaikka	94+907	Helsinki–Turku satama	Raasepori	K	K	K
Pohjois-Haaga	Norra Haga	Poh		Seisake	8+050	Huopalahti–Havukoski	Helsinki			
Pohjois-Louko		Plu		Liikennepaikka	329+329	Tampere–Seinäjoki	Seinäjoki	K		
Poikkeus		Pkk		Liikennepaikka	254+744	Tampere–Seinäjoki	Parkano	K		
Poiksilta		Poi		Liikennepaikka	416+728	Kouvola–Joensuu	Kitee			K
Pori	Björneborg	Pri		Liikennepaikka	322+278	Pori–Aittaluoto, Pori–Mäntyluoto, Kokemäki–Pori	Pori	K	K	K
Porokylä		Por		Liikennepaikka	787+046	Nurmes–Kontiomäki	Nurmes			K
Porvoo	Borgå	Prv		Liikennepaikka	62+287	Olli–Porvoo	Porvoo			K
Puhos		Pus		Liikennepaikka	452+808	Kouvola–Joensuu	Kitee	K	K	K
Puistola	Parkstad	Pla		Seisake	14+050	Helsinki–Riihimäki	Helsinki			
Pukinmäki	Bocksbacka	Pmk		Seisake	9+442	Helsinki–Riihimäki	Helsinki			
Pulsa		Pl		Liikennepaikka	262+491	Luumäki–Vainikkala-rajaa	Lappeenranta	K		K
Punkaharju		Pun		Liikennepaikka	515+111	Savonlinna–Parikkala	Savonlinna	K	K	K
Pyhäkumpu		Pyk		Liikennepaikka	615+415	Pyhäkumpu erkanemisvaihde– Pyhäkumpu	Pyhäjärvi		K	
Pyhäkumpu erkanemisvaihde		Pye		Liikennepaikka	613+511	Iisalmi–Ylivieska, Pyhäkumpu erkanemisvaihde– Pyhäkumpu	Pyhäjärvi	K		
Pyhäsalmi		Phä		Liikennepaikka	615+934	Iisalmi–Ylivieska	Pyhäjärvi	K		K
Pännäinen	Bennäs	Pnä		Liikennepaikka	518+604	Pännäinen–Pietarsaari, Seinäjoki–Oulu	Pedersöre	K		K
Raahe	Brahestad	Rhe		Liikennepaikka	726+726	Raahe–Rautaruukki, Tuomioja–Raahe	Raahe	K	K	K
Raippo		Rpo		Liikennepaikka	270+052	Luumäki–Vainikkala-rajaa	Lappeenranta	K	K	K
Raisio	Reso	Rai		Liikennepaikka	207+829	Turku–Uusikaupunki, Raisio–Naantali	Raisio	K	K	K
Rajamäki		Rm		Liikennepaikka	72+267	Hyvinkää–Karjaa	Nurmijärvi			K
Rajaperkiö		Rjp		Liikennepaikka	448+396	Seinäjoki–Oulu	Lapua	K		
Rantasalmi		Rmi		Liikennepaikka	445+165	Huutokoski–Savonlinna	Rantasalmi	K		K
Rasinsuo		Ras		Liikennepaikka	258+510	Kouvola–Joensuu	Luumäki	K		
Ratikylä		Rlä		Liikennepaikka	284+344	Tampere–Seinäjoki	Kihniö	K		K
Rauha		Rah		Liikennepaikka	318+490	Kouvola–Joensuu	Lappeenranta	K		K
Rauhalahdi		Rhl		Liikennepaikka	380+510	Jyväskylä–Pieksämäki	Jyväskylä		K	K
Rauma	Raumo	Rma		Liikennepaikka	331+659	Kokemäki–Rauma	Rauma	K	K	K
Raunio		Rio		Liikennepaikka	464+845	Seinäjoki–Oulu	Kauhava	K		
Rautaruukki		Rat		Liikennepaikka	730+050	Raahe–Rautaruukki	Raahe		K	K
Rautjärvi		Rjä		Liikennepaikka	345+788	Kouvola–Joensuu	Rautjärvi	K		
Rautpohja		Rph		Liikennepaikka	372+829	Haapamäki–Jyväskylä	Jyväskylä		K	
Rekola	Räckhals	Rkl		Seisake	20+615	Helsinki–Riihimäki	Vantaa			
Retretti		Ree		Seisake	507+500	Savonlinna–Parikkala	Savonlinna			
<b>RIIHIMÄKI</b>		<b>Rii</b>		<b>Osiin jaettu liikennepaikka</b>	<b>–</b>	<b>Helsinki–Riihimäki, Riihimäki–Kouvola, Riihimäki–Tampere</b>		<b>K</b>		
Riihimäki Arolampi		Arp		Liikennepaikan osa (Riihimäki)	66+600		Hausjärvi			

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Riihimäki tavar		Rit		Liikennepaikan osa (Riihimäki)	68+773		Riihimäki			K
Riihimäki lajittelu		Rila		Liikennepaikan osa (Riihimäki)	70+068		Riihimäki			K
Riihimäki asema		Ri	Riihimäki	Liikennepaikan osa (Riihimäki)	71+410		Riihimäki		K	K
Riijärvi		Rjr		Liikennepaikka	502+567	Seinäjoki–Oulu	Uusikaarlepyy	K		
Riippa		Rpa		Liikennepaikka	577+477	Seinäjoki–Oulu	Kokkola	K		
Ristiina		Rst		Liikennepaikka	291+162	Mynttilä–Ristiina	Mikkeli	M	K	K
Ristijärvi		Rjv		Liikennepaikka	676+804	Kontiomäki–Ämmänsaari	Ristijärvi	K		
Rovaniemi		Roi		Liikennepaikka	971+775	Laurila–Kemijärvi	Rovaniemi	K	K	K
Ruha		Rha		Liikennepaikka	431+132	Seinäjoki–Oulu	Lapua	K		
Runni		Rnn		Seisake	568+518	Iisalmi–Ylivieska	Iisalmi			
Ruukki		Rki		Liikennepaikka	705+228	Seinäjoki–Oulu	Siikajoki	K		K
Ruusumäki		Rsm		Liikennepaikka	20+285	Huopalahti–Havukoski	Vantaa	K		
Ryttylä		Ry		Liikennepaikka	80+770	Riihimäki–Tampere	Hausjärvi	K	K	K
Röyttä		Röy		Liikennepaikka	893+917	Tornio–Röyttä	Tornio		K	K
Saakoski		Saa		Liikennepaikka	305+373	Tampere–Jyväskylä	Jyväskylä	K		
Saari		Sr		Liikennepaikka	405+246	Kouvola–Joensuu	Parikkala	K		
Saarijärvi		Srj		Liikennepaikka	452+723	Äänekoski–Haapajärvi	Saarijärvi	M		K
Salminen		Sln		Liikennepaikka	426+718	Pieksämäki–Kontiomäki, Pieksämäki–Kontiomäki	Suonenjoki	K		K
Salo		Slo		Liikennepaikka	143+981	Helsinki–Turku satama	Salo	K		K
Sammalisto		Sam		Liikennepaikka	74+487	Riihimäki–Tampere	Riihimäki	K		
Santala	Sandö	Sta		Seisake	196+908	Karjaa–Hanko	Hanko			
Saunamäki		Smä		Liikennepaikka	180+534	Riihimäki–Kouvola	Jitti			
Savio		Sav		Seisake	26+265	Helsinki–Riihimäki	Kerava			
<b>SAVONLINNA</b>		<b>Svl</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Savonlinna–Parikkala, Huutokoski–Savonlinna</b>				
Savonlinna asema	Nyslott	Sl	Savonlinna	Liikennepaikan osa (Savonlinna)	482+797		Savonlinna	K		
Pääskylähti		Pky		Liikennepaikan osa (Savonlinna)	484+913		Savonlinna	K		K
<b>SEINÄJOKI</b>		<b>Sei</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Tampere–Seinäjoki, Seinäjoki–Oulu, Orivesi–Seinäjoki, Seinäjoki–Vaasa, Seinäjoki–Kaskinen</b>		<b>M</b>		
Seinäjoki tavar		Skt		Liikennepaikan osa (Seinäjoki)	416+580		Seinäjoki		K	K
Seinäjoki asema		Sk	Seinäjoki	Liikennepaikan osa (Seinäjoki)	418+001		Seinäjoki		K	K
Selänpää		Spä		Liikennepaikka	209+869	Kouvola–Pieksämäki	Kouvola	K		
Sieppijärvi		Spj		Liikennepaikka	1045+904	Tornio–Kolari	Kolari	K		K
Sievi		Svi		Liikennepaikka	613+565	Seinäjoki–Oulu	Sievi	K		K
Siikamäki		Skä		Liikennepaikka	389+747	Pieksämäki–Joensuu	Pieksämäki	K		
<b>SIILINJÄRVI</b>		<b>Sii</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Siilinjärvi–Viinijärvi, Pieksämäki–Kontiomäki</b>		<b>K</b>	<b>K</b>	<b>K</b>
Siilinjärvi asema		Sij		Liikennepaikan osa (Siilinjärvi)	489+718		Siilinjärvi	K	K	K
Ruokosuo		Rsu		Liikennepaikan osa (Siilinjärvi)	494+735		Siilinjärvi	K	K	K
Simo		Sim		Liikennepaikka	833+715	Oulu–Laurila	Simo	K		K
Simpele		Spl		Liikennepaikka	368+317	Kouvola–Joensuu	Rautjärvi	K	K	K
Sipilä		Sip		Liikennepaikka	68+697	Kerava–Hakosilta, Kerava–Hakosilta	Mäntsälä	K		
Sisättö		Stö		Liikennepaikka	235+602	Tampere–Seinäjoki	Ikaalinen	K		

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Siuntio	Sjundeå	Sti		Liikennepaikka	51+285	Helsinki–Turku satama	Siuntio	K		
Siuro		Siu		Liikennepaikka	213+355	Lielähti–Kokemäki	Nokia	K		K
Skogby	Kilpilahti	Sgy		Seisake	184+790	Karjaa–Hanko	Raasepori			
Sköldvik		Sld		Liikennepaikka	56+360	Kerava–Sköldvik	Porvoo	M	K	K
Soinlahti		Soa		Liikennepaikka	559+651	Pieksämäki–Kontiomäki	Iisalmi		K	K
Sorsasalo		Sor		Liikennepaikka	473+754	Pieksämäki–Kontiomäki	Kuopio		K	
Sukeva		Skv		Liikennepaikka	589+222	Pieksämäki–Kontiomäki	Sonkajärvi	K		K
Suolahti		Suo		Liikennepaikka	417+796	Jyväskylä–Äänekoski	Äänekoski	K	K	K
Suonenjoki		Snj		Liikennepaikka	413+842	Pieksämäki–Kontiomäki, Suonenjoki–Yläkoski	Suonenjoki	K		K
Suoniemi		Snm		Liikennepaikka	220+655	Lielähti–Kokemäki	Nokia	K		
Syrjä		Syr		Liikennepaikka	452+865	Pieksämäki–Joensuu	Heinävesi			K
Syrjämäki		Ski		Liikennepaikka	341+621	Tampere–Seinäjoki	Seinäjoki	K		
Sysmäjärvi		Smj		Liikennepaikka	669+601	Sysmäjärvi–Vuonos, Siilinjärvi–Viinijärvi	Outokumpu	K	K	K
Säkäniemi		Sä		Liikennepaikka	480+242	Niirala–raja–Säkäniemi, Kouvola–Joensuu	Tohmajärvi	K		
Sänkimäki		Skm		Liikennepaikka	504+505	Siilinjärvi–Viinijärvi	Kuopio			K
Sääksjärvi		Sj		Liikennepaikka	177+734	Riihimäki–Tampere	Tampere	K		
Taavetti		Ta		Liikennepaikka	238+589	Kouvola–Joensuu	Luumäki	K	K	K
Tahkoluoto		Tko		Liikennepaikka	350+750	Pori–Mäntyluoto	Pori		K	K
Taipale		Te		Liikennepaikka	537+605	Pieksämäki–Kontiomäki	Iisalmi	K		
Talviainen		Tv		Liikennepaikka	247+245	Tampere–Jyväskylä	Orivesi	K		K
Talvivaara		Tlv		Liikennepaikka	637+700	Murtomäki–Talvivaara				
Tammisaari	Ekenäs	Tms		Seisake	174+056	Karjaa–Hanko	Raasepori			
<b>TAMPERE</b>		<b>Tre</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Riihimäki–Tampere, Tampere–Seinäjoki, Tampere–Jyväskylä</b>		<b>M</b>		
<i>Tampere tavara</i>		<i>Tpet</i>		<i>Liikennepaikan osa (Tampere)</i>	184+100		<i>Tampere</i>		K	K
<i>Tampere Viinikka</i>		<i>Vka</i>		<i>Liikennepaikan osa (Tampere)</i>	185+400		<i>Tampere</i>		K	K
<i>Tampere asema</i>	<i>Tammerfors</i>	<i>Tpe</i>	<i>Tampere asema</i>	<i>Liikennepaikan osa (Tampere)</i>	187+389		<i>Tampere</i>			K
<i>Tampere Järvensivu</i>		<i>Jvs</i>		<i>Liikennepaikan osa (Tampere)</i>	187+814		<i>Tampere</i>			
Tapanila	Mosabacka	Tna		Seisake	12+610	Helsinki–Riihimäki	Helsinki			
Tapavainola		Tap		Liikennepaikka	270+405	Kouvola–Joensuu	Lappeenranta	K		
Tavastila		Tsl		Seisake	228+854	Kouvola–Kotka	Kotka			
Tervajoki		Tk		Seisake	460+156	Seinäjoki–Vaasa	Isokyrö			
Tervola		Trv		Liikennepaikka	900+521	Laurila–Kemijärvi	Tervola	K		K
Teuva	Östermark	Tuv		Liikennepaikka	497+474	Seinäjoki–Kaskinen	Teuva	M		K
Tikkala		Tkk		Liikennepaikka	592+461	Kouvola–Joensuu	Tohmajärvi	K		
Tikkaperä		Tkp		Liikennepaikka	720+741	Seinäjoki–Oulu	Liminka	K		
<b>TIKKURILA</b>		<b>Tik</b>		<b>Osiin jaettu liikennepaikka</b>		<b>Helsinki–Riihimäki, Huopalahti–Havukoski</b>		<b>K</b>		
<i>Havukoski</i>		<i>Hvk</i>		<i>Liikennepaikan osa (Tikkurila)</i>	17+725		<i>Vantaa</i>			
<i>Hiekkaharju</i>	<i>Sandkulla</i>	<i>Hkh</i>		<i>Liikennepaikan osa (Tikkurila)</i>	17+109		<i>Vantaa</i>			
<i>Tikkurila asema</i>	<i>Dickursby</i>	<i>Tkl</i>		<i>Liikennepaikan osa (Tikkurila)</i>	15+861		<i>Vantaa</i>	K	K	K
Tohmajärvi		Toh		Liikennepaikka	571+752	Niirala–raja–Säkäniemi	Tohmajärvi	K		K
Toijala		Tl		Liikennepaikka	147+339	Toijala–Turku, Riihimäki–Tampere, Toijala–Valkeakoski	Akaa	K	K	K
Toivala		Toi		Liikennepaikka	479+162	Pieksämäki–Kontiomäki	Siilinjärvi	K		K
Tolsa	Tolls	Tol		Seisake	35+454	Helsinki–Turku satama	Kirkkonummi			

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö- mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår- anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Tommola		Tom		Liikennepaikka	117+197	Riihimäki–Kouvola	Hollola	K		
Torkkeli		Trk		Liikennepaikka	240+154	Tampere–Jyväskylä	Orivesi	K		
<b>TORNIO</b>		<b>Trn</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Tornio–Röyttä, Tornio–Kolari, Laurila–Tornio-raja</b>		<b>K</b>		
<i>Tornio asema</i>	<i>Torneå</i>	<i>Tor</i>	<i>Tornio</i>	<i>Liikennepaikan osa (Tornio)</i>	<i>884+656</i>		<i>Tornio</i>	<i>K</i>	<i>K</i>	<i>K</i>
<i>Tornio-raja</i>	<i>Torneå gränsen</i>	<i>Trr</i>		<i>Liikennepaikan osa (Tornio)</i>	<i>887+190</i>		<i>Tornio</i>			
Tornio–Itäinen	Torneå Östra	Tri		Seisake	883+307	Laurila–Tornio-raja	Tornio			
Tuomarila	Domsby	Trl		Seisake	19+022	Helsinki–Turku satama	Espoo			
Tuomioja		Tja		Liikennepaikka	698+504	Seinäjoki–Oulu, Tuomioja–Raahe	Siikajoki	K		K
Turenki		Tu		Liikennepaikka	93+771	Riihimäki–Tampere	Janakkala	K	K	K
<b>TURKU</b>		<b>Tur</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Helsinki–Turku satama, Toijala–Turku, Turku–Uusikaupunki</b>	<b>Turku</b>	<b>K</b>		
<i>Kupittaa</i>	<i>Kuppis</i>	<i>Kut</i>		<i>Liikennepaikan osa (Turku)</i>	<i>196+372</i>		<i>Turku</i>			
<i>Turku asema</i>	<i>Åbo</i>	<i>Tku</i>	<i>Turku päärautatieasema</i>	<i>Liikennepaikan osa (Turku)</i>	<i>199+674</i>		<i>Turku</i>		<i>K</i>	<i>K</i>
<i>Turku tavara</i>		<i>Tkut</i>		<i>Liikennepaikan osa (Turku)</i>	<i>200+460</i>		<i>Turku</i>		<i>K</i>	<i>K</i>
<i>Turku satama</i>	<i>Åbo hamn</i>	<i>Tus</i>		<i>Liikennepaikan osa (Turku)</i>	<i>202+510</i>		<i>Turku</i>		<i>K</i>	
Tuupovaara		Tpv		Liikennepaikka	668+672	Joensuu–Ilomantsi	Joensuu			K
Tuuri		Tuu		Seisake	366+962	Orivesi–Seinäjoki	Alavus			K
Törmä		Tör		Liikennepaikka	878+075	Laurila–Kemijärvi	Keminmaa	K		
Törölä		Trä		Liikennepaikka	264+972	Kouvola–Joensuu	Lappeenranta	K		
Uimaharju		Uim		Liikennepaikka	674+451	Joensuu–Nurmes	Joensuu	K	K	K
Urkala		Ur		Liikennepaikka	165+588	Toijala–Turku	Urkala	K		K
Utajärvi		Uti		Liikennepaikka	810+502	Oulu–Kontiomäki	Utajärvi	K		K
Utti		Uti		Linjavaihde	204+085	Kouvola–Joensuu	Kouvola			K
Uusikaupunki	Nystad	Ukp		Liikennepaikka	264+795	Uusikaupunki–Hangonsaari, Turku–Uusikaupunki	Uusikaupunki	K	K	K
Uusikylä		Ukä		Liikennepaikka	149+485	Riihimäki–Kouvola	Nastola	K		K
Vaajakoski		Vko		Liikennepaikka	384+866	Jyväskylä–Pieksämäki	Jyväskylä	K		K
Vaala		Vaa		Liikennepaikka	844+671	Oulu–Kontiomäki	Vaala	K		K
Vaarala		Vra		Linjavaihde	981+481	Laurila–Kemijärvi	Rovaniemi			K
Vaasa	Vasa	Vs		Liikennepaikka	492+588	Seinäjoki–Vaasa	Vaasa	K	K	K
Vahojärvi		Vjr		Liikennepaikka	244+926	Tampere–Seinäjoki	Parkano	K		
<b>VAINIKKALA</b>		<b>Vai</b>		<b>Osiin jaettu liikennepaikka</b>	–	<b>Luumäki–Vainikkala-raja</b>		<b>M</b>		
<i>Vainikkala tavara</i>		<i>Vnat</i>		<i>Liikennepaikan osa (Vainikkala)</i>	<i>281+700</i>		<i>Lappeenranta</i>		<i>K</i>	<i>K</i>
<i>Vainikkala asema</i>		<i>Vna</i>	<i>Vainikkala</i>	<i>Liikennepaikan osa (Vainikkala)</i>	<i>282+784</i>		<i>Lappeenranta</i>		<i>K</i>	<i>K</i>
Vainikkala-raja		Vnar		Liikennepaikka	284+862		Lappeenranta			
Valimo	Gjuteriet	Vmo		Seisake	7+480	Helsinki–Turku satama	Helsinki			
Valkeakoski		Vi		Liikennepaikka	164+952	Toijala–Valkeakoski	Valkeakoski	M	K	K
Valkeasuo		Vso		Linjavaihde	583+976	Niirala-raja–Säkäniemi	Tohmajärvi			K
Valtimo		Vlm		Liikennepaikka	808+636	Nurmes–Kontiomäki	Valtimo	M		K
Vammala		Vma		Liikennepaikka	245+885	Lielähti–Kokemäki	Sastamala	K		K
Vanattara		Vtr		Liikennepaikka	172+340	Riihimäki–Tampere	Lempäälä	K		
Vantaankoski	Vandaforsen	Vks		Seisake	14+907	Huopalahti–Havukoski	Vantaa			
Varkaus		Var		Liikennepaikka	424+685	Pieksämäki–Joensuu, Varkaus–Kommila	Varkaus	K	K	K
Vartius		Vus		Liikennepaikka	753+755	Kontiomäki–Vartius-raja	Kuhmo	M		K
Vartius-raja		Vur		Liikennepaikka	755+856	Kontiomäki–Vartius-raja	Kuhmo			

Rail Traffic Operating Points/Traffic Operating Points

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Liikenteenohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår-anläggningar	Möjlighet till växling
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Vasikkahaka	Veckal	Vkh		Liikennepaikka	31+175	Helsinki–Turku satama	Kirkkonummi	K		
Vaskiluoto		Vsk		Liikennepaikka	496+463	Vaasa–Vaskiluoto	Vaasa		K	K
Vehkala		Veh		Seisake	15+997	Huopalahti–Havukoski	Vantaa			
Venetmäki		Vki		Liikennepaikka	433+164	Jyväskylä–Pieksämäki	Pieksämäki	K		
Vesanka		Vn		Liikennepaikka	364+469	Haapamäki–Jyväskylä	Jyväskylä	K		
Vieki		Vk		Linjavaihde	753+979	Joensuu–Nurmes	Lieksa			K
Vierumäki		Vrm		Linjavaihde	153+801	Lahti–Heinola	Heinola			K
Vihanti		Vti		Liikennepaikka	684+573	Seinäjoki–Oulu	Raahe	K	K	K
Vihtari		Vih		Liikennepaikka	489+889	Pieksämäki–Joensuu	Heinävesi	K		K
Viiala		Via		Liikennepaikka	154+288	Riihimäki–Tampere	Akaa	K		K
Viinijärvi		Vnj		Liikennepaikka	656+569	Siilinjärvi–Viinijärvi, Pieksämäki–Joensuu	Liperi	K		K
Villähde		Vlh		Liikennepaikka	140+442	Riihimäki–Kouvola	Nastola	K		
Vilppula		Vlp		Liikennepaikka	274+760	Orivesi–Seinäjoki, Vilppula–Mänttä	Mänttä–Vilppula	K	K	K
Vinnilä		Vin		Liikennepaikka	131+243	Riihimäki–Tampere	Hämeenlinna	K		
Virkamies		Vms		Liikennepaikka	25+931	Huopalahti–Havukoski	Vantaa	K		
Voltti		Vt		Liikennepaikka	479+402	Seinäjoki–Oulu	Kauhava	K		K
Vuohijärvi		Vhj		Liikennepaikka	221+308	Kouvola–Pieksämäki	Kouvola	K		K
Vuojoki		Vjo		Liikennepaikka	318+501	Kokemäki–Rauma	Eurajoki	K		
Vuokatti		Vkt		Liikennepaikka	868+838	Nurmes–Kontiomäki, Vuokatti–Lahnaslampi	Sotkamo	M		K
Vuonisolahti		Vsl		Liikennepaikka	705+240	Joensuu–Nurmes	Lieksa	K		
Vuonos		Vns		Liikennepaikka	588+808	Sysmäjärvi–Vuonos	Outokumpu			K
Vuosaari		Vsa		Liikennepaikka	50+184	Kerava–Vuosaari	Helsinki	K	K	K
<b>YKSPIHLAJA</b>		<b>Yks</b>		<b>Ostien jaettu liikennepaikka</b>	–	<b>Kokkola–Ykspihlaja</b>				
Ykspihlaja tavara		Ykst		Liikennepaikan osa (Ykspihlaja)	553+900		Kokkola		K	K
Ykspihlaja väliratapiha		Yksv		Liikennepaikan osa (Ykspihlaja)	555+511		Kokkola		K	K
Ylistaro	Etseri	Yst		Seisake	439+558	Seinäjoki–Vaasa	Seinäjoki			
Ylitornio		Ytr		Seisake	946+139	Tornio–Kolari	Ylitornio			
Ylivall		Ylv		Liikennepaikka	302+016	Tampere–Seinäjoki	Kurikka	K	K	K
Ylivieska		Yv		Liikennepaikka	630+343	Iisalmi–Ylivieska, Seinäjoki–Oulu	Ylivieska	M	K	K
Yläkoski		Ylk		Liikennepaikka	416+849	Suonenjoki–Yläkoski	Suonenjoki	K	K	K
Ylämylly		Yly		Liikennepaikka	639+019	Pieksämäki–Joensuu	Liperi	K		K
Ylöjärvi		Ylö		Liikennepaikka	200+753	Tampere–Seinäjoki	Ylöjärvi	K		K
Ypykkävaara		Ypy		Liikennepaikka	729+780	Kontiomäki–Vartius-raj	Kuhmo	K		K
Äetsä		Äs		Liikennepaikka	258+280	Lielähti–Kokemäki	Sastamala	K		K
Ähtäri		Äht		Liikennepaikka	346+067	Orivesi–Seinäjoki	Ähtäri	K		K
Ämmänsaari		Äm		Liikennepaikka	750+448	Kontiomäki–Ämmänsaari	Suomussalmi	M		K
Äänekoski		Äki		Liikennepaikka	424+515	Jyväskylä–Äänekoski, Äänekoski–Haapajärvi	Äänekoski	K	K	K

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormaust-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Ahonpää				0	927	—	—	—	—	—	—	—	—	—	—
Ahvenus				0	747	—	—	—	—	—	—	—	—	—	—
Ainola	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
Airaksela				0	819	—	—	—	—	—	—	—	T	—	—
Aittaluoto				0	—	—	—	—	—	—	—	—	T	—	—
Ajos				0	—	—	—	—	Y	—	—	—	T	—	—
Alapitkä				0	664	25 A	18	—	K	—	—	—	T	—	—
Alavus	79	203	265	2	711	—	—	—	K	—	—	H	T	—	—
Alholma				0	—	—	—	—	Y	—	—	—	T	—	—
Arola				0	1087	25 A	24	—	K	—	—	—	T	—	—
Asola				0	—	—	—	—	—	—	—	—	—	—	—
Aviapolis	230	230	550	2	—	—	—	—	—	—	—	H	—	—	—
Dragsvik		70	550	1	925	—	—	—	—	—	—	H	—	—	—
Dynamiittivaihde				0	—	—	—	—	—	—	—	—	T	—	—
Eläinpuisto-Zoo		89	265	1	—	—	—	—	—	—	—	H	—	—	—
Eno		80	550	1	664	25 A	—	—	K	—	—	H	T	—	—
Ervelä				0	748	—	—	—	—	—	—	—	—	—	—
Eskola				0	780	—	—	—	—	—	—	—	—	—	—
Espoo	240	322	550	4	326	—	—	—	—	—	—	H	—	—	—
Haapajärvi		84	265	1	731	25 A	—	—	K Y	—	—	H	T	—	—
Haapakoski				0	725	—	—	—	K	—	—	—	—	—	—
Haapamäen kyllästämö				0	—	—	—	—	—	—	—	—	T	—	—
Haapamäki	188	325	265 (265)	3 (1)	644	63 A	128	—	K	—	—	H	T	Y	—
Haarajoki	220	220	550	2	240	—	—	—	—	—	—	H	—	—	—
Hakosilta				0	—	—	—	—	—	—	—	—	—	—	—
Haksi		20	265	1	—	—	—	—	—	—	—	—	—	—	—
Hamina				0	834	25 A	18	K	Y	—	Y	—	T	—	K
Hammassahti				0	686	—	—	—	Y	—	—	—	T	—	—
Hanala				0	—	—	—	—	—	—	—	—	—	—	—
Hangonsaari				0	—	—	—	—	—	—	—	—	T	—	—
Hanhikoski				0	—	—	20	—	K	—	—	—	T	—	—
Hankasalmi	233	289	265	2	754	25 A	20	K	K Y	—	—	H	T	—	—
<b>HANKO</b>															
Hanko asema		100	550	1	274	63 A	113	K	—	—	Y	H	—	—	—
Hanko tavara				0	737	—	—	—	—	—	—	—	T	—	—
Hanko-Pohjoinen		68	550	1	—	—	—	—	—	—	—	H	—	—	—
Harjavalta	250	250	550	2	766	25 A	—	—	K	—	—	H	T	—	—
Harju				0	786	—	—	—	—	—	—	—	—	—	—
Harviala				0	—	—	—	—	—	—	—	—	—	—	—
Haukipudas				0	833	—	11	—	K	—	—	—	—	—	—
Haukivuori	(199)	(200)	(265)	(2)	891	—	—	—	K	—	—	—	T	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormaust-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattform-längden	Längsta plattform-längden	Plattform-höjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
<b>HAUSJÄRVI</b>															
<i>Hausjärvi tavara</i>				0	656	—	—	—	K	Y	—	—	—	—	—
<i>Oitti</i>	102	102	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Haviseva</i>				0	—	—	—	—	—	—	—	—	—	—	—
<i>Heikkilä</i>				0	—	—	—	—	—	—	—	—	—	—	—
<i>Heinola</i>		(107)	(265)	(1)	613	—	15	—	K	—	—	—	T	—	—
<i>Heinoo</i>				0	734	—	—	—	—	—	—	—	—	—	—
<i>Heinävaara</i>				0	—	—	—	—	K	—	—	—	T	—	—
<i>Heinävesi</i>	100	206	265	2	570	—	9	—	K	—	—	H	T	—	—
<b>HELSINKI</b>															
<i>Helsinki asema</i>	244	456	550	19	455	—	—	—	—	—	—	H	—	—	—
<i>Pasila asema</i>	319	435	550	10	-	—	—	—	—	—	—	H	—	22	—
<i>Pasila autojuna-asema</i>	450	450	550	2	—	63 A	—	K	—	—	—	H	—	—	—
<i>Ilmala asema</i>	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Helsinki Kivihaka</i>				0	—	—	—	—	—	—	—	—	—	—	—
<i>Pasila tavara</i>				0	727	63 A	230	K	K Y	—	—	—	T	—	—
<i>Ilmala ratapiha</i>				0	—	1500 V, 63 A	29	—	—	—	Y	—	—	—	—
<i>Käpylä</i>	279 (278)	336	550 (265)	3 (2)	—	—	—	—	—	—	—	H	—	—	—
<i>Oulunkylä</i>	266	266	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Herrala</i>	110	110	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Hirola</i>				0	760	—	—	—	—	—	—	—	—	—	—
<i>Hikiä</i>	120	120	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Hillosensalmi</i>		(165)	(550)	(1)	797	—	—	—	—	—	—	—	—	—	—
<i>Hinthaara</i>	(55)	(65)	(265)	(3)	—	—	—	—	—	—	—	—	—	—	—
<i>Hirvineva</i>				0	753	—	—	—	—	—	—	—	—	—	—
<i>Humppila</i>	245	427	550	3	753	25 A	29	—	Y	—	—	H	T	—	—
<i>Huopalahti</i>	270	270	550	4	—	—	—	—	—	—	—	H	—	—	—
<i>Huutokoski</i>				0	659	—	—	—	—	—	—	—	—	—	—
<i>Hyrnsalmi</i>		(100)	(265)	(1)	734	25 A	12	—	K	—	—	—	T	—	—
<i>Hyvinkää</i>	104	332	550 (265)	3 (1)	814	25 A	20	—	—	—	—	H	T	20	—
<i>Hämeenlinna</i>	257	450	550	3	1038	25 A	34	K	K	—	—	H	T	—	—
<i>Härmä</i>				0	808	—	—	—	K	—	—	—	T	—	—
<i>Höljäkkä</i>		60	265	1	—	—	—	—	K Y	—	—	H	T	—	—
<i>Ii</i>		(92)	(265)	(1)	687	—	—	—	K	—	—	—	—	—	—
<i>Iisalmen teollisuusraiteet</i>				0	—	—	—	—	Y	—	—	—	T	—	—
<i>Iisalmi</i>	70	353	265	3	734	1500 V, 63 A	58	K	Y	—	Y	H	T	Y	—
<i>Iittala</i>	170	170	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Ilola</i>					—	—	—	—	—	—	—	H	—	—	—
<i>Ilomantsi</i>				0	771	25 A	—	—	K	—	—	—	T	—	—
<b>IMATRA</b>															
<i>Imatra asema</i>		450	265	1	—	—	—	—	—	—	—	H	—	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormauskenttä	Nosturi	Polttoaine	Henkilöliikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
<i>Imatra tavara</i>		(218)	(265)	(1)	889	1500 V, 63 A	—	—	K Y	—	Y	—	T	Y	—
<i>Imatrankoski</i>				0	1197	—	18	K	K	—	—	—	T	—	—
<i>Pelkola</i>				0	1373	—	—	—	—	—	—	—	T	—	—
<i>Imatrankoski-raja</i>				0	—	—	—	—	—	—	—	—	T	—	—
<i>Inha</i>		(99)	(265)	(1)	—	—	42	—	K	—	—	—	T	—	—
<i>Inkeroinen</i>	120	172	265	3	792	—	21	—	K	—	—	H	T	—	—
<i>Inkoo</i>	100	170	550	2	243	25 A	14	—	—	—	—	H	—	—	—
<i>Isokyrö</i>	110	150	550, 265	2	509	—	—	—	K	—	—	H	T	—	—
<i>Jalasjärvi</i>		(51)	(550)	(1)	762	—	28	—	K	—	—	—	T	—	—
<i>Jepua</i>				0	825	—	16	—	K	—	—	—	—	—	—
<b>JOENSUU</b>															
<i>Joensuu asema</i>	239	377	265	3	561	1500 V, 63 A	46	—	K	—	—	H	T	20, Y	K
<i>Joensuu Peltola</i>				0	621	—	—	—	K Y	—	—	—	T	—	K
<i>Joensuu Sulkolahti</i>				0	692	—	—	—	—	—	—	—	T	—	K
<i>Jokela</i>	313	321	550	3	821	—	—	—	—	—	—	H	—	—	—
<i>Joroinen</i>				0	—	—	—	—	K	—	—	—	T	—	—
<i>Jorvas</i>	97	124	265	2	—	—	—	—	—	—	—	H	—	—	—
<i>Joutseno</i>	460	460	550	2	811	—	—	—	K	—	—	H	T	—	—
<i>Juankoski</i>				0	583	25 A	13	—	K	—	—	—	T	—	—
<i>Jutila</i>				0	—	—	—	—	—	—	—	—	—	—	—
<i>Juupajoki</i>		80	550	1	—	—	—	—	—	—	—	H	—	—	—
<i>Juurikorpi</i>				0	789	—	—	—	—	—	—	—	—	—	—
<i>Jyväskylä</i>	160	449	550	4	796	1500 V, 63 A	89	K	Y	Y	Y	H	T	—	—
<i>Jämsä</i>	387	387	550	2	769	25 A	—	—	K	—	—	H	T	—	—
<i>Jämsänkoski</i>				0	873	—	—	—	—	—	—	—	T	20	—
<i>Järvelä</i>	122	122	550	3	630	—	12	—	K	—	—	H	T	—	—
<b>JÄRVENPÄÄ</b>															
<i>Järvenpää asema</i>	345	393	550	3	—	—	29	K	—	—	—	H	T	—	—
<i>Saunakallio</i>	180	275	265, 550	4	614	—	—	—	—	—	—	H	T	—	—
<i>Purola</i>	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Kaipiainen</i>				0	770	—	19	—	Y	—	—	—	T	—	—
<i>Kaipola</i>				0	—	—	—	—	—	—	—	—	T	—	—
<i>Kairoskoski</i>				0	—	—	16	—	K	—	—	—	—	—	—
<i>Kaitjärvi</i>				0	1110	—	—	—	—	—	—	—	—	—	—
<i>Kajaani</i>	350	350	265	2	837	1500 V, 63 A	122	—	K	—	—	H	T	—	—
<i>Kaleton</i>				0	—	—	27	—	K	—	—	—	—	—	—
<i>Kalkku</i>				0	—	—	100	—	Y	—	—	—	T	—	—
<i>Kalliovarasto</i>				0	—	—	—	—	—	—	—	—	—	—	—
<i>Kalvitsa</i>				0	864	—	—	—	K	—	—	—	T	—	—
<i>Kangas</i>				0	933	—	—	—	—	—	—	—	—	—	—
<i>Kannelmäki</i>	226	226	550	2	—	—	—	—	—	—	—	H	—	—	—



Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaiturin, suurin pituus	Päätylaituri	Kuormauskenttä	Nosturi	Polttoaine	Henkilöliikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Kannonkoski				0	—	—	13	—	K	—	—	—	T	—	—
Kannus	339	420	265	2	817	—	—	—	—	—	—	H	—	—	—
Karhejärvi				0	778	25 A	4	—	K	—	—	—	—	—	—
Karhukangas				0	840	—	—	—	—	—	—	—	—	—	—
Karjaa	249	352	550	4	765	63 A	—	—	K	—	Y	H	T	20	—
Karkku		250	550	1	856	—	—	—	—	—	—	H	—	—	—
Karviainen				0	745	—	—	—	—	—	—	—	—	—	—
Kaskinen				0	843	—	—	—	Y	—	—	—	T	Y	—
Kattilaharju				0	—	—	—	—	—	—	—	—	—	—	—
Kauhajoki				0	—	—	—	—	—	—	—	—	—	—	—
Kauhava		450	550	1	803	—	—	—	K	—	—	H	T	—	—
<b>KAUKLAHTI</b>															
Kauklahti asema	270	270	550	3	447	—	—	—	—	—	—	H	—	—	—
Mankki	126	136	550, 265	2	—	—	—	—	—	—	—	H	—	—	—
Kaulinranta				0	—	—	—	—	—	—	—	—	—	—	—
Kauniainen	194	204	265	3	269	—	—	—	—	—	—	H	T	—	—
Kaupplanmäki				0	-	—	—	—	K	—	—	—	T	—	—
Kausala	120	120	550	2	—	—	—	—	—	—	—	H	—	—	—
Keitelepoija				0	—	—	—	—	K	—	—	—	T	—	—
Kekomäki				0	—	—	—	—	—	—	—	—	—	—	—
Kemi	450	450	265, 550	2	949	63 A	148	—	K	—	Y	H	T	Y	—
Kemijärvi		352	265	1	501	1500 V, 63 A	6	K	K Y	—	—	H	T	—	—
Kempele		450 (119)	550(265)	1 (1)	762	25 A	9	—	K	—	—	H	—	—	—
Kera	216	224	265	2	—	—	—	—	—	—	—	H	—	—	—
<b>KERAVA</b>															
Kerava asema	270	392	550	4	—	25 A	—	—	—	—	Y	H	—	20, KR	—
Kytömaa				0	—	—	—	—	—	—	—	—	—	—	—
Kerimäki		108	265	1	398	—	—	—	K	—	—	H	T	—	—
Kesälahti		322	265	1	671	—	—	—	—	—	—	H	T	—	—
Keuruu		111	550	1	676	—	—	—	K	—	—	H	T	—	—
Kiiiala		49	265	1	—	—	—	—	—	—	—	H	—	—	—
Kilo	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
Kilpua				0	750	25 A	—	—	—	—	—	—	—	—	—
Kinahmi				0	—	—	—	—	—	—	—	—	—	—	—
Kinni				0	776	—	—	—	—	—	—	—	—	—	—
Kirjola				0	—	—	—	—	Y	—	—	—	—	—	—
Kirkkonummi	316	322	550	3	612	—	—	—	K	—	—	H	—	—	—
Kirkniemi				0	585	—	—	—	—	—	—	—	T	—	—
Kitee		355	265	1	660	25 A	18	—	K Y	—	—	H	T	—	—
Kiukainen				0	768	—	14	—	K	—	—	—	—	—	—
Kiuruvesi		126	265	1	638	25 A	80	—	K Y	—	—	H	T	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormauskenttä	Nosturi	Polttoaine	Henkilöliikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Kivesjärvi		(54)	(265)	(1)	1118	—	—	—	—	—	—	—	—	—	—
Kivistö	292	336	550	2	—	—	—	—	—	—	—	H	—	—	—
Kohtavaara		56	265	1	—	—	—	—	—	—	—	H	—	—	—
Koivu		(40)	(265)	(1)	617	—	32	—	K	—	—	—	T	—	—
Koivuhovi	278	278	550	2	—	—	—	—	—	—	—	H	—	—	—
Koivukylä	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
Kokemäki	249	249	550	3	765	25 A	29	—	K	—	—	H	T	—	—
Kokkola	308	482	265	3	829	1500 V, 63 A	40	—	Y	—	Y	H	T	Y	K
Kolari		451	550	1	790	63 A	22	K	K Y	—	—	H	T	—	—
Kolho		80	550	1	—	—	—	—	Y	—	—	H	T	—	—
Kolppi				0	765	—	—	—	—	—	—	—	—	—	—
Kommila				0	733	25 A	—	—	Y	—	—	—	T	—	—
Komu				0	—	—	—	—	Y	—	—	—	—	—	—
Kontiolahti		(96)	(265)	(1)	577	25 A	—	K	—	—	—	—	T	—	—
Kontiomäki	351	349	265	3	853	63 A	31	K	K	—	Y	H	T	Y, KR	—
Koria	120	120	550	2	—	—	—	—	—	—	—	H	—	—	—
Korkeakoski		(72)	(265)	(1)	747	—	—	K	K	—	—	—	T	—	—
Korso	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
Korvensuo				0	—	—	—	—	—	—	—	—	—	—	—
Koskenkorva				0	—	—	—	—	—	—	—	—	T	—	—
<b>KOTKA</b>															
Kotka Hovinsaari				0	865	63 A	85	—	—	—	—	—	T	—	—
Kotka tavana				0	—	—	—	—	—	—	—	—	T	—	—
Paimenportti		53	265	1	—	—	—	—	—	—	—	H	—	—	—
Kotka asema		193	265	1	270	63 A	—	—	—	—	—	H	—	Y	—
Kotkan satama		110	265	1	539	63 A	280	—	K	—	Y	H	T	—	—
Kotolahti				0	1139	—	—	—	—	—	—	—	T	—	—
Kotka Mussalo				0	1005	—	25	—	Y	—	—	—	T	—	K
<b>KOUVOLA</b>															
Kouvola asema	230	480	550	7	600	1500 V, 63 A	—	—	K	—	Y	H	—	Y	—
Kouvola lajittelu				0	992	25 A	175	K	—	—	—	—	T	—	K
Kouvola Oikoraide				0	—	—	—	—	—	—	—	—	—	KR	—
Kouvola tavana				0	903	—	11	—	Y	—	—	—	T	—	K
Kullasvaara				0	1364	—	—	—	—	—	—	—	T	—	—
Kovjoki				0	757	—	—	—	—	—	—	—	—	—	—
Kruunupyy				0	747	—	49	—	K	—	—	—	T	—	—
Kuivasjärvi				0	781	—	—	—	K	—	—	—	—	—	—
<b>KUOPIO</b>															
Kuopio asema	90	387	265	4	273	63 A	130	K	Y	—	—	H	—	—	—
Kuopio tavana				0	804	1500 V, 63 A	100	—	Y	—	Y	—	T	Y	—
Kurkimäki				0	734	—	—	—	K	—	—	—	T	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraiteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuorma-us-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat		
Namn	Kortaste plattform-längden	Längsta plattform-längden	Plattform-höjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för fartiga ämnen		
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods		
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]							
Kuuriila	32			0	—	—	—	—	—	—	—	—	—	—	—		
Kuusankoski				0	811	63 A	Y	—	Y	—	—	—	T	—	—		
Kylänlahti		56	265	1	—	—	—	—	—	—	—	H	—	—	—		
Kymi		66	265	2	759	—	—	—	—	—	—	H	—	—	—		
Kyminlinna		120	550	1	—	—	—	—	—	—	—	H	—	—	—		
Kyrö				0	739	—	—	—	K	—	—	—	T	—	—		
Kälviä				0	—	—	—	—	—	—	—	—	—	—	—		
Köykkäri				0	763	—	—	—	—	—	—	—	—	—	—		
Laajavuori				0	—	—	—	—	—	—	—	—	—	—	—		
Lahdenperä				0	777	—	—	—	—	—	—	—	—	—	—		
Lahnaslampi			0	—	25 A	—	—	—	—	—	—	—	T	—	—		
Lahti	270	451	265	4	709	63 A	7	K	Y	—	—	H	T	20, KR	—		
Laihia		201	265	1	456	—	—	—	K	—	—	H	T		—		
Lakiala				0	733	—	—	—	—	—	—	—	—		—		
Lamminkoski				0	742	—	—	—	—	—	—	—	—		—		
Lamminniemi				0	—	—	145	—	—	—	—	—	T		—		
Lapinjärvi				0	—	—	12	—	K	—	—	—	T		—		
Lapinlahti		300	354	265	2	759	25 A	—	—	K	—	—	H		T	—	
Lapinneva					0	—	—	—	—	K	—	—	—		—	—	
Lappeenranta			430	450	265, 550	3	739	25 A	60	K	Y	—	Y		H	T	22
Lappila			60	60	550	2	—	—	—	—	—	—	H		—	—	
Lappohja			70	550	1	748	—	—	—	—	—	H	T	—			
Lapua			438	265	1	766	—	—	—	K	—	—	H	T	—		
Larvakytö				0	932	—	—	—	—	—	—	—	—	—	—		
Laukaa				0	—	—	—	—	K	—	—	—	—	—	—		
Laurila				0	618	—	—	—	—	—	—	—	—	—	—		
Lauritsala				0	657	—	—	—	K	—	—	—	T	—	—		
Lautiosaari			0	—	—	—	—	—	—	—	—	—	—	—			
Leinelä	266	266	550	2	—	—	—	—	—	—	—	H	—	—			
Lentoasema	230	230	550	2	—	—	—	—	—	—	—	H	—	—			
Leikola			0	802	—	—	—	—	—	—	—	—	—	—			
Lempäälä	170	170	550	2	772	—	—	—	—	—	—	H	—	—			
Leppäkoski			0	—	—	—	—	—	—	—	—	—	—	—			
Leppävaara	266	292	550	4	—	—	—	—	—	—	—	H	—	—			
Leteensuo			0	—	—	—	—	—	—	—	—	—	—	—			
Liekša		151	265	1	677	25 A	24	K	K	—	Y	H	T	20			
Lieksan teollisuuskylä			0	—	—	—	20	—	—	—	—	—	T	—			
Lielähti			0	780	—	—	8	—	—	—	—	—	T	—			
Lievestuore		(259)	(265)	(1)	824	25 A	23	—	K	—	—	—	T	—			
Liminka			0	739	—	—	—	—	—	—	—	—	—	—			
Lohiluoma			0	—	—	—	—	—	—	—	—	—	—	—			

[illegible]

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormauskenttä	Nosturi	Polttoaine	Henkilöliikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Mynämäki		(124)	(265)	(1)	495	—	—	—	—	—	—	—	—	—	—
Myyrmäki	231	231	550	2	—	—	—	—	—	—	—	H	—	—	—
Mäkkylä	270	288	550	2	—	—	—	—	—	—	—	H	—	—	—
Mäntsälä	220	220	550	2	998	—	—	—	—	—	—	H	—	—	—
Mänttä				0	553	—	—	—	K	—	—	—	T	—	—
Mäntyharju	457	457	550	2	989	—	159	—	K	—	—	H	T	—	—
Mäntyluoto				0	779	—	—	—	Y	—	—	—	T	—	—
Naantali				0	393	—	20	—	—	—	—	—	T	—	—
Naarajärvi				0	770	—	—	—	K	—	—	—	T	—	—
Nakkila				0	733	—	—	—	—	—	—	—	—	—	—
Nastola	120	120	550	2	—	—	—	—	—	—	—	H	—	—	—
Niemenpää				0	—	—	—	—	—	—	—	—	—	—	—
Niinimaa				0	—	—	—	—	K	—	—	—	—	—	—
Niinimäki				0	1077	—	—	—	—	—	—	—	—	—	—
Niinisalo				0	—	—	21	—	K	—	—	—	—	—	—
Niirala		(42)	(265)	(1)	987	25 A	—	—	K	—	—	—	T	—	K
Niirala-raja				0	—	—	—	—	—	—	—	—	T	—	—
Niittylahti				0	695	—	—	—	—	—	—	—	—	—	—
Nikkilä		(30)	(265)	(1)	—	—	—	—	—	—	—	—	—	—	—
Nivala		97	265	1	825	25 A	—	—	K	—	—	H	T	—	—
Nokia		250	550	1	865	—	120	—	K	—	—	H	T	—	—
Nummela				0	328	—	—	—	K	—	—	—	T	—	—
Nuppulinna	210	240	550	2	—	—	—	—	—	—	—	H	—	—	—
Nurmes	71	205	265	2	850	25 A	50	K	—	—	—	H	T	18	—
Närpiö				0	—	—	—	—	—	—	—	—	—	—	—
Ohenmäki				0	—	—	—	—	K	—	—	—	—	—	—
Olli				0	—	—	—	—	—	—	—	—	—	—	—
Onttola				0	—	—	—	—	—	—	—	—	T	—	—
Orimattila				0	—	—	12	—	K	—	—	—	T	—	—
Orivesi	273	360	550	3	765	25 A	—	—	K	—	Y	H	T	13,7	—
Orivesi keskusta		80	550	1	—	—	—	—	—	—	—	H	—	—	—
Otanmäki				0	—	—	—	—	K	—	—	—	T	—	—
Otava		(152)	(265)	(1)	735	—	—	—	K	—	—	—	T	—	—
Otavan satama				0	—	—	—	—	—	—	—	—	—	—	—
Oulainen	450	492	550	3	864	25 A	80	—	K	—	—	H	T	—	—
<b>OULU</b>															
<i>Oulu Nokela</i>				0	990	63 A	—	—	—	—	Y	—	T	—	—
<i>Oulu Oritkari</i>				0	—	63 A	200	—	Y	—	—	—	T	—	—
<i>Oulu tavara</i>				0	769	25 A	6	—	—	—	—	—	T	Y	—
<i>Oulu asema</i>	362	498	550, 265	3	488	1500 V, 63 A	—	K	—	—	—	H	—	—	—
<i>Oulu Tuira</i>				0	759	—	66	—	K	—	—	—	T	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormaust-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattform-längden	Längsta plattform-längden	Plattform-höjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplatt-form	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Paimio				0	763	—	—	—	—	—	—	—	—	—	—
Palopuro				0	—	—	—	—	—	—	—	—	—	—	—
Paltamo		231	265	1	664	25 A	—	—	K	—	—	H	T	—	—
Pankakoski				0	—	—	—	—	K Y	—	—	—	T	—	—
Parikkala	294	379	265	3	705	25 A	30	K	—	—	—	H	—	—	—
Parkano	600	600	550	3	943	25 A	10	—	K Y	—	Y	H	T	—	—
Parola	180	192	550	2	923	—	31	Y	K	—	—	H	T	—	—
Patokangas				0	772	—	—	—	Y	—	—	—	T	—	—
Pello		454	265	1	585	25 A	35	—	Y	—	—	H	T	—	—
Peltosalmi				0	—	25 A	—	—	K	Y	—	—	T	—	—
Peräseinäjoki				0	762	—	16	—	K	—	—	—	T	—	—
Pesiökylä		(74)	(265)	(1)	—	—	—	—	—	—	—	—	—	—	—
Petäjävesi		142	265	1	762	—	—	—	K	—	—	H	T	—	—
<b>PIEKSÄMÄKI</b>															
<i>Pieksämäki asema</i>	332	611	265	4	499	1500 V, 63 A	5	—	Y	—	—	H	—	—	—
<i>Pieksämäki Temu</i>				0	947	63 A	—	—	K Y	—	Y	—	—	KR	—
<i>Pieksämäki lajittelu</i>				0	875	—	—	—	—	—	—	—	T	—	—
<i>Pieksämäki tavara</i>				0	775	—	—	—	—	—	—	—	T	—	—
Pietarsaari				0	706	25 A	—	—	—	—	—	—	T	—	—
Pihlajavesi	99	120	265, 550	2	546	—	—	—	—	—	—	H	—	—	—
Pihtipudas				0	—	—	—	—	K	—	—	—	T	—	—
Piikkiö				0	303	—	—	—	K	—	—	—	T	—	—
Pikkarala				0	759	—	—	—	—	—	—	—	—	—	—
Pitäjänmäki	270	306	550	2	—	—	—	—	—	—	—	H	—	—	—
Pohjankuru				0	301	—	—	—	K	—	—	—	T	—	—
Pohjois-Haaga	240	240	550	2	—	—	—	—	—	—	—	H	—	—	—
Pohjois-Louko				0	—	—	—	—	—	—	—	—	—	—	—
Poikkeus				0	715	—	—	—	—	—	—	—	—	—	—
Poiksilta				0	—	—	—	—	K	—	—	—	T	—	—
Pori	251	251	550	2	733	—	—	—	Y	—	—	H	T	—	—
Porokylä				0	—	—	—	—	K	—	—	—	T	—	—
Porvoo		118	265	1	—	—	—	—	—	—	—	H	—	Y	—
Puhos				0	648	25 A	13	—	K	—	—	—	T	—	—
Puistola	274	274	550	2	—	—	—	—	—	—	—	H	—	—	—
Pukinmäki	273	279	550	2	—	—	—	—	—	—	—	H	—	—	—
Pulsa				0	1834	—	—	—	—	—	—	—	—	—	—
Punkaharju		201	265	1	435	25 A	—	—	K	—	—	H	T	—	—
Pyhäkumpu				0	366	—	9	—	—	—	—	—	T	—	—
Pyhäkumpu erkanemisvaihe				0	—	—	—	—	—	—	—	—	—	—	—
Pyhäsalmi		105	265	1	666	25 A	—	—	K	—	—	H	T	—	—
Pännäinen	450	450	550	2	750	—	—	—	—	—	—	H	—	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri- korkeus	Laituriraiteiden lukumäärä	Mitoittava raidepituus (tavara-liikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuorma- kenttä	Nosturi	Polttoaine	Henkilö- liikennettä	Tavara- liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat		
Namn	Kortaste plattform- längden	Längsta plattform- längden	Plattform- höjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplatt- form	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för fartiga ämnen		
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods		
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]							
Raahe	(111)	(168)	(265)	0	1147	63 A	53	—	K	—	—	—	T	—	—		
Raippo				0	1847	—	144	—	—	—	—	—	—	T	—	—	
Raisio				0	—	—	—	—	—	—	—	—	—	T	—	—	
Rajamäki				0	—	—	—	—	—	K	—	—	—	T	—	—	
Rajaperkiö				0	746	—	—	—	—	—	—	—	—	—	—	—	
Rantasalmi				0	784	—	—	—	—	K	—	—	—	—	T	—	—
Rasinsuo				0	740	—	—	—	—	—	—	—	—	—	—	—	—
Ratikylä				0	748	—	—	—	—	K	—	—	—	—	T	—	—
Rauha				0	791	—	—	—	—	K	—	—	—	—	T	—	—
Rauhalahti	0	—	—	—	—	—	—	—	—	—	—	T	—	—			
Rauma	0	916	25 A	15	K	Y	—	—	—	—	—	T	—	—			
Raunio	0	759	—	—	—	—	—	—	—	—	—	—	—	—			
Rautaruukki	0	—	—	—	—	—	—	—	—	—	—	—	T	—	—		
Rautjärvi	0	784	—	—	—	—	—	—	—	—	—	—	—	—	—		
Rautpohja	0	—	—	—	—	—	—	—	Y	—	—	—	T	—	—		
Rekola	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—		
Retretti		121	265	1	—	—	—	—	—	—	—	H	—	—	—		
<b>RIIHIMÄKI</b>																	
Riihimäki Arolampi				0	—	—	—	—	—	—	—	—	—	—	K		
Riihimäki lajittelu				0	719	—	—	—	—	—	—	—	T	—	K		
Riihimäki tavara				0	997	—	—	—	K Y	—	—	—	T	—	K		
Riihimäki asema	392	417	550, 265	5	643	1500 V, 63 A	26	—	—	—	Y	H	—	Y	K		
Riijärvi				0	757	—	—	—	—	—	—	—	—	—	—		
Riippa				0	968	—	—	—	—	—	—	—	—	—	—		
Ristiina				0	765	—	—	—	K	—	—	—	T	—	—		
Ristijärvi				0	—	—	—	—	—	—	—	—	—	—	—		
Rovaniemi	443	484	550, 265	3	731	1500 V, 63 A	188	K Y	Y	—	Y	H	T	20	—		
Ruha				0	—	—	—	—	—	—	—	—	—	—	—		
Runni		36	550	1	—	—	—	—	—	—	—	H	—	—	—		
Ruukki		454	550	1	738	—	—	—	K	—	—	H	T	—	—		
Ruusumäki				0	—	—	—	—	—	—	—	—	—	—	—		
Ryttylä	171	173	550	2	—	—	7	—	K	—	—	H	T	—	—		
Röyttä				0	—	25 A	—	—	K	—	—	—	T	—	—		
Saakoski				0	816	25 A	5	—	—	—	—	—	—	—	—		
Saari		(201)	(265)	(1)	692	—	—	—	—	—	—	H	T	—	—		
Saarijärvi		(69)	(265)	(1)	—	—	40	K	K	—	—	—	T	—	—		
Salminen				0	736	—	—	—	K	—	—	—	—	—	—		
Salo	306	308	550	3	380	—	—	K	K	—	—	H	T	—	—		
Sammalisto				0	—	—	—	—	—	—	—	—	—	—	—		
Santala		70	550	1	—	—	—	—	—	—	—	H	—	—	—		
Saunamäki				0	—	—	—	—	—	—	—	—	—	—	—		

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri- korkeus	Laituriraiteiden lukumäärä	Mitoittava raidepituus (tavara liikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuorma- kenttä	Nosturi	Polttoaine	Henkilö- liikennettä	Tavara- liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattform- längden	Längsta plattform- längden	Plattform- höjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplatt- form	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för fartiga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Savio	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
SAVONLINNA															
Savonlinna asema		90	550	1	—	—	—	—	—	—	—	H	—	—	—
Pääskylahdi		90	550	1	663	63 A	—	—	—	—	Y	H	—	—	—
SEINÄJOKI															
Seinäjäki tavara				0	861	25 A	40	—	K	—	—	—	T	Y	—
Seinäjäki asema	396	459	550, 265	4	478	1500 V, 63 A	65	—	Y	—	Y	H	T	21	—
Selänpää				0	772	—	—	—	—	—	—	—	—	—	—
Sieppijärvi				0	—	—	—	—	K	—	—	—	T	—	—
Sievi				0	743	—	—	—	—	—	—	—	—	—	—
Siikamäki				0	—	—	—	—	—	—	—	—	—	—	—
SIILIJÄRVI															
Siilinjärvi asema	156	360	265	2	702	25 A	—	—	K	—	—	H	T	KR	—
Ruokosuo				0	—	—	—	—	—	—	—	—	T	KR	—
Simo		(88)	(265)	(1)	990	—	46	—	K	—	—	—	—	—	—
Simpele	247	301	265	3	796	25 A	17	—	K	—	—	H	T	—	—
Sipilä				0	—	—	—	—	—	—	—	—	—	—	—
Sisättö				0	757	—	—	—	—	—	—	—	—	—	—
Siuntio	112	176	550	2	513	—	—	—	—	—	—	H	—	—	—
Siuro		(113)	(265)	(1)	703	—	—	—	K	—	—	—	—	—	—
Skogby		68	550	1	—	—	—	—	—	—	—	H	—	—	—
Sköldvik				0	945	25 A	—	—	—	—	—	—	T	—	K
Soinlahti				0	—	—	—	—	K	—	—	—	T	—	—
Sorsasalo				0	—	—	—	—	—	—	—	—	T	—	—
Sukeva	181	239	550, 265	2	624	25 A	—	—	K	—	—	—	T	—	—
Suolahti	(80)	(147)	(265)	(2)	676	25 A	—	—	K	—	—	—	T	—	—
Suonenjoki	250	341	265	3	822	25 A	—	—	K	—	—	H	T	20	—
Suoniemi				0	743	—	—	—	—	—	—	—	—	—	—
Syrjä				0	—	—	5	—	—	—	—	—	—	—	—
Syrjämäki				0	—	—	—	—	—	—	—	—	—	—	—
Sysmäjärvi				0	—	—	—	—	K	—	—	—	T	—	—
Säkäniemi				0	—	—	—	—	—	—	—	—	—	—	—
Sänkimmäki				0	—	—	—	—	K	—	—	—	T	—	—
Sääksjärvi				0	—	—	—	—	—	—	—	—	—	—	—
Taavetti				0	723	—	18	—	—	—	—	—	T	—	—
Tahkoluoto				0	—	—	—	—	Y	—	—	—	T	—	—
Taipale				0	829	—	—	—	—	—	—	—	—	—	—
Talviainen				0	732	25 A	—	—	—	—	—	—	—	—	—
Talvivaara				0	614	—	—	—	—	—	—	—	T	—	—
Tammisaari		80	550	1	—	—	—	—	—	—	—	H	—	—	—
TAMPERE															



Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormauskenttä	Nosturi	Polttoaine	Henkilöliikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
<i>Tampere tavara</i>				0	767	1500 V, 63 A	15	—	—	Y	Y	—	T	22	—
<i>Tampere Viinikka</i>				0	966	25 A	134	K	Y	—	—	—	T	—	K
<i>Tampere asema</i>	500	500	550	5	693	1500 V, 63 A	—	K	—	—	—	H	—	—	—
<i>Tampere Järvensivu</i>				0	—	—	—	—	—	—	—	—	—	KR	—
<i>Tapanila</i>	272	272	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Tapavainola</i>				0	748	—	—	—	—	—	—	—	—	—	—
<i>Tavastila</i>		47	265	1	—	—	—	—	—	—	—	H	—	—	—
<i>Tervajoki</i>		171	265	1	—	—	—	—	—	—	—	H	—	—	—
<i>Tervola</i>	231	301	265	2	709	25 A	11	—	K	—	—	H	—	—	—
<i>Teuva</i>				0	—	25 A	—	—	K	—	—	—	T	—	—
<i>Tikkala</i>				0	1029	—	—	—	—	—	—	—	—	—	—
<i>Tikkaperä</i>				0	925	—	—	—	—	—	—	—	—	—	—
<b>TIKKURILA</b>															
<i>Havukoski</i>				0	0	—	—	—	—	—	—	—	—	—	—
<i>Hiekkaharju</i>	255	526	550	3	—	—	—	—	—	—	—	H	—	—	—
<i>Tikkurila asema</i>	320	445	550	6	412	—	30	—	K	—	—	H	T	—	—
<i>Tohmajärvi</i>				0	735	—	—	—	K	—	—	—	T	—	—
<i>Toijala</i>	450	450	550	4	690	25 A	—	—	K	Y	—	H	T	Y	—
<i>Toivala</i>				0	749	25 A	—	—	K	—	—	—	T	—	—
<i>Tolsa</i>	220	220	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Tommola</i>				0	—	—	—	—	—	—	—	—	—	—	—
<i>Torkkeli</i>				0	786	—	—	—	—	—	—	—	—	—	—
<b>TORNIO</b>															
<i>Tornio asema</i>	(101)	(157)	(265)	(2)	321	63 A	24	K	K	—	—	—	T	—	—
<i>Tornio-raja</i>				0	—	—	—	—	—	—	—	—	T	—	—
<i>Tornio-Itäinen</i>		297	550	1	—	—	—	—	—	—	—	H	—	KR	—
<i>Tuomarila</i>	220	222	550	2	—	—	—	—	—	—	—	H	—	—	—
<i>Tuomioja</i>				0	940	—	—	—	—	—	—	—	—	KR	—
<i>Turenki</i>	170	170	550	2	1204	—	—	—	K	—	—	H	T	—	—
<b>TURKU</b>															
<i>Kupittaa</i>	420	420	550	2	632	—	—	—	—	—	—	H	—	—	K
<i>Turku asema</i>	315	466	550	6	756	1500 V, 63 A	—	K	—	—	—	H	T	—	K
<i>Turku tavara</i>		(200)	(265)	(1)	382	25 A	10	—	K Y	—	—	—	T	—	K
<i>Turku satama</i>	300	304	550	2	421	63 A	—	—	—	—	—	H	—	—	K
<i>Tuupovaara</i>				0	—	—	14	—	K	—	—	—	T	—	—
<i>Tuuri</i>		66	550	1	—	—	—	—	K	—	—	H	—	—	—
<i>Törmä</i>				0	857	—	—	—	—	—	—	—	—	—	—
<i>Törölä</i>				0	756	—	—	—	—	—	—	—	—	—	—
<i>Uimaharju</i>		98	550	1	805	25 A	—	—	K Y	—	—	H	T	—	—
<i>Ujala</i>				0	732	—	8	—	—	—	—	—	—	—	—
<i>Utajärvi</i>	163	174	265	2	713	—	25	—	K	—	—	H	T	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormauskenttä	Nosturi	Polttoaine	Henkilöliikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Utti				0	—	—	101	—	—	—	—	—	T	—	—
Uusikaupunki		(66)	(265)	(1)	680	—	—	—	—	—	—	—	T	—	—
Uusikylä	120	120	550	2	1382	—	6	—	K	Y	—	—	T	—	—
Vaajakoski				0	725	—	14	—	K	—	—	—	T	—	—
Vaala	183	236	265	2	1019	25 A	25	—	K	—	—	H	—	—	—
Vaarala				0	—	—	—	—	K	—	—	—	T	—	—
Vaasa		290	550	1	450	1500 V, 63 A	—	—	—	—	—	H	T	—	—
Vahojärvi				0	716	—	—	—	—	—	—	—	—	—	—
<b>VAINIKKALA</b>															
Vainikkala tavara				0	1409	25 A	50	K	Y	—	Y	—	T	—	K
Vainikkala asema	482	484	550, 265	3	952	—	—	—	K	—	—	H	T	—	K
Vainikkala-raja				0	—	—	—	—	—	—	—	—	T	—	K
Valimo	270	270	550	2	—	—	—	—	—	—	—	H	—	—	—
Valkeakoski		(44)	(265)	(1)	346	—	54	—	K	—	—	—	T	—	—
Valkeasuo				0	—	—	—	—	K	—	—	—	—	—	—
Valtimo				0	756	—	—	—	K	—	—	—	T	—	—
Vammala	251	251	550	3	843	—	128	—	Y	—	—	H	T	—	—
Vanattara				0	—	—	—	—	—	—	—	—	—	—	—
Vantaankoski	193	196	550	2	—	—	—	—	—	—	—	H	—	—	—
Varkaus	180	213	265	2	728	63 A	124	K	K Y	—	—	H	T	KR	—
Vartius				0	1093	25 A	—	—	K	—	—	—	T	—	—
Vartius-raja				0	—	—	—	—	—	—	—	—	T	—	—
Vasikkahaka				0	—	—	—	—	—	—	—	—	—	—	—
Vaskiluoto				0	—	—	Y	—	Y	—	—	—	T	—	—
Vehkala	242	242	550	2	—	—	—	—	—	—	—	H	—	—	—
Venetmäki				0	825	—	—	—	—	—	—	—	—	—	—
Vesanka				0	—	—	5	—	K	—	—	—	—	—	—
Viekki				0	—	—	—	—	K	—	—	—	—	—	—
Vierumäki				0	—	—	92	—	K	—	—	—	T	—	—
Vihanti	450	450	550	2	698	—	—	—	Y	—	—	H	—	—	—
Vihtari	58	98	265	2	562	25 A	134	—	K	—	—	H	T	—	—
Viiala	170	170	550	2	—	—	—	—	—	—	—	H	—	—	—
Viinijärvi	132	186	265	2	641	25 A	—	—	—	—	—	H	T	—	—
Villähde	120	120	550	2	—	—	—	—	—	—	—	—	—	—	—
Vilppula		112	550	1	694	25 A	—	—	K	—	—	H	T	—	—
Vinnilä				0	—	—	—	—	—	—	—	—	—	—	—
Virkamies				0	—	—	—	—	—	—	—	—	—	—	—
Voltti				0	761	—	—	—	—	—	—	—	—	—	—
Vuohijärvi				0	710	—	15	K	—	—	—	—	T	—	—
Vuojoki				0	760	—	—	—	—	—	—	—	—	—	—
Vuokatti	(110)	(141)	(265)	(2)	627	25 A	—	—	K Y	—	—	—	T	—	—

Nimi	Lyhin laituripituus	Pisin laituripituus	Laituri-korkeus	Laituriraitteiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkö-virran saanti	Sivulaituri, suurin pituus	Päätylaituri	Kuormaust-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavara-liikennettä	Kääntöpöytä tai kolmioraide (KR)	VAK-ratapihat
Namn	Kortaste plattformslängden	Längsta plattformslängden	Plattformshöjden	Antal spår med plattform	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sidoplattform	Plattform i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-traffic	Godstrafik	Vändskiva eller triangelspår (KR)	Bangård för farliga ämnen
Name	Min. platform length	Max. platform length	Platform height	Number of tracks with platforms	Design train length (freight traffic)	Power supply	Side loading platform length	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic	Turntable or triangle rail (KR)	Rail yard for dangerous goods
	[m]	[m]	[mm]		[m]	[400 V, A]	[m]			[t]					
Vuonisahti		55	265	1	—	—	—	—	—	—	—	H	—	—	—
Vuonos				0	—	—	16	—	—	—	—	—	T	—	—
Vuosaari				0	927	—	—	—	—	—	—	—	T	—	—
<b>YKSPIHLAJA</b>															
Ykspihlaja tavara				0	767	—	—	—	K Y	—	—	—	T	—	K
Ykspihlaja väliratapiha				0	939	63 A	—	—	K Y	—	—	—	T	—	K
Ylistaro		177	265	1	—	—	—	—	—	—	—	H	—	—	—
Ylitornio		167	265	1	—	25 A	—	—	—	—	—	H	—	—	—
Ylivall				0	1014	—	—	—	Y	—	—	—	—	—	—
Ylivieska	312	480	265	3	767	63 A	113	—	K Y	—	Y	H	T	20	—
Yläkoski				0	—	—	—	—	Y	—	—	—	T	—	—
Ylämylly				0	—	—	77	—	K	—	—	—	T	—	—
Ylöjärvi				0	712	—	62	—	K	—	—	—	T	—	—
Ypykkävaara				0	748	—	—	—	K	—	—	—	T	—	—
Äetsä				0	924	—	—	—	K	—	—	—	—	—	—
Ähtäri	82	224	265	2	614	—	—	—	—	—	—	H	—	—	—
Ämmänsaari				0	570	25 A	—	—	K	—	—	—	T	—	—
Äänekoski	(35)	(75)	(265)	(2)	857	25 A	14	—	K	—	—	—	T	—	—

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Kauko-ohjaus/ manuaalinen	Yksityis- raiteita	Vaihtotyö- mahdollisuus
Namn	Namn på svenska	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår- anläggningar	Möjlighet till växlarbete
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Haimoo	Rödsand	Hmo			87+700	Hyvinkää–Karjaa	Vihti	K		
Honkaranta		Hkr			572+882	Isalmi–Ylivieska	Kiuruvesi	K		
Isalmen		Ilk			553+399	Isalmi–Ylivieska	Isalmi	K		
kolmioraide										
Jäniskorpi		Jnk			586+419	Seinäjoki–Oulu	Kannus	K		
Karvoskylä		Kvä			662+676	Isalmi–Ylivieska	Nivala	K		
Kiilinkangas		Kkg			299+490	Kouvola–Joensuu	Lappeenranta	K		
Kuninkaanmäki		Knm			38+500	Kerava–Vuosaari	Vantaa	K		
Lapinkylä		Lpk			19+900	Vantaankoski–Havukoski	Vantaa	K		
Latukka		Ltk			563+440	Pieksämäki–Kontiomäki	Isalmi	K		
Liminpuro		Lmp			864+750	Oulu–Kontiomäki	Vaala	K		
Niska		Nsk			826+880	Oulu–Kontiomäki	Utajärvi	K		
Pappilankangas		Pkg			308+633	Kouvola–Joensuu	Lappeenranta	K		
Petas		Pet			17+170	Vantaankoski–Havukoski	Vantaa	K		
Puikkokoski		Pui			665+680	Kontiomäki–Vartius-raj	Paltamo	K		
Puolukkasuo		Puo			23+510	Vantaankoski–Havukoski	Vantaa	K		
Rasimäki		Rmk			602+460	Pieksämäki–Kontiomäki	Kajaani	K		
Raudaskylä		Rkä			691+015	Isalmi–Ylivieska	Ylivieska	K		
Ruoneva		Rnv				Seinäjoki–Oulu	Siikajoki	K		
Ruskeasanta		Rs			28+760	Vantaankoski–Havukoski	Vantaa	K		
Saarela		Srl			594+018	Seinäjoki–Oulu	Kannus	K		
Salmenmäki		Sal				Seinäjoki–Oulu		K		
Temmesjoki		Tmj				Seinäjoki–Oulu	Liminka	K		
Tuomaanvaara		Tva			682+300	Kontiomäki–Vartius-raj	Ristijärvi	K		
Tupavuori		Tvu			260+100	Kouvola–Joensuu	Lappeenranta	K		
Tupos		Tup			736+500	Seinäjoki–Oulu	Kempele	K		
Viinikkala		Vkl			22+590	Vantaankoski–Havukoski	Vantaa	K		
Yllikkälä	Vinikby	Yll			268+500	Kouvola–Joensuu	Lappeenranta	K		

### Rail Traffic Operating Points/Future Traffic Operating Point Information

[illegible]

Nimi	Toinen nimi	Lyhenne	Kaupallinen nimi	Tyyppi	Km Hki	Rataosuus	Kunta	Kauko-ohjaus/ manuaalinen	Yksityisraiteita	Vaihtotyö- mahdollisuus
Namn	Namn på svenska	Förkortning	Kommersiellt namn	Typ	Km Hki	Banavsnitt	Kommun	Trafikledning	Privata spår- anläggningar	Möjlighet till växelarbeta
Name	Another name	Abbr.	Commercial name	Type	Km Hki	Section	Municipality	Traffic control	Private sidings	Shunting
Buslovskaja		Bsl			288+000	Vainikkala raja – Viipuri		K		
Haaparanta	Haparanda	Hpa			888+130	Tornio–raja – Boden	Haparanda	K		
Kivijärvi		Kiv			759+800	Vartius–raja – Kostamus		K		
Svetogorsk		Stg			338+200	Imatrankoski–raja – Kamennogorsk (Antrea)		K		
Värtsilä		Vrs			553+300	Niirala–raja – Matkaselkä		K		

[illegible]

# Transport Operating Regulations for Cross-Border Movements on the Line Section Tornio-Haaparanta

## INTRODUCTION

Appendix 3 has expired. It is based on an agreement between the previous Finnish Rail Administration (now the Finnish Transport Agency) and the previous Swedish Rail Administration (now the Swedish Transport Administration), which has not been renewed at the time of printing this Network Statement. Appendix 3 will be completely updated as soon as the agreement has been renewed. Some terms have been brought up to date in this appendix.

The original regulations were laid down in cooperation between the Swedish Rail Administration's Northern Rail Region and the Finnish Rail Administration. The present administrations (the Swedish Transport Administration and the Finnish Transport Agency) will follow these regulations until a new agreement and new regulations enter into force.

At the national border the area between signals HP 6/3 and T 832 is called as a "Common zone", which is jointly reserved by the Swedish and Finnish traffic control operators.

In principle, only one train movement is allowed at a time within the common zone, with the exception of irregular situations, such as engine failure or accident.

## SCOPE

The regulations are applicable to cross-border movements between Tornio and Haaparanta, and within the common zone.

## REFERENCE DOCUMENTS

### Sweden

JvSFS 2008:7	Transportstyrelsen/Handbok JTF/10-Växling Transportstyrelsen/Handbok JTF/3 H – Signaler, system H
--------------	--

### Finland

RVI/363/412/2008	Junan jarrutuskyky sekä jarrujen tarkastus ja koettelu
RVI/301/412/2008	Liikennöinti ilman JKV-veturilaitetta
RVI/1092/412/2009	Liikennöinti ja ratatyö rautatiejärjestelmässä
RVI/295/411/2008	Museoliikenne
RVI/1091/412/2009	Rautatiejärjestelmän opasteista, opastimista ja liikennöintiin liittyvistä merkeistä
RVI/1090/412/2009	Viestintä rautatiejärjestelmässä
RVI/725/412/2008	Tavaravaunujen suurimmasta sallitusta kuormasta, juna-painosta ja junan kokoonpanosta



## DEFINITIONS

<b>Common zone</b>	The area to be jointly reserved by the Swedish and Finnish traffic control operators and limited on the Swedish side by the 6/3 intermediate signal and on the Finnish side by the T 832 ground signal.
<b>Cross-border movement</b>	Movements entirely or partly operated within the common zone.
<b>Movement</b>	Refers to railway work and shunting.
<b>Permission</b>	Refers to permission to allow movement to begin.
<b>Swedish movement</b>	Shunting or railway work started in Sweden.
<b>Finnish movement</b>	Shunting or railway work started in Finland.

## GENERAL

The regulations are drafted in Swedish and Finnish with an identical content.

No movement is allowed within the common zone without the Swedish and Finnish traffic control operators having reserved the relevant section of line.

More than one movement is allowed in the common zone only in irregular situations, such as engine failure or accident. In such cases, the work of several movements shall be agreed at the time.

## TORNIO-HAAPARANTA CROSS-BORDER MOVEMENTS

### General

Movements are operated as specified in the Finnish RVI/1092/412/2009, as "shunting" operations, and as specified in the Swedish JvSFS 2008:7 JTF/10, as "shunting" or "small-wagon shunting" operations.

### Messages and message transmission

The Finnish staff shall be in contact with the Finnish traffic control operators, who will deliver message to the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators, who will deliver the message to the Finnish traffic control operators.

### Haaparanta-Tornio

Prior to the commencement of a Swedish cross-border shunting operation Haaparanta-Tornio direction, permission by the traffic control operators in Haaparanta is required.

Prior to the commencement of a Finnish cross-border shunting operation Haaparanta-Tornio direction, permission by the traffic control operators in Tornio is required.  
The traffic control unit that granted a permission shall be notified of the completion of the movement.

### **Tornio-Haaparanta**

Prior to the commencement of a Finnish cross-border shunting operation Tornio-Haaparanta direction, permission by the traffic control operators in Tornio is required.

Prior to the commencement of a Swedish cross-border shunting operation Tornio-Haaparanta direction, permission by the traffic control operators in Haaparanta is required.

The traffic control unit that granted permission shall be notified of the completion of the movement.

## **RAILWAY WORK WITHIN THE COMMON ZONE**

### **General**

The Finnish staff shall be in contact with the Finnish traffic control operators transmitting possible messages to and from the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators transmitting possible messages to and from the Finnish traffic control operators.

### **Swedish staff**

The permission of the Haaparanta traffic control operators is required for work carried out by the Swedish staff within the common zone.

Prior to the granting permission, the Haaparanta and Tornio traffic control operators shall reserve the common zone.

The Haaparanta traffic control operators shall be notified of the completion of the work.

### **Finnish staff**

The permission of the Tornio traffic control operators is required for work carried out by the Finnish staff within the common zone.

Prior to granting permission, the Tornio and Haaparanta traffic control operators shall reserve common zone.

The Tornio traffic control operators shall be notified of the completion of the work.

## **SAFETY CALLS AND DOCUMENTATION**

### **Safety calls**

The safety calls between the Swedish and Finnish traffic control operators shall be conducted either in Swedish or in Finnish.

There is a word list with translations in section 1.5, while section 1.6 includes examples of phrases to be used.

The safety calls shall be repeated.

### **Train Log**

A train log shall be used according to the instructions and regulations of the traffic control.

## **RESERVATION OF COMMON ZONE**

The reservation of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

The clearance of the occupancy of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

## **MAXIMUM PERMITTED SPEED**

The maximum permitted speeds are specified in the speed signs, which are described in section 1.2.

## **ACCIDENTS**

Any accident or risk of accident shall be reported to traffic control operators.

### **1.1 SIGNALS AND SIGNAL ASPECTS**

The signals are applicable in conformity with the regulations of the country concerned.

#### **Manual Signalling**

The Swedish shunting staff shall implement manual signalling as specified in JvSFS 2008:7/10, irrespective of whether the activity takes place on the Swedish or Finnish side of the border.

The Finnish shunting staff shall implement manual signalling as specified in RVI/1091/412/2009, irrespective of whether the activity takes place on the Finnish or Swedish side of the border.

A "stop" signal shall always be followed, irrespective of whether it is operated in conformity with the Swedish or Finnish regulations.

**Haaparanta – Tornio direction**

**From Finnish track, intermediate signal (main ground signal) 1/6, km 1310.845.**



"Stop"



"Proceed"  
check clearance"



"Proceed –  
turnouts and  
clearance"



"Proceed  
check"

**From Swedish tracks, intermediate signal 5/6, km 1310.697.**



"Stop"



"Proceed – check turnouts and clearance"

**Swedish and Finnish tracks, intermediate signal 6/8, km 1311.006.**



"Stop"



"Proceed"

Common track, Tornio T 832, km 886.8



"Stop"



"Proceed with caution"

Tornio – Haaparanta direction

No optical signals are used in Tornio for movements towards Sweden.

Intermediate signal 6/3, km 1311.012.



"Stop"



"Proceed –  
check turnouts and clearance"

1.2 SPEED SIGNS

In **conformity** with RVI/1092/412/2009



*Maximum admissible speed  
(example displaying max. 30 km/h)*


In **conformity** with JvSFS 2008:7/JTF/3 H



*Maximum admissible speed  
(example displaying max. 30 km/h)*


### 1.3 STOP SIGNALLING

In **conformity** with JvSFS 2008:7/JTF/3 H




Read: Stop

In **conformity** with RVI/1092/412/2009




Read: Stop



Read: Danger (emergency stop)

#### 1.4 DRAWING ON HAAPARANTA – TORNIO AREA



#### 1.5 TRANSLATION TABLE

Should any language problems arise, the below table may be implemented.

Table 1. Translation table

Swedish	Finnish	English
Växling	Vaihtotyö	Shunting work
Arbete	Työ	Work
Reserverad zon	Varaus	Reserved / Occupied
Upphävande	Peruuttaminen	Clearance of occupancy
Tågklarerare	Junasuorittaja	Dispatcher
Trafikledning	Liikenteenohjaus	Traffic control
Station	Asema	Station
Fara	Vaara	Danger
Stoppsignal	Seis-opaste	Stop aspect
Passage av en signal	Opastimen ohittaminen	Passing of signal
Signal	Opastin/Opaste	Signal / Signal aspect
Repetera	Toistaa	Repeat
Rätt uppfattat	Oikein ymmärretty	Correctly read

## 1.6 EXAMPLE PHRASES

### Zone reservation request for shunting work

Swe: *Tågklareraren \_\_\_\_\_, reserverad zon Haparanda – Torneå, växling.*

Fin: Liikenteenohjaus \_\_\_\_\_, varaus Haaparanta – Tornio välille, vaihtotyö.

Eng: Traffic control \_\_\_\_\_, reservation Haaparanta – Tornio, shunting.

### Zone reservation request for railway work

Swe: *Tågklareraren \_\_\_\_\_, reserverad zon Haparanda – Torneå, arbete.*

Fin: Liikenteenohjaus \_\_\_\_\_, varaus välille Haaparanta – Tornio, työ.

Eng: Traffic control \_\_\_\_\_, reservation Haaparanta – Tornio, work.

### Clearance of occupied zone

Swe: *Tågklareraren \_\_\_\_\_, upphävande reserverad zon \_\_\_\_\_ - \_\_\_\_\_*

Fin: Liikenteenohjaus \_\_\_\_\_, varauksen peruuttaminen välille \_\_\_\_\_ - \_\_\_\_\_

Eng: Traffic control \_\_\_\_\_, clearance of occupied zone \_\_\_\_\_ - \_\_\_\_\_

### Request for reservation in dangerous situation

Swe: *Tågklareraren \_\_\_\_\_, Fara Haparanda-Torneå.*

Fin: Liikenteenohjaus \_\_\_\_\_, vaara Haaparanta-Tornio.

Eng: Traffic control \_\_\_\_\_, danger Haaparanta-Tornio.

### Permission to pass stop signal aspect, Haaparanta

Swe: *Tågklareraren Haparanda, medgivande att passera signal (ett-sex) och/eller (åtta-tre) och/eller (sex-åtta)*

Fin: Liikenteenohjaus Haaparanta, lupa ohittaa opastin ( yksi-kuusi ) ja/tai ( kahdeksan-kolme ) ja/tai ( kuusi-kahdeksan )

Eng: Traffic control Haaparanta, permission to pass signal (one-six) and/or (eight/three) and/or (six-eight).

### Permission to pass stop signal aspect, Tornio

Swe: *Tågklareraren Torneå, växling, medgivande att passera signal (T åtta-tre-två)*

Fin: Liikenteenohjaus Tornio, vaihtotyö, lupa ohittaa opastin (T kahdeksan-kolme-kaksi )

Eng: Traffic control Tornio, shunting, permission to pass signal (T eight—three-two).

### Correctly read

Swe: *Rätt uppfattat*

Fin: Oikein ymmärretty

Eng: Correctly read.

### Repeat

Swe: *Repetera*

Fin: Toista.

Eng: Repeat



## Loading Gauge

The loading gauge (KU) refers to the space inside which the load on an open wagon shall remain, when the wagon is in the centre position on a straight, even track




Image 1. Principal dimensions of the loading gauge.

### Use of the Loading Gauge

The loading gauge is valid in the whole rail network with the exceptions mentioned below.

The loading gauge may be used for wagons in which the wheel-base or the distance between bogie centres is max. 17.5 m, and the length of the loading area of the wagon outside the wheel-base or the distance between bogie centres is max. 0.2 times the length of the wheel-base or the distance between bogie centres. In other cases, loading shall be examined separately.

If there is a risk that the load may be displaced laterally outside the loading gauge during transportation, the width of the load shall be reduced correspondingly. If the displacement of the load may increase the height of some parts of the load so that they extend outside the loading gauge, the height of the load shall be reduced correspondingly.

If the load extends below the floor level of the wagon, the regulations concerning the vehicle gauge (LKU) are applied or the load is carried as a special transport.

#### **Loading Gauge Restrictions**

The bridges on the line section Helsinki (passenger railway yard) - Pasila (passenger railway yard) – Ilmala (depot) restrict the loading gauge. The loading gauge valid on these bridges is marked with dashed line (-----) on the loading gauge drawing (Figure 1).

On several industrial and other sidings, there are loading gauge restrictions, which shall be taken into account when operating in local traffic.

### **Transport Terms and Conditions for Vehicles or other Loading Units Exceeding the Loading Gauge**

Lorries, lorry trailers and containers exceeding the loading gauge may be transported on the following conditions. The conditions are based on the Finnish Rail Agency's regulation 1172/300/2006 <http://www.trafi.fi>.

Other transports exceeding the loading gauge are transported as special transports.

#### **Loading**

Loading of a vehicle or other loading units exceeding the loading gauge is permitted if the largest width of the vehicle is max. 2,600 mm, and the greatest height is max. 4,200 mm, when the floor height is 1,100 mm.

The greatest load height from the upper surface of the rail shall not exceed 5,300 mm and a maximum  $\pm 100$  mm deviation of the lateral load is allowed.

The instructions for loading from vehicles to goods wagons shall be applied to loading of wagons intended for vehicle transports (onto combined transport wagons).

#### **Railway line sections and tracks where it is allowed to transport wagons exceeding the loading gauge**

Vehicles or loading units exceeding the loading gauge may be transported on the line sections mentioned in tables 1 and 2 according to the stock category in table 3.

At the traffic operating points, which have not been indicated for the different line sections in the tables, it is allowed to use all through routes according to the rules applying to the use of safety devices.

If a track has been indicated for a traffic operating point in the table, where the same track number is used for different track sections separated with letters, the track number itself refers to all such sections.

If these transports require shunting operations on tracks which are not mentioned here, the tracks shall be specified locally by a railway technology specialist.

Loading, inspections and unloading of wagons on or in the vicinity of electrified railways shall comply with the safety regulations.

*Table 1. Wagon length  $\leq 24.0$  m*

Wagon length $\leq 24.0$ m	
I	Helsinki–Kemi–Tornio / Rovaniemi
II	Helsinki–Karjaa–Turku
III	Hanko–Hyvinkää
IV	Uusikaupunki–Turku–Toijala
V	(Tampere)–Lielähti–Mäntyluoto / Tahkoluoto / Rauma
VI	Seinäjoki–Vaskiluoto
VII	Tampere–Jämsä–Pieksämäki
VIII	Riihimäki–Kouvola–Ämmänsaari
IX	Kouvola–Lieksa
X	Pieksämäki–Varkaus–Joensuu
XI	Kontiomäki–Oulu
XII	Viinijärvi–Siilinjärvi
XIII	Kouvola–Kotka / Kotka Mussalo
XIV	Lahti–Port of Loviisa
XV	Kerava–Hakosilta
XVI	Luumäki–Vainikkala border
XVII	Rovaniemi–Kemijärvi

*Table 2.  $24.0\text{m} \leq \text{Wagon length} \leq 26.0$  m*

$24.0\text{m} \leq \text{Wagon length} \leq 26.0$ m	
XVIII	Helsinki–Oulu
XIX	Riihimäki–Kouvola–Vainikkala border
XX	Kerava–Hakosilta
XXI	Kouvola–Kontiomäki–Oulu–Kemijärvi
XXII	Lielähti–Kokemäki
XXIII	Parkano–Niinisalo

### **Wagon stock and speed of combined transports**

The stock used for combined transports has been divided into two categories according to the principal dimensions. The allowed line sections for these categories are presented in tables 1 and 2.

Table 3. *Principal measures of stock used for combined transports.*

Principal measures of stock used for combined transports				
Category	Length [s] over buffers / max. coupling length	Distance between bogie centres	Maximum wheelbase (distance between inner wheelsets)	Example
A	$s \leq 24.0 \text{ m}$	18.4 m	16.6 m	Rbnqss
B	$24.0 \text{ m} \leq s \leq 26.0 \text{ m}$	20.0 m	18.2 m	Sdggnqss-w

The maximum allowed transport speed is 120 km/h. However, the transport speed shall not be higher than the speed limit imposed for the transporting wagons, the line section or otherwise.

# Structure Gauge

No fixed installations or equipment must be placed within the structure gauge envelope.

The form and dimensions of the structure gauge (ATU) on a straight track, on open line and in the railway yard are shown in Figure 1. The space required for the mounting of the catenary structure and for the passage of the pantograph on electrified lines is marked by the broken line D-E-F-G-H-L. The widths of the structure gauge in curves, restrictions and more detailed instructions are presented in the Ratatekniset ohjeet (RATO) publication, part 2 "Radan geometria" (Track geometry).




Figure 1. Principal dimensions of the structure gauge.

### **Effective Passing Clearance**

The structure gauge is used as a guideline for building and mounting new structures and installations in the vicinity of the track. The structure gauge or the deviations from it constitute the so-called effective available structure gauge, i.e. the passing clearance, for special consignments. Information on the passing clearance is collected for each line section and continuously updated by the track maintainers.

## Superstructure Categories, EN Categories Derived from the Superstructure Categories and Permitted Speeds for Different Axle Loads

### Division of lines into EN categories

The lines are divided into EN categories according to the superstructure as follows:

*Table 1. Division of lines into EN categories*

Categories		Superstructure		
Finnish Transport Agency's superstructure category	EN category SFS-EN 15528	Rails	Sleepers	Ballast
A	C4	K30, K33	wooden	gravel or equivalent
B <sub>1</sub>	D4	K43, 54 E1, K60, 60 E1	wooden	gravel or equivalent
B <sub>2</sub>	D4	K43, K60	wooden, concrete	railway ballast
C <sub>1</sub>	D4 /E4	54 E1	wooden, concrete before 1987	railway ballast
C <sub>2</sub>	D4/E4	54 E1	concrete from 1987 onwards	railway ballast
D	D4/E4	60 E1/60E2	concrete	railway ballast

The limit of the line category is marked in the middle of the station building at the traffic operating point, unless another point is indicated by the kilometre marking.

The line categories for sections of lines are also presented in Figure 1.

### Responsibility of Track Maintenance Service Provider

The track maintenance service provider has the right to restrict the permitted axle load and speed depending on the condition of the track superstructure.

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

*Table 2. Superstructure categories and EN categories derived from the superstructure categories of the main lines and permitted speeds for different axle loads.*

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
<b>Helsinki–Turku satama</b>								
Helsinki asema–km 25,2	D	D4	120	120	120	120	100	–
km 25,2–km 29,0	C1	D4	120	120	120	120	100	–
km 29,0–Kirkkonummi	D	D4	120	120	120	120	100	–
Kirkkonummi–km 41,4	D	D4	160	180	120	120	100	–
km 41,4–Siuntio	C1	D4	160	180	120	120	100	–
Siuntio–km 55,8	D	D4	160	180	120	120	100	–
km 55,8–km 59,2	C1	D4	160	180	120	120	100	–
km 59,2–km 75,4	D	D4	160	180	120	120	100	–
km 75,4–km 80,4	C1	D4	160	180	120	120	100	–
km 80,4–Karjaa	D	D4	160	180	120	120	100	–
Karjaa–km 96,6	D	D4	160	200	120	120	100	–
km 96,6–km 103,6	C1	D4	160	180	120	120	100	–
km 103,6–km 119,2	C2	D4	160	200	120	120	100	–
km 119,2–km 121,3	D	D4	160	200	120	120	100	–
km 121,3–km 126,0	C1	D4	160	180	120	120	100	–
km 126,0–km 130,8	D	D4	160	180	120	120	100	–
km 130,8–km 152,0	D	D4	160	200	120	120	100	–
km 152,0–km 158,0	C1	D4	160	200	120	120	100	–
km 158,0–km 193,4	C1	D4	160	180	120	120	100	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12



Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
km 193,4–Turku asema	D	D4	160	180	120	120	100	–
Turku asema–Turku satama	C1	D4	40	40	40	40	40	–
<b>Huopalahti–Tikkurila</b>								
Huopalahti–Havukoski	D	D4	120	120	–	–	–	–
<b>Hyvinkää–Karjaa</b>								
Hyvinkää–km 133,1	C1	D4	80	80	80	80	80	–
km 133,1–Kirkniemi	D	D4	80	80	80	80	80	–
Kirkniemi–km 152,2	D	E4	80	80	80	80	80	80
km 152,2–Karjaa	C1	E4	80	80	80	80	80	60
<b>Karjaa–Hanko</b>								
Karjaa–km 205,7	D	E4	120	120	120	120	100	100
km 205,7–Hanko-Pohjoinen	C1	E4	60	60	60	60	60	60
Hanko-Pohjoinen–Hanko asema	B1	D4	35	35	35	35	35	35
<b>Turku–Uusikaupunki</b>								
Turku asema–Raisio (km 207,4)	C1	D4	60	60	60	60	60	–
Raisio (km 207,4)– Uusikaupunki	B1	D4	60	60	60	60	50	–
<b>Uusikaupunki–Hangonsaari</b>								
Uusikaupunki–km 269,0 <sup>1</sup>	C1	D4	–	–	30	30	30	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
km 269,0–Hangonsaari <sup>1</sup>	B1	D4	–	–	30	30	30	–
<b>Raisio–Naantali</b>	B1	D4	50	50	50	50	50	–
<b>Helsinki–Riihimäki</b>								
Helsinki asema–Pasila asema	D	D4	80	80	80	80	80	–
Pasila asema–Tikkurila asema								
läntisin raide	D	E4	160	160	120	120	100	100
Pasila asema–Tikkurila asema								
läntinen keskiraide	D	E4	160	160	120	120	100	100
Pasila asema–Tikkurila asema								
itäinen keskiraide	D	E4	120	120	120	120	100	100
Pasila asema–Tikkurila asema								
itäisin raide	D	E4	120	120	120	120	100	100
Tikkurila asema–Kerava asema								
läntisin raide	D	E4	200	200	120	120	100	100
Tikkurila asema–Kerava asema								
läntinen keskiraide	D	E4	200	200	120	120	100	100
Tikkurila asema–Kerava asema								
itäinen keskiraide	D	E4	120	120	120	120	100	100
Tikkurila asema–Kerava asema								
itäisin raide	D	E4	120	120	120	120	100	100
Kerava asema–Kytömaa								
läntisin raide	D	E4	120	120	120	120	100	100
Kerava asema–Kytömaa	D	E4	200	200	120	120	100	100

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
läntinen keskiraide								
Kerava asema–Kytömaa								
itäinen keskiraide	D	E4	200	200	120	120	100	100
Kerava asema–Kytömaa								
itäisin raide	D	E4	120	120	120	120	100	100
Kytömaa–Kyrölä	D	E4	200	200	120	120	100	100
Kyrölä–Purola								
läntinen raide	D	E4	200	200	120	120	100	100
Kyrölä–Purola								
keskiraide	D	E4	200	200	120	120	100	100
Kyrölä–Purola								
itäinen raide	D	E4	120	120	120	120	100	100
Purola–Riihimäki asema	D	E4	200	200	120	120	100	100
<b>Kerava–Hakosilta</b>								
Kytömaa–Hakosilta	D	E4	200	220	120	120	100	100
<b>Kerava–Sköldvik</b>								
Kytömaa–Sköldvik	D	D4	80	80	80	80	80	–
<b>Olli–Porvoo<sup>2</sup></b>	A	C4	35	50	35	–	–	–
<b>Kerava–Vuosaari</b>	D	E4	–	–	80	80	80	80

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
<b>Riihimäki–Tampere</b>								
Riihimäki asema–Sääksjärvi	D	E4	200	200	120	120	100	100
Sääksjärvi–Tampere tavara								
läntinen raide	D	E4	200	200	120	120	100	100
Sääksjärvi–Tampere tavara								
keskiraide	D	E4	200	200	120	120	100	100
Sääksjärvi–Tampere tavara								
itäinen raide	D	E4	100	100	100	100	100	100
Tampere tavara–Tampere asema	D	E4	200	200	120	120	100	100
<b>Toijala–Turku</b>								
Toijala–km 264,7	D	D4	140	140	120	120	100	–
km 264,7–Turku asema	D	D4	120	120	120	120	100	–
<b>Toijala–Valkeakoski</b>	C1	D4	50	50	50	50	50	–
<b>Tampere–Seinäjoki</b>								
Tampere asema–Lielähti	D	E4	120	120	120	120	100	80
Lielähti–Pohjois-Louko	D	D4	200	200	120	120	100	–
Pohjois-Louko–Seinäjoki asema								
läntinen raide	D	D4	200	200	120	120	100	–
Pohjois-Louko–km 343,2								
itäinen raide	D	D4	160	160	120	120	100	–
km 343,2–Seinäjoki asema	D	D4	130	160	120	120	100	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
itäinen raide								
<b>Lielähti–Kokemäki</b>	D	E4	140	140	120	120	100	100
<b>Kokemäki–Pori</b>								
Kokemäki–Harjavalta	D	D4	140	140	120	120	100	–
Harjavalta–Pori	D	E4	140	140	120	120	100	100
<b>Pori–Mäntyluoto</b>	C1	E4	70	70	70	70	70	50
<b>Mäntyluoto–Tahkoluoto<sup>1</sup></b>	B2	D4	-	-	50	50	50	-
<b>Kokemäki–Rauma</b>	D	E4	100	100	100	100	100	80
<b>Pori–Aittaluoto<sup>1</sup></b>	B1	D4	–	–	20	20	20	–
<b>Niinisalo–Parkano–Kihniö</b>								
Niinisalo–Parkano	A	C4	30	30	30	30	–	–
<b>Seinäjäki–Vaasa</b>	C2	D4	120	120	120	120	100	–
<b>Seinäjäki–Kaskinen<sup>3</sup></b>								
Seinäjäki–km 452,0	B1	D4	80	80	80	60	50	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
km 452,0–km 513,8	B1	D4	60	60	60	50	40	–
km 513,8–km 514,6	B1	D4	30	30	30	30	30	–
km 514,6–Kaskinen	B1	D4	60	60	60	50	40	–
<b>Seinäjoki–Oulu</b>								
Seinäjoki asema–km 435,3	D	D4	200	200	120	120	100	–
km 435,3–Lapua	D	D4	160	200	120	120	100	–
Lapua–km 459,0	D	D4	160	200	120	120	100	–
km 459,0–km 467,5	D	D4	200	200	120	120	100	–
km 467,5–km 482,8	D	D4	190	200	120	120	100	–
km 482,8–km 507,8	D	D4	200	200	120	120	100	–
km 507,8–km 519,2	D	D4	180	200	120	120	100	–
km 519,2–km 524,6	D	D4	190	200	120	120	100	–
km 524,6–km 529,3	D	D4	200	200	120	120	100	–
km 529,3–km 550,5	D	D4	170	200	120	120	100	–
km 550,5–km 553,1	C2	D4	70	70	70	70	70	–
km 553,1–Ylivieska	D	D4	140	140	120	120	100	–
Ylivieska–km 634,3	D	D4	120	160	120	120	100	–
km 634,3–km 637,4	D	D4	160	190	120	120	100	–
km 637,4–Kangas	D	D4	160	200	120	120	100	–
Kangas–km 646,7	D	D4	120	160	120	120	100	–
km 646,7–km 650,2	D	D4	160	200	120	120	100	–
km 650,2–km 652,4	D	D4	150	200	120	120	100	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
km 652,4–km 653,9	D	D4	130	170	120	120	100	–
km 653,9–Oulainen	D	D4	200	200	120	120	100	–
Oulainen–km 675,2	D	D4	160	200	120	120	100	–
km 675,2–Tuomioja	D	D4	200	200	120	120	100	–
Tuomioja–Ruukki	D	D4	140	190	120	120	100	–
Ruukki–km 723,0	D	D4	200	200	120	120	100	–
km 723,0–Liminka	D	D4	170	200	120	120	100	–
Liminka–Oulu asema	D	D4	140	140	120	120	100	–
<b>Pännäinen–Pietarsaari</b>	C2	D4	60	60	60	60	60	–
<b>Pietarsaari–Alholma<sup>1</sup></b>	B1	D4	–	–	35	35	35	–
<b>Kokkola–Ykspihlaja</b> Kokkola–Ykspihlaja väliratapiha	B1	D4	35	35	35	35	35	–
<b>Tuomioja–Raahe</b>	C2	D4	80	80	80	80	80	–
<b>Raahe–Rautaruukki<sup>1</sup></b>	C2	D4	–	–	35	35	35	–
<b>Riihimäki–Kouvola</b> Riihimäki asema–Hakosilta	D	D4	140	140	120	120	100	–
Hakosilta–Lahti	D	E4	160	200	120	120	100	80

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
Lahti-Kouvola asema	D	E4	200	200	120	120	100	100
<b>Kouvola-Kuusankoski</b> Kouvola asema-Kuusankoski	C1	D4	50	50	50	50	50	–
<b>Lahti-Heinola</b>	B1	D4	60	60	60	60	50	–
<b>Lahti-Loviisan satama</b>	B1	D4	60	60	60	60	50	–
<b>Lahti-Mukkula<sup>1</sup></b>	B1	D4	–	–	35	35	35	–
<b>Kouvola-Kotka</b> Kouvola tavara-Juurikorpi läntinen raide	D	D4	120	120	120	120	100	–
Kouvola Oikoraide-Inkeroinen itäinen raide	C1	D4	120	120	120	120	100	–
Inkeroinen-Juurikorpi itäinen raide	D	D4	120	120	120	120	100	–
Juurikorpi-Paimenportti	D	D4	120	120	120	120	100	–
Paimenportti-Kotka asema	C1	D4	80	80	80	80	80	–
Kotka asema-Kotkan satama	C1	D4	35	35	35	35	35	–
<b>Kotka Hovinsaari-Kotka Mussalo</b>	C1	D4	50	50	50	50	50	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12



Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
<b>Juurikorpi–Hamina</b>	C1	D4	100	100	100	100	100	–
<b>Kouvola–Joensuu</b>								
Kouvola asema–Luumäki	D	E4	200	200	120	120	100	100
Luumäki–km 395,5	D	D4	140	140	120	120	100	–
km 395,5–Säkäniemi	C2	D4	140	140	120	120	100	–
Säkäniemi–Joensuu Sulkulahti	D	D4	140	140	120	120	100	–
Joensuu Sulkulahti–Joensuu asema	C1	D4	90	90	90	90	90	–
<b>Luumäki–Vainikkala-raja</b>	D	E4	140	140	120	120	100	80
<b>Lappeenranta–Mustolan satama<sup>1</sup></b>	C1	D4	–	–	50	50	50	–
<b>Imatra tavara–Imatrankoski-raja</b>	D	D4	50	50	50	50	50	–
<b>Niirala-raja–Säkäniemi</b>	D	D4	100	100	100	100	100	–
<b>Joensuu–Ilomantsi</b>								
Joensuu Sulkulahti–Heinävaara	B2	D4	60	60	60	60	60	–
Heinävaara–km 660,4	A	C4	50	50	50	40	–	–
km 660,4–km 664,1	B1	C4	50	50	50	40	–	–
km 664,1–km 678,4	A	C4	50	50	50	40	–	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
km 678,4–km 683,8	B1	C4	50	50	50	40	–	–
km 683,8–km 687,9	A	C4	50	50	50	40	–	–
km 687,9–km 692,5	B1	C4	50	50	50	40	–	–
km 692,5–Ilomantsi	A	C4	50	50	50	40	–	–
<b>Joensuu–Kontiomäki</b>								
Joensuu asema–Uimaharju	C2	D4	120	120	120	120	100	–
Uimaharju–Lieksa	C2	D4	100	100	100	100	100	–
Lieksa–Nurmes	B2	D4	110	110	110	90	80	–
Nurmes–Porokylä (km 787,9)	B2	D4	80	80	80	80	80	–
Porokylä (km 787,9)–km 807,5	C2	D4	80	80	80	80	80	–
km 807,5–km 809,2	C2	D4	60	60	60	60	60	–
km 809,2–km 810,2	B2	D4	60	60	60	60	60	–
km 810,2–km 813,7	C2	D4	60	60	60	60	60	–
km 813,7–Vuokatti	C2	D4	80	80	80	80	80	–
Vuokatti–Kontiomäki	B1	D4	80	80	80	60	50	–
<b>Lieksa–Pankakoski<sup>1</sup></b>								
	A	C4	–	–	30	30	20	–
<b>Vuokatti–Lahnaslampi<sup>1</sup></b>								
	B2	D4	–	–	50	50	50	–
<b>Kouvola–Pieksämäki</b>								
Kouvola asema–km 245,9	D	D4	140	140	120	120	100	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
km 245,9–Otava	D	D4	160	200	120	120	100	–
Otava–Pieksämäki asema	D	D4	140	140	120	120	100	–
<b>Mynttilä–Ristiina</b>	A	C4	50	50	50	35	20	–
<b>Pieksämäki–Kontiomäki</b>								
Pieksämäki asema–Kuopio km 464,3	D	D4	140	140	120	120	100	–
Kuopio km 464,3–Kuopio km 466,0	C2	D4	50	50	50	50	50	–
Kuopio km 466,0–Toivala	D	D4	120	120	120	120	100	–
Toivala–Iisalmi	D	D4	140	140	120	120	100	–
Iisalmi–Murtomäki	C2	D4	140	140	120	120	100	–
Murtomäki–Kajaani	C1	D4	140	140	120	120	100	–
Kajaani–Kontiomäki	C1	D4	140	140	120	120	100	–
<b>Suonenjoki–Yläkoski<sup>1</sup></b>	B1	D4	–	–	35	35	35	–
<b>Murtomäki–Otanmäki<sup>1</sup></b>	A	C4	–	–	50	40	–	–
<b>Murtomäki–Talvivaara</b>	C2	D4	80	80	80	80	80	–
<b>Kajaani–Lamminniemi<sup>1</sup></b>	B1	D4	–	–	35	35	35	–
<b>Pieksämäki–Joensuu</b>								

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
Pieksämäki–Varkaus	C2	D4	120	120	120	120	100	–
Varkaus–Joensuu asema	C2	D4	120	120	120	120	100	–
<b>Varkaus–Kommila</b>	B2	D4	50	50	50	50	50	–
<b>Huutokoski–Rantasalmi</b>	C2	D4	80	80	80	80	80	–
<b>Savonlinna–Parikkala<sup>3</sup></b>								
Savonlinna asema–Parikkala	B2	D4	110	110	110	90	80	–
<b>Siilinjärvi–Viinijärvi</b>	C2	D4	100	100	100	100	100	–
<b>Sysmäjärvi–Vuonos<sup>1</sup></b>	B2	D4	–	–	35	35	35	–
<b>Tampere–Jyväskylä</b>								
Tampere Järvensivu–Orivesi								
pohjoinen raide	D	E4	140	140	120	120	100	100
Tampere Järvensivu–km 205,0								
eteläinen raide	C2	E4	140	140	120	120	100	80
km 205,0–km 208,0								
eteläinen raide	D	E4	140	140	120	120	100	80
km 208,0–Orivesi								
eteläinen raide	C2	E4	140	140	120	120	100	80
Orivesi–Jämsänkoski	D	E4	120	140	120	120	100	80

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
Jämsänkoski–km 308,2	D	D4	160	160	120	120	100	–
km 308,2–km 312,6	C1	D4	160	160	120	120	100	–
km 312,6–km 329,7	D	D4	160	160	120	120	100	–
km 329,7–km 332,8	C1	D4	160	160	120	120	100	–
km 332,8–Jyväskylä	D	D4	160	160	120	120	100	–
<b>Jämsä–Kaipola<sup>1</sup></b>	B1	E4	–	–	50	50	50	50
<b>Orivesi–Seinäjoki</b>								
Orivesi–Haapamäki	B1	D4	100	100	100	70	50	–
Haapamäki–Pihlajavesi	C2	D4	100	100	100	100	100	–
Pihlajavesi–Seinäjoki	B1	D4	100	100	100	60	50	–
<b>Vilppula–Mänttä</b>	B1	D4	50	50	50	50	50	–
<b>Haapamäki–Jyväskylä</b>	B1	D4	100	100	100	70	50	–
<b>Jyväskylä–Pieksämäki</b>								
Jyväskylä–Pieksämäki asema	C1	D4	140	140	120	120	100	–
<b>Jyväskylä–Äänekoski</b>	C1	D4	100	100	100	100	100	–
<b>Äänekoski–Haapajärvi</b>								

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
Äänekoski–Saarijärvi	C2	D4	80	80	80	80	80	–
Saarijärvi–Haapajärvi	A	C4	60	60	60	40	–	–
<b>Iisalmi–Ylivieska</b>								
Iisalmi–km 555,8	C1	D4	120	120	120	120	100	–
km 555,8–km 613,1	D	D4	120	120	120	120	100	–
km 613,1–km 699,0	C2	D4	120	120	120	120	100	–
km 699,0–Ylivieska	D	D4	120	120	120	120	100	–
<b>Pyhäkumpu erk.vh–Pyhäkumpu</b>	C2	D4	35	35	35	35	35	–
<b>Oulu–Laurila</b>								
Oulu asema–Laurila	C2	D4	140	140	120	120	100	–
<b>Kemi–Ajos<sup>1</sup></b>								
Kemi–Ajos km 861,8	B1	D4	–	–	50	50	50	–
Ajos km 861,8–km 863,5	C2	D4	–	–	50	50	50	–
Ajos km 863,5–867,1	B1	D4	–	–	50	50	50	–
<b>Laurila–Tornio-raja</b>								
Laurila–Tornio asema	C2	D4	120	120	120	120	100	–
Tornio asema–Tornio-raja	C1	D4	40	40	40	40	40	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
<b>Tornio–Röyttä<sup>1</sup></b> Tornio asema–Röyttä	B1	D4	–	–	50	50	50	–
<b>Tornio–Kolari</b> Tornio asema–km 886,1	B2	D4	80	80	80	80	80	–
km 886,1–Kolari	D	D4	100	100	80	80	80	–
<b>Laurila–Kemijärvi</b> Laurila–Koivu	D	D4	140	140	120	120	100	–
Koivu–Rovaniemi	D	D4	120	120	120	120	100	–
Rovaniemi–Misi	C2	D4	100	100	100	100	100	–
Misi–km 1037,1	C1	D4	100	100	100	100	100	–
km 1037,1–Kemijärvi	B1	D4	100	100	100	60	50	–
<b>Kemijärvi–Patokangas</b> <b>Oulu–Kontiomäki</b> Oulu Nokela–km 775,9	C2	D4	50	50	50	50	50	–
km 775,9–km 787,4	C1	D4	120	120	120	120	100	–
km 787,4–km 794,5	C1	D4	140	140	120	120	100	–
km 794,5–km 796,5	C1	D4	120	120	120	120	100	–
km 796,5–km 809,3	C1	D4	130	130	120	120	100	–
km 809,3–Utajärvi	C1	D4	120	120	120	120	100	–
Utajärvi–km 835,5	C1	D4	140	140	120	120	100	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Agency	SFS-EN 15528	locomotive-hauled	motor cars	≤160 kN	160 ≤ 200 kN	200 ≤ 225 kN	225 ≤ 250 kN
835,5–km 878,2	D	D4	140	140	120	120	100	–
km 878,2–km 879,6	D	D4	120	120	120	120	100	–
km 879,6–km 893,7	D	D4	140	140	120	120	100	–
km 893,7–Paltamo	D	D4	120	120	120	120	100	–
Paltamo–Kontiomäki	D	D4	140	140	120	120	100	–
<b>Kontiomäki–Ämmänsaari</b>	A	C4	50	50	50	40	–	–
<b>Kontiomäki–Vartius-raja</b>	C2	D4	80	80	80	80	80	–

<sup>1</sup> Shunting operations only

<sup>2</sup> Museum line

<sup>3</sup> Bridge restriction, see Appendix 12



**Permitted speed in turnouts and diamond crossings**

Table 3. Permitted speed in turnouts and diamond crossings.

	Superstructure category					
	A	B <sub>1</sub>	B <sub>2</sub>	C <sub>1</sub>	C <sub>2</sub>	D
<b>Straight track</b>						
Single turnouts, 60 E 1, short	70	100	110	180	200	200
Single turnouts, 60 E 1, long	—	100	110	180	200	220
Single turnouts, 54 E 1, long	70	100	110	140	140	140
Single turnouts, other	70	100	110	160	160	160
Double turnouts	70	100	110	120	120	120
Diamond crossings with slips	35	90	90	90	90	90
Standard diamond crossings	35 <sup>1</sup>	90 <sup>1</sup>	90 <sup>1</sup>	90 <sup>1</sup>	90 <sup>1</sup>	90 <sup>1</sup>
<b>Diverted track</b>						
Short turnouts R = 165 m	20 <sup>1</sup>	20 <sup>1</sup>	20 <sup>1</sup>	20 <sup>1</sup>	20 <sup>1</sup>	20 <sup>1</sup>
Short turnouts	35	35	35	35	35	35
Short turnouts when axle load max. 225 kN	—	10	20	20	20	35
Long turnouts						
R = 500 m	—	—	—	60	60	60
R = 530 m	70	70	70	—	—	—
R = 900 m, when axle load max. 225 kN	—	80	80	80	80	80
R = 900 m, when axle load over 225 kN	—	—	—	60	60	60
R = 1,600 m	—	—	—	140	140	140
R = 2,500 m	—	—	—	—	—	160
<b>Non-interlocked turnout</b>						
Straight and diverted track	30 <sup>1</sup>	30 <sup>1</sup>	30 <sup>1</sup>	30 <sup>1</sup>	30 <sup>1</sup>	30 <sup>1</sup>

<sup>1</sup> Indicated with a speed board




Figure 1. Superstructure categories

## Maintenance level on main lines

The maintenance levels on main lines used as the basis for railway maintenance are illustrated in figure 2.




Figure 2. Maintenance levels in the Finnish railway network.

# Electrification

## Electrified railway lines

Helsinki asema–Turku satama  
Huopalahti–Havukoski  
Helsinki asema–Riihimäki asema  
Kytömaa–Hakosilta  
Kerava–Sköldvik  
Riihimäki asema–Tampere asema  
Toijala–Turku tavara  
Tampere asema–Seinäjoki asema  
Lielehti–Kokemäki  
Kokemäki–Pori  
Kokemäki–Rauma  
Seinäjoki asema–Oulu asema  
Oulu Nokela–Oulu Oritkari  
Tuomioja–Raahe  
Raahe–Rautaruukki  
Riihimäki asema–Kouvola asema  
Kouvola asema–Kuusankoski  
Kouvola–Kotkan satama  
Kotka Hovinsaari–Kotka Mussalo  
Juurikorpi–Hamina  
Kouvola asema–Joensuu asema  
Luumäki–Vainikkala raja  
Kouvola asema–Pieksämäki asema  
Pieksämäki asema–Kontiomäki  
Tampere–Jyväskylä  
Jyväskylä–Pieksämäki asema  
Oulu asema–Laurila  
Laurila–Rovaniemi  
Oulu Nokela–Kontiomäki  
Kontiomäki–Vartius  
Kerava–Vuosaari  
Murtomäki–Talvivaara  
Kokkola–Ykspihlaja  
Seinäjoki–Vaasa  
Rovaniemi–Kemijärvi  
Kemijärvi–Patokangas  
Pietarsaari–Pännäinen

The electrified railway lines are also illustrated in figure 1.




Figure 1. Electrified railway lines.

## Signalling systems

The signalling systems used on the lines are represented in the figures in this appendix.


### Lines with a section blocking system

Helsinki asema–Turku satama	Juurikorpi–(Hamina)
Huopalahti–Havukoski	Kouvola–Imatra tavara tracks
Hyvinkää–Hanko	Luumäki–Vainikkala
Helsinki asema–Riihimäki asema	Kouvola asema–Pieksämäki asema
Kytömaa–Hakosilta	Pieksämäki asema–Kuopio asema–
Kerava–Sköldvik	Iisalmi
Riihimäki asema–Tampere asema	Tampere Järvensivu–Jyväskylä
Toijala–Turku tavara	Jyväskylä–Pieksämäki asema
Tampere asema–Seinäjoki asema	Oulu asema–Laurila
Lielähti–Kokemäki	Laurila–Tornio tracks 721, 722, 732, 741
Kokemäki–Mäntyluoto	and Oulu Nokela–(Kontiomäki)
Kokemäki–Rauma	Säkäniemi–(Niirala)
Seinäjoki asema–Oulu asema	Turku asema–Uusikaupunki
Kokkola–Ykspihlaja väliratapiha	Kerava–Vuosaari
Tuomioja–Raahe tracks 001 andma	Kemijärvi–Patokangas
Kouvola–Kymi track 001–(Kotka)	

### Double-track or multi-track railway lines with section blocking systems in both directions

Helsinki asema–Kirkkonummi  
Huopalahti–Havukoski  
Helsinki asema–Lielähti  
Kytömaa–Hakosilta  
Pohjois–Louko–Ruha  
Riihimäki asema–Luumäki  
Tampere Järvensivu–Orivesi  
Kokkola–Karhukangas

The railway lines with section blocking systems and the lines where the blocking system is under construction are illustrated in figure 1.



*Figure 1. Lines with a section blocking system.*

### **Reporting use of the left-hand track**

Usage of the left-hand track on the railway sections below must be reported in an advance report to the driver or in a report to the traffic control. The report to the driver must always include information about to what point the moving train is allowed to use the left-hand track.

Kouvola–Juurikorpi

### **Lines with a centralised traffic control system**

Helsinki–Turku satama  
Huopalahti–Havukoski  
Hyvinkää–(Hanko)  
Helsinki–Riihimäki  
Kytömaa–Hakosilta  
Kerava–Sköldvik  
Riihimäki–(Tampere)  
Toijala–Turku  
(Tampere)–(Seinäjoki)  
Lielähti–Kokemäki  
Kokemäki–Mäntyluoto  
Kokemäki–Rauma  
(Seinäjoki)–(Ylivieska)–(Oulu)  
Kokkola–Ykspihlaja väli­ratapiha  
Tuomioja–Raahe  
Riihimäki–Kouvola  
Kouvola–(Inkeroinen)–Kymi track 002–(Kotka)  
Juurikorpi–(Hamina)  
Kouvola–Luumäki  
Luumäki–(Joensuu)  
Luumäki–(Vainikkala)  
Kouvola–Pieksämäki  
Pieksämäki–(Kuopio)–Iisalmi  
Siilinjärvi–Kemira  
(Tampere)–Jyväskylä  
Jyväskylä–Pieksämäki  
(Oulu)–Laurila  
Laurila–Tornio  
(Oulu)–(Kontiomäki)  
Säkäniemi–(Niirala)  
Turku–Uusikaupunki  
Kerava–Vuosaari  
(Murtomäki)–Talvivaara  
Kemijärvi–Patokangas

The centralised controlled railway sections and railway sections where centralised control is under construction are illustrated in figure 2.






Figure 2. Lines with a centralised traffic control system.

### Lines with ATP

ATP is a class B system "ATP-VR/RHK-Junankulunvalvonta (JKV)" according to appendix B to the technical specification for interoperability relating to the control-command and signalling subsystem of the trans-European conventional rail system of 28 March 2006.

The following railway lines are equipped with ATP:

Helsinki asema–Turku satama	Pieksämäki asema–Kontiomäki
Huopalahti–Havukoski	Pieksämäki–Joensuu asema
Hyvinkää–Hanko asema	Huutokoski–Rantasalmi
Helsinki asema–Riihimäki asema	Savonlinna–Parikkala
Kytömaa–Hakosilta	Siilinjärvi–Viinijärvi
Kerava–Sköldvik	Tampere–Jyväskylä
Riihimäki asema–Tampere asema	Orivesi–Seinäjoki
Toijala–Turku tavara	Haapamäki–Jyväskylä
Tampere asema–Seinäjoki asema	Jyväskylä–Pieksämäki asema
Lielähti–Kokemäki	Jyväskylä–Äänekoski
Kokemäki–Mäntyluoto	Iisalmi–Ylivieska
Kokemäki–Rauma	Oulu asema–Laurila
Seinäjoki asema–Vaasa	Laurila–Tornio
Seinäjoki asema–Oulu asema	Tornio–Kolari
Kokkola–Ykspihlaja väliratapiha	Laurila–Patokangas
Tuomioja–(Raahe)	Oulu Nokela–Kontiomäki
Riihimäki asema–Kouvola asema	Kontiomäki–Vartius
Paimenportti–(Kotka Mussalo)	Säkäniemi–(Niirala)
Juurikorpi–(Hamina)	Turku–Uusikaupunki
Kouvola asema–Joensuu asema	Kerava–Vuosaari
Luumäki–(Vainikkala)	Seinäjoki asema–Kaskinen
Joensuu asema–Nurmes	Murtomäki–Talvivaara
Kouvola asema–Pieksämäki asema	

The railway lines with ATP and the lines where ATP is under construction are illustrated in figure 3.




Figure 3. Lines with ATP.

**Lines with a radio-controlled traffic system**

(Seinäjoki)–Vaasa  
(Joensuu)–Nurmes  
(Iisalmi)–Kontiomäki  
(Pieksämäki)–(Joensuu)  
Huutokoski–Rantasalmi  
Savonlinna–Parikkala  
(Siilinjärvi)–Viinijärvi  
(Orivesi)–(Seinäjoki)  
Haapamäki–(Jyväskylä)  
(Jyväskylä)–Äänekoski  
(Iisalmi)– (Ylivieska)  
(Tornio)–Kolari  
(Laurila –Kemijärvi  
Kontiomäki–Vartius  
(Seinäjoki)–Kaskinen

The lines with a radio-controlled traffic system are illustrated in figure 4.



The lines with combined signals are illustrated in figure 5.




Figure 5. Lines with combined signals.

## Vibration-related speed restrictions

Table 1. Vibration-related speed restrictions.

Line section	Operating point	Km-stretch	Speed restriction
Helsinki–Riihimäki	Jokela	47+950–49+950	≥ 3000 ton trains 40 km/h
Kerava–Sköldvik	Kerava	30+700–31+650	all trains 40 km/h
Kerava–Sköldvik	Nikkilä	38+850–40+160	all trains 40 km/h
Toijala–Turku	Toijala	150+400–150+900	all trains 40 km/h
Toijala–Turku	Loimaa	208+000–210+600	≥ 3000 ton trains 40 km/h
Toijala–Turku	Turku	271+900–273+700	≥ 3000 ton trains 40 km/h
Seinäjoki–Kaskinen	Kurikka	450+500–452+000	all trains 40 km/h
Seinäjoki–Oulu	Liminka	726+900–729+200	≥ 3000 ton trains 50 km/h
Seinäjoki–Oulu	Kempele	740+600–741+700	≥ 3000 ton trains 50 km/h
Riihimäki–Kouvola	Hollola	116+200–118+500	≥ 3000 ton trains 40 km/h
Riihimäki–Kouvola	Lahti	125+000–125+400	≥ 3000 ton trains 40 km/h
Riihimäki–Kouvola	Koria	182+900–186+400	all trains 60 km/h
Kouvola–Kotka	Myllykoski	201+500–203+100	≥ 3000 ton trains 40 km/h
Kouvola–Kotka	Keltakangas	207+300–207+700	all trains 60 km/h
Oulu–Kontiomäki	Oulu	762+800–763+800	≥ 3000 ton trains 45 km/h
Oulu–Kontiomäki	Muhos	786+000–790+000	≥ 3000 ton trains 60 km/h
Kerava–Lahti	Järvenpää	35+800–36+200	≥ 3000 ton freight trains 40 km/h
Joensuu–Viinijärvi	Joensuu	631+100–631+700	≥ 3000 ton freight trains 40 km/h

## Speed Limits due to Track Conditions

The information in table 1 for 2017 will be updated on 9 December 2016

[illegible]



## Maximum Train Speeds in Tunnels

*Table 1. Tunnels owned by the Finnish Transport Agency.*

Tunnel	Length (m)	Km-location	Section
Espoo	99	21+145–21+244	Helsinki–Turku satama
Lillgård	187	46+790–46+977	Helsinki–Turku satama
Riddarbacken	273	47+770–48+043	Helsinki–Turku satama
Bäljens	298	88+924–89+218	Helsinki–Turku satama
Köpskog	43	90+492–90+535	Helsinki–Turku satama
Åminne	101	92+391–92+492	Helsinki–Turku satama
Högbacka	200	94+365–94+565	Helsinki–Turku satama
Kaivosmäki	99	113+961–114+060	Helsinki–Turku satama
Haukkamäki	436	114+304–114+740	Helsinki–Turku satama
Harmaamäki	265	115+150–115+415	Helsinki–Turku satama
Lemunmäki	775	125+820–126+595	Helsinki–Turku satama
Märjänmäki	1240	126+940–128+180	Helsinki–Turku satama
Lavianmäki	582	137+720–138+302	Helsinki–Turku satama
Tottola	531	139+084–139+615	Helsinki–Turku satama
Halikko	186	150+207–150+393	Helsinki–Turku satama
Pepallonmäki	531	152+420–152+951	Helsinki–Turku satama
Malminkartano	230	10+636–10+866	Huopalahti–Havukoski
Kivistö	432	18+122–18+554	Huopalahti–Havukoski
Lentoasema	8260	21+388–29+636	Huopalahti–Havukoski
Savio	13575	32+659–46+234	Kerava–Vuosaari
Labbacka	651	48+728–49+379	Kerava–Vuosaari
Kehä II	388	194+646–195+029	Kouvola–Kotka
Suurivuori	765	236+028–236+793	Juurikorpi–Hamina
Paksunniemi	26	399+111–399+137	Kouvola–Joensuu
Voisalmensaari	198	290+167–290+365	Lappeenranta, Metsä-Saimaan rata
Venekallio	180	204+400–204+580	Kouvola–Pieksämäki
Vuohijärvi	191	222+400–222+591	Kouvola–Pieksämäki
Kulonpalonvuori	418	232+075–232+493	Kouvola–Pieksämäki
Mustamäki	249	416+960–417+211	Pieksämäki–Kontiomäki
Mustavuori I	283	417+791–418+075	Pieksämäki–Kontiomäki
Mustavuori II	374	418+341–418+718	Pieksämäki–Kontiomäki
Pieni Neulamäki	1003	454+288–455+291	Pieksämäki–Kontiomäki
Kyrönniemi	336	483+892–484+214	Savonlinna–Parikkala
Matomäki	262	303+987–304+249	Tampere–Jyväskylä
Lahdenvuori	4293	308+214–312+507	Tampere–Jyväskylä
Sahinmäki	153	316+064–316+217	Tampere–Jyväskylä
Lautakkomäki	399	321+171–321+570	Tampere–Jyväskylä
Paavalinvuori	771	328+364–329+135	Tampere–Jyväskylä
Paasivuori	2474	330+108–332+581	Tampere–Jyväskylä
Keljonkangas I	1093	333+973–335+066	Tampere–Jyväskylä
Keljonkangas II	224	335+302–335+525	Tampere–Jyväskylä
Möykynmäki	350	365+969–366+319	Haapamäki–Jyväskylä
Pönttövuori	1429	394+476–395+905	Jyväskylä–Pieksämäki

Tunnel	Length (m)	Km-location	Section
Kangasvuori	2735	380+028–382+763	Jyväskylä–Äänekoski

### Maximum Train Speeds in Tunnels

This table presents the tunnels with a speed limit. The speed limit of the track section in question is applied for all other tunnels.

*Table 2. In the following tunnels there are operational restrictions due to the piston effect, when a train has one or more cars similar to those mentioned in the table.*

Tunnel	Km-location	Maximum speed [km/h]		
		Single deck	Double deck	Motorised trains
Helsinki–Karjaa				
Lillgård	46+790–46+977	160	120	180
Riddarbacken	47+770–48+043	160	120	180
Karjaa–Salo				
Bäljens	88+924–89+218	160	140	200
Köpskog	90+492–90+535	160	140	200
Åminne	92+391–92+492	160	140	200
Högbacka	94+365–94+565	160	140	200
Kaivosmäki	113+961–114+060	160	140	200
Haukkamäki	114+304–114+740	160	140	200
Harmaamäki	115+150–115+415	160	140	200
Lemunmäki	125+820–126+595	160	160	160
Märjänmäki	126+940–128+180	160	160	160
Lavianmäki	137+720–138+302	160	160	180
Tottola	139+084–139+615	160	120	180
Salo–Turku				
Halikko	150+207–150+393	160	140	200
Pepallonmäki	152+420–152+951	160	140	200
Orivesi–Jyväskylä				
Keljonkangas II	335+301–335+526	140	140	140

Table 3. *Following tunnels have speed limits due to their condition.*

Section	Tunnel	Km-location	Maximum speed [km/h]
Jämsänkoski–Jyväskylä	Lahdenvuori	308+200–312+700	120
Jämsänkoski–Jyväskylä	Paasivuori	330+100–332+700	120
Haapamäki–Jyväskylä	Möykynmäki	365+900–366+400	50
Jyväskylä–Äänekoski	Kangasvuori	380+000–382+800	50

## Bridge-Related Restrictions

Table 1 lists the bridges with axle load and speed restrictions for rolling stock. The reasons for imposing restrictions may be that the original load-carrying capacity of the bridge is too low, the bridge is in poor condition or it is movable.

The maximum speed on the bridges is indicated with speed-restriction boards.

The axle loads below must not be exceeded, and the excess load shall be unloaded at the station where it has been discovered.

The weight limits on bridges do not apply to 6-axle or 8-axle wagons built according to the Russian standard. Such wagons can be carried over the bridges with weight limits only as special transport on the conditions laid down in the transport permit.

*Table 1 Bridge-related restrictions*

Bridge	Section of line	Km	Max. permitted axle load, kN	Category (EN 15528)	Max. permitted speed		Reason for restriction
					Passenger trains	Freight trains	
Tikkalansaari drawbridge	Kuopio-Siilinjärvi	472+817	350	E5	50	50	Movable bridge
Honkasalmi railway bridge	Siilinjärvi-Iisalmi	527+080	225	D4	120	120	Poor condition
Railway bridge over Saimaa Canal	Lappeenranta-Imatra	294+170	225	D4	80	40	Poor condition
Mansikkakoski railway bridge	Imatra-Parikkala	324+183	225	D4	40	40	Poor condition
Syrjäsalmi railway bridge	Parikkala-Säkäniemi	445+395	225	D4	80	60	Poor condition
Pielisjoki railway bridge	Joensuu-Uimaharju	625+146	250	E4	50	50	Movable bridge
Uimasalmi railway bridge	Joensuu-Uimaharju	673+486	250	E4	60	60	Movable bridge
Vääräjoki railway bridge	Kokkola-Ylivieska	611+217	225	D4	80	80	Poor condition
Siikajoki railway bridge	Tuomioja-Oulu	705+684	250	E4	80	80	Poor condition
Heikinkatu underpass	Tuomioja-Oulu	752+850	225	D4	40	40	Poor condition
Simojoki railway bridge	Oulu-Kemi	832+960	225	D4	90	90	Poor condition
Jämsänjoki railway bridge	Orivesi-Jämsänkoski	287+003	250	E4	40	40	Poor condition
Kyrönsalmi railway bridge	Parikkala-Savonlinna	483+659	225	D4	20	20	Movable bridge
Heinlampi underpass	Jyväskylä-Pieksämäki	448+690	250	E4	80	80	Insufficient ballast depth
Pirtinvirta railway bridge	Varkaus-Viinijärvi	425+570	225	D4	40 <sup>1</sup>	40 <sup>1</sup>	Movable bridge

Bridge	Railway section	Km	Maximum permitted axle load, kN	Category SFS-EN 15528	Permitted speed [km/h]		Reason for restriction
					Passenger trains	Freight trains	
Railway bridge over Taipale Canal	Varkaus-Viinijärvi	426+855	225	D4	30 <sup>1</sup>	30 <sup>1</sup>	Movable bridge
Nickby railway bridge (Sipoonjoki)	Kerava-Sköldvik	039+744	225	D4	40	40	Poor condition
Pohja railway bridge, western part of the sound	Karjaa-Hanko	175+051	250	E4	50	50	Swing bridge
Jyränkö railway bridge	Lahti-Heinola	166+604	225	D4	60	60	Poor condition
Tahkoluoto railway bridge	Pori-Mäntyluoto	343+792	250	E4	50	50	Movable bridge
Seinäjoki railway bridge	Seinäjoki-Kaskinen	419+367	225	D4	50	50	Original load-carrying capacity
Kyrönjoki railway bridge	Seinäjoki-Kaskinen	442+875	225	D4	50	50	Original load-carrying capacity.
Nenättömänluoma railway bridge	Seinäjoki-Kaskinen	446+650	225	D4	60	60	Original load-carrying capacity
Kainastonjoki railway bridge	Seinäjoki-Kaskinen	482+348	225	D4	60	60	Original load-carrying capacity
Teuvanjoki railway bridge	Seinäjoki-Kaskinen	502+165	225	D4	60	60	Original load-carrying capacity
Närpiönjoki railway bridge	Seinäjoki-Kaskinen	518+951	225	D4	60	60	Original load-carrying capacity
Kaskistensalmi railway bridge	Seinäjoki-Kaskinen	528+922	225	D4	60	60	Original load-carrying capacity
Vaalansalmi railway bridge	Oulu-Vaala	843+637	225	D4	80	80	Poor condition
Kiehimänjoki railway bridge	Vaala-Kontiomäki	902+658	225	D4	50	50	Poor condition

[1] The bridge and rail joints may be locked, in which case the maximum speed is 60 km/h.

# Track Work

## 1 Traffic arrangements during track work

The Finnish Transport Agency negotiates with the Railway Undertakings and traffic planners about the timing of track work and other work requiring track possessions. The Finnish Transport Agency's track work and traffic management process are followed when deciding the timing of track work.

At the time of publication, Table 1 in Appendix 13 contains the best estimate of the track works affecting traffic and, consequently, the rail capacity needs of the infrastructure management during timetable period 2017. The schedule, the timing of tasks and required track possessions will change as the funding and plans are specified. Table 1 in Appendix 13 is thus not binding for the Finnish Transport Agency.

The transport needs and infrastructure management needs are matched before the start of the timetable period. The Finnish Transport Agency will make a separate decision on all track works significantly affecting traffic and on the required track possessions prior to the upcoming timetable period, that is, in December 2016 for timetable period 2017.

The allocated rail capacity is at the disposal of the railway operators, unless it overlaps track possessions required for infrastructure management operations. At least two months prior to commencing infrastructure management operations, the Infrastructure Manager will inform the Railway Undertakings if they have been allocated rail capacity which overlaps with the infrastructure management needs. In such cases the capacity is no longer available to the Railway Undertakings.

Short track possessions for urgent maintenance operations are planned on the terms of the train traffic and these are specified and entered into the Advance Information System. The aim is to specify the capacity required for track possessions and the capacity required for traffic in a synchronized manner. When the rail capacity required for infrastructure management operations has been entered into the Advance Information System, it is reserved, and consequently the railway operators cannot apply for it or use it at that time. In cases where the Advance Information System is not used in its entirety in the marshalling yard, information about this is provided by the traffic planner or, during malfunctions, by the traffic control.

Compensation liability will not arise for possible traffic impacts, caused by track work as described in the decision for timetable period 2017, or for investment work specified at least three months in advance and for maintenance work, specified at least two months in advance. Track work specified three months prior to implementation (investment work) will typically entail track possessions lasting for weeks or months and several weekend breaks in the construction phase. Track work specified two months prior to implementation (maintenance work) will be implemented on the terms of the train traffic, or they will have non-recurring impacts on single objects within the railway network. Such track work is, for example, replacement of sleepers, rails or turnouts and repairs of bridges and culverts. Some demanding maintenance projects, such as certain bridge objects, replacement of the carrying cable in the catenary system, or sub- or superstructure work may have impacts of longer duration, much like those of investment work. Such maintenance work is handled in the same way as investment work in the annual planning. If the maintenance work has significant traffic impacts, of which the

railway operator has not been informed at least three months ahead, traffic arrangements are negotiated separately with the operator to find a solution minimising the impacts on traffic.

Information about investment and maintenance work affecting high-speed international passenger transport must be given at least four months in advance.

Each party is responsible for its own communication on the track work. The Infrastructure Manager is responsible for the communication regarding the track and access to it and for informing about track work. The Railway Undertakings are responsible for the communication regarding train services and timetables. The parties coordinate and agree on the concrete measures to be taken concerning the communication about the track work in advance.

## 2 Estimate of planned track work

Table 1 displays an estimate of track work during the 2017 timetable period, which may affect traffic. The information in the table may change as the funding and plans are specified. An updated list will be published on the Finnish Transport Agency's website

<http://www.liikennevirasto.fi/ammattiliikenne-raiteilla/liikennesuunnittelu/ratatyot#.VjdiQbU8Kpo>

Table 1. Track work in 2017

Location	Affects traffic	Break description
<b>SOUTHERN FINLAND</b>		
Improvement of Helsinki railway yard (HELRA Project)	x	Weeknight and weekend breaks Alterations in track usage
Building of Central Pasila	x	Weeknight and weekend breaks Alterations in track usage
Pasila western additional track	x	Weeknight and weekend breaks
Renewal of the superstructure on the Helsinki–Ilmala yard tracks	x	Weeknight and weekend breaks
Pasila-Kerava: replacement of rails on the westernmost track	x	Weeknight and weekend breaks
Pasila-Käpylä: building of a pedestrian and bicycle lane, blasting	x	Weeknight and weekend breaks
Renewal of substations: Kytömaa SA, Pikkusuo SA, Ilmala SA, Oulunkylä SA, Riihimäen VK and new substation at Rekola.	x	Weeknight and weekend breaks
Increased capacity on the section Pasila–Riihimäki	x	Weeknight and weekend breaks. Ainola-Purola western track closed for two months from Midsummer onwards
Kerava–Sköldvik: renewal of Nickby railway bridge	x	Total break for two days and nights
Leppävaara-Kirkkonummi: station arrangements at Jorvas	x	Only one track in use and weekend breaks. Commuter traffic arrangements

Location	Affects traffic	Break description
Kirkkonummi-Siuntio: repairs on Jolkbyjoki railway bridge	x	Weeknight and weekend breaks
Kirkkonummi-Karjaa: rail replacements	x	Weeknight and weekend breaks
Kirkkonummi-Turku: repair of tunnels	x	Weeknight and weekend breaks
Deck at Kupittaa	-	No work affecting traffic
Deck at Tammisaari	x	Weeknight and weekend breaks
Turku-Uusikaupunki: renewal of 62 km of superstructure	x	Daily 8-10h track possessions, weekend breaks.
Renewal of superstructure on the Helsinki-Ilmala yard tracks	x	Weeknight and weekend breaks
Pasila-Kerava: renewal of superstructure on 24 km of the westernmost track	x	Weeknight and weekend breaks
<b>EASTERN FINLAND</b>		
Kotka-Mussalo: underpass in Hirsisaari	x	24 h traffic break
Myllykoski-Inkeroinen: renewal of superstructure on the eastern track	x	Only one track in use, daily 8h track possessions
Kouvola-Juurikorpi-Kotka/Hamina: turnout replacements	x	Only one track in use on Kouvola-Juurikorpi line, daily 8h track possessions, weekend breaks
Kotka-Mussalo: superstructure renewal	x	Daily 8h track possessions
Juurikorpi-Hamina: rail replacements	x	Daily 8h track possessions
Juurikorpi-Hamina: repairs on Myllyoja railway bridge	x	Daily 8h track possessions
Juurikorpi-Hamina: tunnel repairs	x	Daily 8h track possessions, weekend breaks
Hovinsaari: superstructure renewal and turnout work on tracks r035-r038	x	Alterations in track usage
Kouvola-Luumäki: replacement of 4 long turnouts	x	Only one track in use, weekend breaks
Kouvola-Luumäki: ballast and rail replacements on the northern track	x	Only one track in use, daily 8h track possession
Luumäki-Vainikkala: replacement of 2 long turnouts in Raippo	x	Only one track in use, weekend breaks
Vainikkala: signal box renewal, extension of tracks in the eastern marshalling yard	x	Alterations in track usage and weekend breaks
Lappeenranta-Imatra: railway bridges at Saimaa Canal and Mansikkakoski, underpass at main road 6	x	10h weekend breaks, 24-36h weekend breaks when the bridge is moved
Kuopio-Pieksämäki: tunnel repairs at Pieni Neulamäki, Mustamäki and Mustavuori 1 and Mustavuori 2	x	Weekend breaks
Alteration of Kuopio traffic operating point	x	Alterations in track usage and traffic breaks
Kuopio: repairs on Puijonkatu and	x	In connection with alterations at



Location	Affects traffic	Break description
Maaherrankatu underpasses		traffic operating point
Jyväskylä-Pieksämäki: superstructure renewal	x	Daily 8-10h track possessions, weekend breaks.
Jyväskylä-Pieksämäki: repair of Halssila underpass	x	In connection with renewal of superstructure
Jyväskylä-Äänekoski: major repair of superstructure, renovation of traffic operating points, electrification, major repair of Kangasvuori tunnel	x	Daily 8-10h track possessions in April-August, weekend breaks
Parikkala-Säkäniemi: renewal of superstructure	x	Daily 8-10h track possessions, weekend breaks.
Vuokatti-Kontiomäki: renewal of superstructure	x	Daily 10h track possessions, total breaks
<b>WESTERN FINLAND</b>		
Turku-Toijala: building of Kyrö underpass	x	36h weekend break
Riihimäki-Tampere: rail replacement, continuous tamping of both tracks	x	Only one track in use, nightly 6h track possessions
Riihimäki-Tampere: renewal of signal boxes, ATP alterations required for 25t axle load on the Tampere-Hämeenlinna line	x	Only one track in use, ATP construction areas, track possessions on weeknights and weekends. 4-6 breaks lasting 8-16h each when the equipment is taken into use.
Toijala-Tampere: Lempäälä Canal and underpass	x	Only one track in use and weekend breaks
Tampere deck and Central Arena project: deck construction, turnout and track alterations at the southern end of the Tampere passenger railway yard	x	Alterations in track usage, no other work affecting traffic in 2017
Tampere-Orivesi: rail replacement on 37 km of the southern track	x	Only one track in use, daily 8h track possession
Tampere-Orivesi: increasing of capacity, signalling work	x	ATP construction area, only one track in use. Breaks when the signalling is introduced. Coordinated with the rail replacement work
Jämsänkoski-Jyväskylä: major improvement of tunnels, ballast operations	x	Daily 8-10h track possessions in April and July, weekend breaks. Total break for two months in May-June
Tampere: construction of the remote control system (TAKO) and its introduction on the lines Tampere-Pieksämäki, Jyväskylä-Äänekoski and Tampere-Seinäjoki	-	
Tampere region: renewal of the remote control system (TASKU) on the electrified line	-	
Renewal of substations: Kukkola SA, Arometsä SA, Riihimäki VK, Iittala VK ja Vanattara VK	x	Weeknight and weekend breaks

Location	Affects traffic	Break description
Tampere-Seinäjoki: replacement of long turnouts on main line for high-speed traffic	x	Weekend breaks. Restrictions imposed on passing track
Tampere-Seinäjoki: upgrading to 25t axle loads, ATP alterations	x	Weekend breaks
Kokkola-Ykspihlaja: renewal of superstructure	x	Daily 8 h track possessions
Improved level of service on the Seinäjoki–Oulu section: Building of Kokkola-Ylivieska double track	x	16-20h weekend breaks, 24h Midsummer break, ATP construction areas
Hämeenlinna: building of track to SSAB factory. Joint venture between the factory, the city and the Finnish Transport Agency.	x	Total break for 3 weeks
<b>NORTHERN FINLAND</b>		
Improved level of service on the Seinäjoki–Oulu section: Ylivieska: renewal of Kalajoki railway bridges. Liminka-Oulu: realignment of the track at Temmesjoki	x	12.5-17.5h weekend breaks, Midsummer break, 48h weekend break at Ylivieska traffic operating point and Liminga
Ylivieska: renewal of signal box	x	Restricted track use, ATP construction areas, weekday track possessions and weekend breaks
Tuomioja-Raahe: upgrading to 25t axle loads.	x	Daily track possessions and weekend breaks. ATP construction areas. Coordinated with the work on the Seinäjoki-Oulu railway line
Oulu: Heikinkatu underpass	x	Only one track in use north of Oulu station. 2-4 days Midsummer break
Oulu-Muhos: renewal of superstructure	x	From July onwards 10h track possessions Mon-Fri during 15 weeks. Sporadic weekend breaks. 3h track possessions in April-May on specified days for rail distribution
Oulu-Laurila: renewal of 112 km of superstructure	x	Daily 8h track possessions, weekend breaks
Laurila–Tornio: major improvement and painting of railway bridges at Raumonjoki, Kaakamojoki and Keropudas	x	Daily 8h track possessions
Misi-Kemijärvi: renewal of superstructure	x	Daily 10h track possessions
Rovaniemi-Kemijärvi: painting of Ounaskoski railway bridge	x	Daily 10h track possessions
Murtomäki-Kontiomäki: renewal of 44 km of superstructure	x	Daily 8-10h track possessions
Arola-Vartiuss: rail replacement	x	Daily 8h track possessions

Location	Affects traffic	Break description
<b>OTHER TRACK POSSESSION REQUIREMENTS</b>		
Investments to improve punctuality	x	-
Level crossing renewals and removals, station arrangements	x	-
Bridge, culvert and superstructure repairs	x	-
Tunnel repairs	x	Weekend breaks on some railway sections
Renewal and maintenance of the catenary system, its carrying cable, foundations	x	-
Investments to secure availability of raw materials for the wood processing industry	x	-
Repairs of areas with frost heave damage and soft soils on the following line sections: Siilinjärvi-Iisalmi, Kuopio-Siilinjärvi, Iisalmi-Kontiomäki, Kontiomäki-Vartius, Iisalmi-Ylivieska, Joensuu-Siilinjärvi, Joensuu-Kontiomäki, Kirkkonummi-Turku, Karjaa-Hanko, Helsinki-Kirkkonummi, Helsinki-Riihimäki, Riihimäki-Tampere, Riihimäki-Lahti, Lahti-Kouvola, Toijala-Turku, Hyvinkää-Karjaa, Kerava-Sköldvik, Kouvola-Kotka, Juurikorpi-Hamina, Kouvola-Pieksämäki, Kouvola-Joensuu, Luumäki-Vainikkala, Säkäniemi-Niirala	x	-
Replacement of individual turnouts at the following railway yards: Helsinki, Kouvola, Kotka, Hamina, Vainikkala, Harakka marshalling yard in Imatra, Joensuu, Pieksämäki, Tampere, Seinäjoki, Jyväskylä, Turku, Riihimäki, Oulu	x	8-16h track possessions
Walking inspections on tracks where the maximum allowed speed exceeds 140 km/h	x	-
Maintenance tamping of tracks and turnouts	x	-
Replacement of single sleepers and worn rails in curves	x	-
Rolling stock monitoring equipment	x	-
Removal of mandatory signals at sets of tracks	-	-
Kerava-Vuosaari: Maintenance of Savio tunnel	x	8 h track possession on Mondays
Helsinki-Riihimäki: catenary	x	4 h track possessions on the first night

Location	Affects traffic	Break description
maintenance		between Monday and Tuesday of the month

## CONTACTS

Traffic and track work coordinators (Finrail Oy)

### YHTEYSTIEDOT

Liikennesuunnittelijat (Finrail Oy)

#### Helsinki

[liikennesuunnittelu.helsinki@liikenteenohjaus.fi](mailto:liikennesuunnittelu.helsinki@liikenteenohjaus.fi)

Miikkola Reijo 040 866 3840  
Lahtinen Hannu 040 866 3751  
Hyppänen Pertti 040 862 0926

#### Tampere

[liikennesuunnittelu.tampere@liikenteenohjaus.fi](mailto:liikennesuunnittelu.tampere@liikenteenohjaus.fi)

Jalanto Esko 040 863 0570  
Kunelius Juha 040 863 1118

#### Oulu

[liikennesuunnittelu.oulu@liikenteenohjaus.fi](mailto:liikennesuunnittelu.oulu@liikenteenohjaus.fi)

Meripaasi Sakari 040 864 5450  
Tumelius Tommi 040 864 5446

#### Kouvola

[liikennesuunnittelu.kouvola@liikenteenohjaus.fi](mailto:liikennesuunnittelu.kouvola@liikenteenohjaus.fi)

Lahtinen Juha 040 863 4271  
Papunen Arto (Joensuu) 040 864 0379

## Traffic and track work coordination areas

### Liikennesuunnittelualueet

- Helsinki
- Tampere
- Oulu
- Kouvola




Figure 1. Traffic and track work coordination areas and contacts

## Passenger Information at the Traffic Operating Points in the State-owned Railway Network

The Finnish Transport Agency is responsible for the electronic and fixed passenger information at railway stations and in platform areas. The electronic information is produced in the passenger information and announcement system MIKU. MIKU generally produces information automatically, but in exceptional situations the personnel of the Information Centre or the Traffic Control enters the data on the screens or give announcements.

Possible changes will be updated on the FTA's website

<http://www.liikennevirasto.fi/ammattiliikenne-raiteilla/rautateiden-verkkoselostus#.VjeAILU8Kpo>

Table 1. Passenger information at traffic operating points.

Station	Swedish name of station	No information system	Only announcement system	Track displays	Main displays	(bridge and other)	LCD monitors	Tunnel displays	TFT displays	Total
<b>Total</b>		<b>14</b>	<b>63</b>	<b>506</b>	<b>36</b>	<b>6</b>	<b>41</b>	<b>3</b>	<b>443</b>	<b>1112</b>
Ainola				2	0	0	0	0	0	2
Alavus			1	0	0	0	0	0	0	1
Aviapolis				6	0	0	0	0	3	9
Dragsvik		1		0	0	0	0	0	0	1
Eläinpuiisto-Zoo			1	0	0	0	0	0	0	1
Eno			1	0	0	0	0	0	0	1
Espoo	Esbo			6	0	0	0	0	14	20
Haapajärvi			1	0	0	0	0	0	0	1
Haapamäki				0	0	0	0	0	0	0
Haarajoki				4	0	0	0	0	4	8
Hankasalmi			1	0	0	0	0	0	0	1
Hanko	Hangö		1	0	0	0	0	0	0	1
Hanko-Pohjoinen	Hangö Norra	1		0	0	0	0	0	0	1
Harjavalta				0	0	0	0	0	1	1
Haukivuori			1	0	0	0	0	0	0	1
Heinävesi			1	0	0	0	0	0	0	1
Helsinki	Helsingfors			25	6	2	10	3	38	84
Herrala			1	0	0	0	0	0	0	1
Hiekkaharju	Sandkulla			4	0	0	0	0	2	6
Hikiä			1	0	0	0	0	0	0	1
Humppila				3	0	0	0	0	2	5
Huopalahti	Hoplax			8	0	0	0	0	10	18
Hyvinkää	Hyvinge			4	0	0	0	0	4	8
Hämeenlinna	Tavastehus			5	2	0	0	0	4	11

Station	Swedish name of station	No information system	Only announcement system	Track displays	Main displays	(bridge and other	LCD monitors	Tunnel displays	TFT displays	Total
Höljäkkä		1		0	0	0	0	0	0	1
Iisalmi	Idensalmi			1	0	0	0	0	2	3
Iittala				2	0	0	0	0	0	2
Ilmala				2	0	0	0	0	2	4
Imatra				2	0	0	0	0	2	4
Inkeroinen			1	0	0	0	0	0	0	1
Inkoo	Ingå			2	0	0	0	0	0	2
Isokyrö	Storkyro		1	0	0	0	0	0	0	1
Joensuu				3	0	0	0	0	6	9
Jokela				4	0	0	0	0	2	6
Jorvas				2	0	0	0	0	0	2
Joutseno				2	0	0	0	0	0	2
Juupajoki			1	0	0	0	0	0	0	1
Jyväskylä				3	2	0	10	0	0	15
Jämsä				2	0	0	0	0	1	3
Järvelä			1	0	0	0	0	0	0	1
Järvenpää	Träskända			7	0	0	0	0	4	11
Kajaani	Kajana			1	0	0	0	0	2	3
Kannelmäki	Gamlas			2	0	0	0	0	0	2
Kannus				2	0	0	0	0	1	3
Karjaa	Karis			7	0	0	1	0	4	12
Karkku			1	0	0	0	0	0	0	1
Kauhava				1	0	0	0	0	0	1
Kauklahti	Köklax			3	0	0	0	0	1	4
Kauniainen	Grankulla			3	0	0	0	0	2	5
Kausala				2	0	0	0	0	0	2
Kemi				2	0	0	0	0	2	4
Kemijärvi			1	0	0	0	0	0	0	1
Kempele				1					1	2
Kera				2	0	0	0	0	0	2
Kerava	Kervo			10	0	0	0	0	11	21
Kerimäki			1	0	0	0	0	0	0	1
Kesälahti				1	0	0	0	0	0	1
Keuruu			1	0	0	0	0	0	0	1
Kilo				4	0	0	0	0	0	4
Kirkkonummi	Kyrkslätt			3	0	0	0	0	3	6
Kitee				1	0	0	0	0	1	2
Kiuruvesi			1	0	0	0	0	0	0	1
Kivistö				6	0	0	0	0	3	9
Kohtavaara		1		0	0	0	0	0	0	1
Koivuhovi	Björkgård			2	0	0	0	0	0	2
Koivukylä	Björkby			4	0	0	0	0	5	9

Station	Swedish name of station	No information system	Only announcement system	Track displays	Main displays (bridge and other)	LCD monitors	Tunnel displays	TFT displays	Total
Kokemäki	Kumo			0	0	0	0	0	0
Kokkola	Karleby			6	0	0	0	2	8
Kolari				0	0	0	0	2	2
Kolho			1	0	0	0	0	0	1
Kontiomäki				0	0	0	0	1	1
Koria				2	0	0	0	0	2
Korso				4	0	0	0	2	6
Kotka				0	0	0	0	1	1
Kotkan satama			1	0	0	0	0	0	1
Kouvola				13	2	0	5	2	22
Kuopio				4	0	0	0	6	10
Kupittaa	Kuppis			4	0	2	2	4	12
Kylänlahti		1		0	0	0	0	0	1
Kymi	Kymmene	1		0	0	0	0	0	1
Kyminlinna		1		0	0	0	0	0	1
Käpylä	Kottby			4	0	0	0	2	6
Lahti	Lahtis			12	2	0	0	5	19
Laihia	Laihela		1	0	0	0	0	0	1
Lapinlahti				2	0	0	0	0	2
Lappeenranta	Villmanstrand			3	0	0	4	1	8
Lappila			1	0	0	0	0	0	1
Lappohja	Lappvik	1		0	0	0	0	0	1
Lapua	Lappo			2	0	0	0	0	2
Leinelä	Lejle			6	0	0	0	3	9
Lempäälä				2	0	0	0	0	2
Lentoasema	Flygplatsen			6	0	0	0	3	9
Leppävaara	Alberga			8	0	0	1	5	14
Lieksa			1	0	0	0	0	0	1
Lievestuore			1	0	0	0	0	0	1
Loimaa				1	0	0	0	1	2
Louhela	Klippsta			2	0	0	0	2	4
Luoma	Bobäck			2	0	0	0	0	2
Lusto			1	0	0	0	0	0	1
Malmi	Malm			4	0	0	0	8	12
Malminkartano	Malmgård			4	0	0	0	4	8
Mankki	Mankby			2	0	0	0	0	2
Martinlaakso	Mårtensdal			4	0	0	0	2	6
Masala	Masaby			4	0	0	0	0	4
Mikkeli	St. Michel			5	0	2	0	7	14
Misi		1		0	0	0	0	0	1
Mommila			1	0	0	0	0	0	1
Muhos			1	0	0	0	0	0	1

Station	Swedish name of station	No information system	Only announcement system	Track displays	Main displays (bridge and other)	LCD monitors	Tunnel displays	TFT displays	Total
Muurola			1	0	0	0	0	0	1
Myllykoski			1	0	0	0	0	0	1
Myllymäki			1	0	0	0	0	0	1
Myyrmäki	Myrbacka			2	0	0	0	1	3
Mäkkylä				2	0	0	0	2	4
Mäntsälä				4	0	0	0	4	8
Mäntyharju				4	0	0	0	1	5
Nastola				2	0	0	0	0	2
Nivala			1	0	0	0	0	0	1
Nokia			1	0	0	0	0	1	2
Nuppulinna				2	0	0	0	0	2
Nurmes			1	0	0	0	0	0	1
Oitti			1	0	0	0	0	0	1
Orivesi				2	0	0	0	1	3
Orivesi keskusta				0	0	0	0	0	0
Oulainen				3	0	0	0	1	4
Oulu	Uleåborg			6	2	0	0	5	13
Oulunkylä	Äggelby			4	0	0	0	4	8
Paimenportti		1		0	0	0	0	0	1
Paltamo			1	0	0	0	0	0	1
Parikkala				5	0	0	0	2	7
Parkano				3	0	0	0	2	5
Parola				2	0	0	0	0	2
Pasila	Böle			40	4	0	1	56	101
Pasila autojuna-asema	Böle biltågstation			2	0	0	0	2	4
Pello			1	0	0	0	0	0	1
Petäjävesi			1	0	0	0	0	0	1
Pieksämäki				9	2	0	0	2	13
Pihlajavesi			1	0	0	0	0	0	1
Pitäjänmäki	Sockenbacka			4	0	0	0	4	8
Pohjois-Haaga	Norra Haga			2	0	0	0	2	4
Pori	Björneborg			0	0	0	0	3	3
Puistola	Parkstad			4	0	0	0	4	8
Pukinmäki	Bocksbacka			4	0	0	0	3	7
Punkaharju			1	0	0	0	0	0	1
Purola				2	0	0	0	0	2
Pyhäsalmi			1	0	0	0	0	0	1
Pännäinen	Bennäs			4	0	0	0	1	5
Pääskylahti			1	0	0	0	0	0	1
Rekola	Räckhals			2	0	0	0	1	3
Retretti		1		0	0	0	0	0	-



Station	Swedish name of station	No information system	Only announcement system	Track displays	Main displays	(bridge and other	LCD monitors	Tunnel displays	TFT displays	Total
Riihimäki				8	6	0	3	0	11	28
Rovaniemi				3	0	0	0	0	5	8
Runni			1	0	0	0	0	0	0	1
Ruukki			1	0	0	0	0	0	0	1
Ryttylä				2	0	0	0	0	0	2
Salo				6	0	0	1	0	3	10
Santala	Sandö	1		0	0	0	0	0	0	1
Saunakallio				4	0	0	0	0	0	4
Savio				4	0	0	0	0	1	5
Savonlinna	Nyslott			0	0	0	0	0	1	1
Seinäjoki				9	2	0	0	0	7	18
Siilinjärvi				1	0	0	0	0	1	2
Simpele			1	0	0	0	0	0	0	1
Siuntio	Sjundeå			2	0	0	0	0	0	2
Skogby		1		0	0	0	0	0	0	1
Sukeva			1	0	0	0	0	0	0	1
Suonenjoki				1	0	0	0	0	1	2
Tammisaari	Ekenäs		1	0	0	0	0	0	0	1
Tampere	Tammerfors			15	2	0	0	0	27	44
Tapanila	Mosabacka			4	0	0	0	0	2	6
Tavastila		1		0	0	0	0	0	0	1
Tervajoki			1	0	0	0	0	0	0	1
Tervola			1	0	0	0	0	0	0	1
Tikkurila	Dickursby			18	0	0	0	0	55	73
Toijala				4	0	0	0	0	3	7
Tolsa	Tolls			2	0	0	0	0	0	2
Tornio-Itäinen	Torneå Östra		1	0	0	0	0	0	0	1
Tuomarila	Domsby			3	0	0	0	0	0	3
Turenki				2	0	0	0	0	0	2
Turku	Åbo			9	2	0	3	0	3	17
Turku satama	Åbo hamn			2	0	0	0	0	3	5
Tuuri			1	0	0	0	0	0	0	1
Uimaharju			1	0	0	0	0	0	0	1
Utajärvi			1	0	0	0	0	0	0	1
Uusikylä				2	0	0	0	0	0	2
Vaala			1	0	0	0	0	0	0	1
Vaasa	Vasa			2	2	0	0	0	4	8
Vainikkala			1	0	0	0	0	0	0	1
Valimo	Gjuteriet			4	0	0	0	0	1	5
Vammala			0	0	0	0	0	0	1	1
Vantaankoski	Vandaforsen			6	0	0	0	0	3	9
Varkaus				0	0	0	0	0	3	3

Station	Swedish name of station	No information system	Only announcement system	Track displays	Main displays (bridge and other)	LCD monitors	Tunnel displays	TFT displays	Total
Vehkala	Veckal			6	0	0	0	3	9
Vihanti				4	0	0	0	1	5
Vihtari			1	0	0	0	0	0	1
Viiala				2	0	0	0	0	2
Viinijärvi			1	0	0	0	0	0	1
Villähde				2	0	0	0	0	2
Vilppula			1	0	0	0	0	0	1
Vuonisahti			1	0	0	0	0	0	1
Ylistaro			1	0	0	0	0	0	1
Ylitornio	Övertorneå		1	0	0	0	0	0	1
Ylivieska				3	0	0	0	2	5
Ähtäri	Etseri		1	0	0	0	0	0	1

# Description and Pricing of the Traffic Control Service for Shunting Operations

## 1 Description of traffic control service for shunting operations

This document describes the traffic control services that the Finnish Transport Agency offers railway operators in return for the infrastructure charge, as included in the allocated rail capacity. The document also includes descriptions of other traffic control services that the Finnish Transport Agency may offer to railway operators, which are not included in the infrastructure charge but instead covered by a separate service charge. Provision of traffic control services not covered by the infrastructure charge shall be agreed upon with the Finnish Transport Agency. Services requiring signal box and shunting operators shall be agreed upon with the provider of other services, depending on the traffic operating point.

### **Traffic control services in return for the infrastructure charge**

#### Train traffic control

##### Trains departing from their departure station

- Moving a locomotive to the front of an already coupled set of wagons (including change of locomotives while underway)
- Moving a set of wagons from a storage siding or loading siding to the departure track. This also includes moving a full departing set of wagons in a marshalling yard to the departure track, if the train cannot depart from the sorting siding for infrastructure reasons.

##### Shunting operations and locomotives looping intermediate traffic operating points:

- Permission for shunting operations
- Local permissions
- Moving the locomotive from one end of the set of wagons to the other when changing direction.

##### Removing suddenly damaged rolling stock from the train, immediate actions.

##### Trains arriving at their destination station:

- Moving the locomotive from the front of the set of wagons to a storage siding or yard track (also applies to locomotives changed while underway)
- Moving an arriving train, without changing the train formation, from the departure siding to a storage siding, a loading/unloading track (or to a new departure track, see below)
- Moving a locomotive, which has hauled an arriving set of wagons to a storage siding, a loading/unloading track or to a new departure track, to a storage siding or yard track, or to the front of a departing set of wagons (on-call operations covered by a separate service charge).

On-call units:

- Permission for shunting operations
- Local permissions

If a traffic control service covered by the infrastructure charge described here cannot be fully provided due to technical circumstances (operation of points) by anyone other than the railway operator's staff travelling in the rolling stock, this is not considered "shunting operations in line service", and therefore the railway operator shall not invoice the Finnish Transport Agency for these operations.

Similarly, if there is no local traffic control staff or shunting or signal box operators in the marshalling yard, the railway operator shall operate the points.

Moving departing sets of wagons to departure tracks and arriving trains to service or storage sidings are included in the basic infrastructure charge.

The additional service charge covers arrangements regarding rolling stock which have been damaged in Helsinki and in the railway network, moving parts of arriving sets of wagons to another departure track, as well as sorting sets of wagons for service or storage.

The required changes are discussed in the meetings on railway network access.

## **2 Pricing of the traffic control service for shunting operations (additional service not included in the infrastructure charge)**

The pricing of traffic control service for shunting operations is based on performance. The railway operator's need for a control service, the time used for traffic control shunting operations and the performance-based price for traffic control have been taken into account when calculating the price. The traffic control performance refers to the so-called shunting route in one direction.

- The railway operator reports his need of traffic control to the Finnish Transport Agency in a mutually agreed-upon manner. The quantity describing the control need is determined on a case-by-case basis (for example shunting route, number, time)
- The time used for the traffic control performance and the performance quantity is specified/confirmed at least twice a year on the basis of the weekly follow-up carried out by the traffic control.
- A 12% margin is added to the results of the weekly follow-ups in order to ensure availability of the service and flexibility in situations that change daily without having to reserve resources in advance.
- The performance price of the traffic control service for shunting operations correlates directly to the cost of the traffic control function. The annual price is confirmed by the end of April of the year in question. Before that, the previous year's price will be used.

At least four times a year, the Finnish Transport Agency will send the railway operator a pro-forma invoice, including a performance-based estimate and the total price.

## Speed depending on the rolling stock

The rolling stock for which the Finnish Transport Safety Agency has granted a commissioning licence, which is valid until further notice, has been listed in the tables below. As soon as the above mentioned commissioning licence has been granted, the rolling stock type will be entered into the respective table.

*Table 1. Maximum speed allowable for locomotives and train sets*

Superstructure category						
Series	A <sup>1</sup>	B <sub>1</sub>	B <sub>2</sub>	C <sub>1</sub>	C <sub>2</sub>	D
Dv12	50 <sup>2, 3</sup>	100	110	125	125	125
Dv17 9810 6003070-8	30	40	40	40	40	40
Dr14, added weight	–	50	75 <sup>4</sup>	75 <sup>4</sup>	75 <sup>4</sup>	75 <sup>4</sup>
Dr16	–	70	110	140 <sup>5</sup>	140 <sup>5</sup>	140 <sup>5</sup>
Dr17 9810 6007001-9	30	65	65	65	65	65
Dr17 9810 6006010-1	–	50	50	50	50	50
Dr25 9810 8029002-7	20	25	25	25	25	25
Dr25 9810 8129002-6	20	25	25	25	25	25
Dr25 9810 8129003-4	20	25	25	25	25	25
Dr35 9810 8039011-6	20	60	60	60	60	60
Dr35 9810 8139005-7	–	30	30	30	30	30
Dr35 9810 8139006-5	–	30	30	30	30	30
Dr35 9810 8039013-2	35	60	60	60	60	60
Dr45 9810 8049001-5	–	60	60	60	60	60
Sr1	–	80	100	140	140	140
Sr2	–	80	100	180 <sup>6</sup>	200	210
Motor cars						
Sm1, Sm2	–	90	110	120	120	120
Sm3	–	100	110	180	200	220
Sm4	–	90	110	160	160	160
Sm5	–	90	110	160	160	160
Sm6	–	100	110	180	200	220
Dm12	50	100	110	120	120	120

<sup>1</sup> For tracks belonging to superstructure category A, see USE OF LOCOMOTIVES ON TRACKS BELONGING TO SUPERSTRUCTURE CATEGORY A.

<sup>2</sup> Max. speed 40 km/h in curves with a radius under 600 m. Max. speed 60 km/h on the line section Äänekoski-Haapajärvi.

<sup>3</sup> 20 km/h in the deflecting section of K30 turnouts.

<sup>4</sup> 80 km/h when hauled.

<sup>5</sup> 135 km/h without wagons, either on its own or with double heading.

<sup>6</sup> 160 km/h without wagons. 160 km/h with double heading.

## SMALL-POWER LOCOMOTIVES AND TRACK MOTOR CARS

(Towing speed in brackets, if it differs from the maximum speed when self-propelled)

Superstructure category				
Series	A <sup>1</sup>	B <sub>1</sub>	B <sub>2</sub>	C <sub>1</sub> , C <sub>2</sub> ja D
Tve1	30 (60)	30 (80)	30 (80)	30 (80)
Tve2	45 (60)	45 (80)	45 (80)	45 (80)
Tve4	35	60	80	80
Tve5	20 (50)	20 (50)	20 (50)	20 (50)
Tka3–6	60	60 (80)	60 (80)	60 (80)
Tka7, numbers 168–238, 243–247	60	80	80	80
Tka7, with snow plough, numbers 168–238	35 <sup>7</sup>	60 <sup>7</sup> (80)	60 <sup>7</sup> (80)	60 <sup>7</sup> (80)
Tka7, numbers 239–242	50	80	80	80
Tka7 with snow plough, numbers 239–247	35 <sup>7</sup>	60 <sup>7</sup> (80)	60 <sup>7</sup> (80)	60 <sup>7</sup> (80)
Tka7, with welding container, numbers 168–238, 243–247	35	60	60	80
Tka8	35	60	80	80
Tka9 numbers 91901	20 <sup>8</sup>	50 <sup>8</sup>	70 <sup>8</sup>	70 <sup>8</sup>
Otso4 numbers 920001	20 <sup>9</sup>	45	45	45

## MAXIMUM ALLOWABLE SPEED FOR SELF-PROPELLED MACHINERY

(Hauling speed in brackets, if the machine can be coupled to the train and the hauling speed differs from the above mentioned)

Superstructure category				
Series	A	B <sub>1</sub>	B <sub>2</sub>	C <sub>1</sub> , C <sub>2</sub> , D
<b>Track inspection cars</b>				
Et number 66	20 <sup>10</sup>	60	60	100
Ttr1 number 51	60	80	120	120
<b>Snow brooms</b>				
Tlh number 741 <sup>11</sup>	50	60	60	60
<b>Snow ploughs</b>				
Tla 90109691001-2	35	60	60	60
<b>Rail planing machines</b>				
Tkh number 894 <sup>11</sup>	60	80	80	80
<b>Track renewal machines</b>				
Trk number 870	20	20 (50)	20 (80)	20 (100)
<b>Ballast ploughs</b>				
Tsl numbers 880, 882, 884, 885, 890 <sup>11</sup>	70	80	80	80

<sup>7</sup> The maximum snow-ploughing speed is specified in the machine operator's manual.

<sup>8</sup> Hauling according to the manufacturer's instructions.

<sup>9</sup> 20 km/h on sidings which belong to superstructure category A.

<sup>10</sup> Same as the maximum speed on the section in question, as assessed by a railway technology specialist taking the measurements, and a representative of the local maintenance entrepreneur.

<sup>11</sup> Wheel diameter max. 790 mm, which necessitates caution in diamond crossings with slips.

Superstructure category				
Series	A	B <sub>1</sub>	B <sub>2</sub>	C <sub>1</sub> , C <sub>2</sub> , D
Tsl number 883 <sup>11</sup>	35	50	60	60
Tsl number 888 <sup>11</sup>	50	60	60	80
Tsl number 889 <sup>11</sup>	20	50	80	80
Tsl number 91021	20	70	70	70
<b>Ballast cleaning machines</b>				
Tsp numbers 891, 893	20	60	80	80
Tsp number 892	50	80	80	80
<b>Multi-purpose machines</b>				
Ttm1 number 91101	20 <sup>12</sup>	50	70	70
<b>Tamping machines</b>				
Ttk1 <sup>11</sup> numbers 801–803, 821, 823, 831, 91042	60	80	80	80
<b>Multi-purpose machines</b>				
Ttk1 <sup>11</sup> numbers 818–820	25 (50) <sup>13</sup>	25 (50) <sup>13</sup>	25 (50) <sup>13</sup>	25 (50) <sup>13</sup>
Ttk1 <sup>11</sup> numbers 822, 824–829	50	50 (80)	50 (80)	50 (80)
Ttk1 <sup>11</sup> numbers 830	60	85 (90)	85 (90)	85 (90)
Ttk1 <sup>11</sup> numbers 832, 833	50	80	80	80
Ttk1 number 834	50 <sup>14</sup>	80	80	80
Ttk1 <sup>11</sup> number 91041	60	60	60	60
Ttk1 number 91042	60	70	70	70
Ttk1 number 9010 9122002-9	50	80	80	80
Ttk1 number 9010 9422001-8	50	80	80	80
<b>Stabilisation machines</b>				
Ttk2 numbers 841, 844, 849 <sup>11</sup>	60	80	80	80
Ttk2 number 842 <sup>11</sup>	35	60	60	80
Ttk2 numbers 850, 856	20	60	80	90 (100)
Ttk2 numbers 851–855 <sup>11</sup>	50	50 (80)	50 (80)	50 (80)
Ttk2 number 857	20	60	80	80 (100)
Ttk2 nro 858	– <sup>14</sup>	60	75	90 (100)
Ttk2 number 859	20 <sup>14</sup>	60	75	90 (100)
Ttk2 number 91051	15	35	50	70 <sup>16</sup>
<b>Ballast compacting machines</b>				
Ttk3 nrot 862, 863 <sup>11</sup>	60	80	80	80
<b>Tamping machines</b>				
Ttk4 number 91501	20	40	40	40
Ttk5 number 9010 9422001-8	50	80	80	80
<b>Service and inspection vehicles on electrified lines</b>				
Tta numbers 1, 2	30 <sup>16</sup>	30 <sup>16</sup>	50 <sup>16</sup>	50 <sup>16</sup>
Tta number 3	30 <sup>16</sup>	50 <sup>16</sup>	70 <sup>16</sup>	70 <sup>16</sup>
Tte numbers 21–29	70	100	110	110
Tte numbers 91201, 91202	20	60	80	80
Ttv numbers 6, 9, 12, 15	50	70	70	90

<sup>12</sup> Max. axle load of trailer vehicle 160 kN (16 t).

<sup>13</sup> 15 km/h in turnouts.

<sup>14</sup> Max. 20 km/h on sidings which belong to railway category A.

<sup>15</sup> Max. hauling speed 80 km/h.

<sup>16</sup> 5 km/h in diamond crossing with slips, due to the small wheel diameter (440 mm).

Superstructure category				
Series	A	B <sub>1</sub>	B <sub>2</sub>	C <sub>1</sub> , C <sub>2</sub> , D
<b>Rail-mounted cranes</b>				
Tnk4 numbers 982, 983	15 (20)	15 (50)	15 (60)	15 (60)
Tnk4 number 984	15 (50)	15 (60)	15 (60)	15 (60)
Tnk4 numbers 985–989	15 (60)	15 (60)	15 (60)	15 (60)
Tnk4 number 990	15 (20)	15 (50)	15 (60) <sup>17</sup>	15 (60) <sup>17</sup>
<b>Electrification trains</b>				
Tnv-sr numbers 911002, 911003	40 (40)	40 (60)	40 (80)	40 (100)

## MAXIMUM SPEED FOR MUSEUM LOCOMOTIVES

(Hauling speed in brackets, whether it differs from the maximum speed when self-propelled)

Superstructure category				
Series	A <sup>18</sup>	B <sub>1</sub>	B <sub>2</sub>	C <sub>1</sub> , C <sub>2</sub> , D
Dr12	20 <sup>19</sup>	60 <sup>20</sup>	90	120
Dr13	20 <sup>19</sup>	100	110	120
Dv15	60	75 (80)	75 (80)	75 (80)
Dv16	60	85	85	85
Hr1	20 <sup>19</sup>	80	100	110 <sup>21</sup>
Hv1	60	80	80	80
Hv3	20 <sup>22</sup>	70	70	70
Pr1	20 <sup>19</sup>	80	80	80
Tk3	60	60	60	60
Tr1	20 <sup>19</sup>	80	80	80
Vr1	40 <sup>23</sup>	40	40	40
Rau 2	70	70	70	70
Dm7	70	95	95	95
Dm9	50	100	110	120

## USE OF LOCOMOTIVES ON TRACKS BELONGING TO SUPERSTRUCTURE CATEGORY A

Locomotives of the Dr and Sr series must not operate on tracks belonging to superstructure category A. Locomotives of the Dr and Sr series are allowed to operate at a maximum speed of 20 km/h on sidings when carrying out renewal work. Other types of locomotives may operate at a maximum speed of 50 km/h on tracks belonging to superstructure category A.

<sup>17</sup> Hauling speed 80 km/h, when the balance weight has been moved to the crane trailer.

<sup>18</sup> For tracks belonging to superstructure category A, see USE OF LOCOMOTIVES ON TRACKS BELONGING TO SUPERSTRUCTURE CATEGORY A.

<sup>19</sup> Operation only allowed on sidings.

<sup>20</sup> 80 km/h on the line sections Orivesi–Haapamäki and Haapamäki–Jyväskylä.

<sup>21</sup> 100 km/h without wagons, either on its own or with double heading.

<sup>22</sup> Max. speed 20 km/h in the deflecting section of K30 turnouts.

<sup>23</sup> 25 km/h on its own.



## Transport of overweight wagons

A wagon whose axle load exceeds the maximum axle load given for the different line sections in the appendix 6 is overweight for that line section. The terms for transporting wagons with an axle load over 225 kN in eastern transit traffic are listed below.

The load specified in the wagon load table may not be exceeded intentionally. Any excess load must be unloaded at the first possible traffic operating point, if the load exceeds the permitted load by more than 5% when the maximum axle load is 225 kN or by more than 2% when the maximum axle load is 250 kN.

Overweight wagons must be transported in line with the regulations governing exceptional transport. Before transport the wagon's wheel sets and the rest of the bogie structure must be inspected.

Temporary transport of overweight wagons can be considered in case of ad hoc need. Any temporary transport of overweight loads must be notified to the track's maintenance operator with a view to monitoring the condition of the track superstructure.

### Transport of overweight wagons in the domestic and western transit traffic

When the maximum axle load of a wagon is 225 kN, individual wagons bearing excess weight may be transported at no more than the following speeds:

Superstructure category	Maximum axle load kN	Speed km/h
A	225 <sup>1</sup>	20 <sup>24</sup>
B1	235	35
B2	235	50
C1, C2, D	235	80

**Transport of wagons with an axle load over 225 kN in the eastern transit traffic and on line sections belonging to superstructure categories C and D, on which it is allowed to operate with a maximum axle load of 250 kN.**

Maximum axle load 245 kN.

In the eastern transit traffic, individual wagons with an axle load over 225 kN, but no more than 245 kN, may be transported at the speed limit imposed on axle loads exceeding 225 kN.

Maximum speed 60 km/h.

---

<sup>1</sup> On main lines and secondary tracks belonging to superstructure category A, individual overweight wagons with axle loads exceeding 200 kN, but no more than 225 kN, may only be transported on a temporary basis at a speed of 20 km/h. It is prohibited to operate wagons with an axle load exceeding 225 kN on main lines and secondary tracks.

**Transport of wagons with an axle load over 225 kN in the eastern transit traffic and on line sections belonging to superstructure categories C and D, on which it is allowed to operate with a maximum axle load of 225 kN.**

a) Axle load over 225 kN, but no more than 235 kN  
Maximum speed 60 km/h.

Maximum axle load 235 kN.

In the eastern transit traffic, individual wagons with an axle load over 225 kN, but no more than 235 kN, may be transported at the speed limit imposed on axle loads exceeding 225 kN.

b) Axle load over 235 kN

In case the axle load of a wagon in the eastern transit traffic exceeds 235 kN, the Rail Traffic Management Centre at the Finnish Transport Agency grants transport permits up to an axle load of 245 kN on the line sections listed below. For other line sections, permission must be granted by the Infrastructure and Environment Department at the Finnish Transport Agency. The wagons must be transported as abnormal loads at the speed specified in the permit.

Kerava–Sköldvik  
Tampere–Seinäjoki  
Lielähti–Kokemäki  
Kokemäki–Harjavalta  
Kokemäki–Rauma  
Seinäjoki–Oulu  
Kokkola–Ykspihlaja  
Tuomioja–Raahe  
Raahe–Rautaruukki  
Riihimäki–Hakosilta  
Kouvola–Kotka  
Kotka Hovinsaari–Kotka Mussalo  
Juurikorpi–Hamina  
Luumäki–Joensuu  
Imatra tavara–Imatrankoski-raja  
Niirala-raja–Säkäniemi  
Joensuu–Uimaharju  
Kouvola–Pieksämäki  
Pieksämäki–Kontiomäki  
Pieksämäki–Joensuu  
Siilinjärvi–Viinijärvi  
Iisalmi–Ylivieska  
Oulu–Laurila  
Laurila–Tornio  
Tornio–Röyttä  
Oulu–Kontiomäki  
Kontiomäki–Vartius-raja

**Transport of wagons with an axle load over 225 kN in the eastern transit traffic on a line section belonging to superstructure category B.**

Individual wagons with axle loads exceeding 235 kN may temporarily be transported as abnormal loads on a line section belonging to superstructure category B1 at a speed of 35 km/h, and at 50 km/h on a line section belonging to superstructure category B2. A permit for this must be granted by the Rail Traffic Management Centre at the Finnish Transport Agency.

**Transport of wagons with axle loads over 225 kN in the eastern transit traffic on tracks and in turnouts with K30 and K33 rail profiles.**

It is prohibited to operate wagons with an axle load exceeding 225 kN in the eastern transit traffic on tracks and in turnouts with K30 and K33 rail profiles.

## Transport of wagons complying with the Russian standard (for eastern transit traffic)

If the train contains at least one goods wagon which complies with the Russian standard, the maximum speed on the sidings between the following traffic operating points or their parts is 20 km/h.

**Helsinki-Turku satama**  
Kauniainen

**Huopalahti-Havukoski**  
—

**Hyvinkää-Karjaa**  
—

**Karjaa-Hanko**  
Hanko

**Turku-Uusikaupunki**  
—

**Uusikaupunki-Hangonsaari**  
—

**Raisio-Naantali**  
—

**Helsinki-Riihimäki**  
—

**Kerava-Hakosilta**  
—

**Kerava-Sköldvik**  
—

**Kerava-Vuosaari**  
—

**Riihimäki-Tampere**  
—

**Toijala-Turku**  
—

**Toijala-Valkeakoski**  
—

**Tampere-Seinäjoki**  
Ylöjärvi

Parkano  
Ratikylä  
Peräseinäjoki  
Seinäjoki asema  
Seinäjoki tavara

**Lielähti-Kokemäki**  
—

**Kokemäki-Pori**  
Pori

**Pori-Mäntyluoto**  
Pori  
Mäntyluoto

**Mäntyluoto-Tahkoluoto**  
Mäntyluoto

**Kokemäki-Rauma**  
—

**Kiukainen-Säkylä**  
—

**Niinisalo-Parkano-Kihniö**  
Parkano

**Seinäjoki-Vaasa**  
Seinäjoki asema  
Seinäjoki tavara

**Seinäjoki-Kaskinen**  
Seinäjoki asema  
Seinäjoki tavara  
Kaskinen

**Seinäjoki–Oulu**

Seinäjoki asema  
Seinäjoki tavara  
Lapua  
Jepua  
Pännäinen  
Kälviä  
Kannus  
Eskola  
Sievi  
Ylivieska  
Oulainen  
Kilpua  
Vihanti  
Tuomioja  
Oulu tavara

**Pännäinen–Pietarsaari**

Pännäinen  
Pietarsaari

**Tuomioja–Raahe**

—

**Riihimäki–Kouvola**

—

**Kouvola–Kuusankoski**

Kuusankoski

**Lahti–Heinola**

Heinola

**Lahti–Loviisan satama**

—

**Kouvola–Kotka**

Kymi

**Kotka Hovinsaari–Kotka Mussalo**

—

**Juurikorpi–Hamina**

—

**Kouvola–Joensuu**

Joensuu Peltola  
Joensuu asema

**Luumäki–Vainikkala-raja**

—

**Imatra tavara–Imatrankoski-raja**

—

**Niirala-raja–Säkäniemi**

Tohmajärvi

**Joensuu–Ilomantsi**

Joensuu Peltola  
Joensuu asema

**Joensuu–Nurmes**

Joensuu Peltola  
Joensuu asema

**Nurmes–Kontiomäki**

Valtimo  
Vuokatti

**Kouvola–Pieksämäki**

Pieksämäki asema  
Pieksämäki Temu  
Pieksämäki lajittelu  
Pieksämäki tavara

**Mynttilä–Ristiina**

Ristiina

**Pieksämäki–Kontiomäki**

Pieksämäki asema  
Pieksämäki Temu  
Pieksämäki lajittelu  
Pieksämäki tavara  
Haapakoski  
Markkala  
Suonenjoki  
Salminen  
Kurkimäki  
Kuopio asema  
Kuopio tavara  
Murtomäki

**Pieksämäki–Joensuu**

Pieksämäki asema  
Pieksämäki Temu  
Pieksämäki lajittelu  
Pieksämäki tavara  
Varkaus  
Heinävesi  
Joensuu asema  
Joensuu Peltola

**Murtomäki–Talvivaara**

Murtomäki

**Varkaus–Kommila**

Varkaus

Kommila

**Huutokoski–Rantasalmi**

—

**Savonlinna–Parikkala**

Kerimäki

Punkaharju

**Siilinjärvi–Viinijärvi**

—

**Tampere–Jyväskylä**

—

**Orivesi–Seinäjoki**

Vilppula

Ähtäri

Alavus

**Vilppula–Mänttä**

Vilppula

**Haapamäki–Jyväskylä**

Keuruu

**Jyväskylä–Pieksämäki**

Pieksämäki asema

Pieksämäki Temu

Pieksämäki lajittelu

Pieksämäki tavara

**Jyväskylä–Äänekoski**

—

**Äänekoski–Haapajärvi**

Haapajärvi

**Iisalmi–Ylivieska**

Pyhäsalmi

Haapajärvi

**Pyhäkumpu erkanemisvaihe–****Pyhäkumpu**

—

**Oulu–Laurila**

Oulu tavara

**Laurila–Tornio-raja**

—

**Tornio–Kolari**

Pello

**Laurila–Kemijärvi**

Rovaniemi

Kemijärvi

**Kemijärvi–Patokangas**

Kemijärvi

**Oulu–Kontiomäki**

Paltamo

Oulu tavara

**Kontiomäki–Ämmänsaari**

Hyrnsalmi

Pesiökylä

Ämmänsaari

**Kontiomäki–Vartius-raja**

—

# Monitoring of Rolling Stock

## Rolling stock monitoring equipment

The location of the equipment for monitoring rolling stock in the railway network is illustrated in figure 1.




Figure 1. Rolling stock monitoring equipment.

### Matters concerning wheel flats

Each passing train must be monitored to detect wheel defects, overheated bearings or brakes, an uneven or unstable load, or something else potentially alarming. The monitoring should be carried out on both sides of the train, whenever there is sufficient staff. If a defect or deficiency is detected, it should be addressed immediately or the unit detached from the train. The unit with defective wheels should, if possible, be transported in the same train to the nearest depot, unless this causes apparent danger or damage, and the maintainer of the vehicle unit should be notified.

The wheel condition can be monitored both manually and with automatic measuring devices. In the monitoring process the following measures should be taken:

- I. If harmful wheel flats are detected, the length of the notch should be measured at the next stop. Further transport of a unit with a wheel flat is permitted on the following conditions:
  - a) If the length of the notch is less than 45 mm, no direct action is required
  - b) If the length of the notch is 46–60 mm and the outdoor temperature is below  $-10^{\circ}\text{C}$ , the maximum speed allowed is 10 km/h. No speed limit when the temperature  $\geq -10^{\circ}\text{C}$ ; the speed range 20–45 km/h should however be avoided. The wheelset must be replaced at the next depot.
  - c) If the length of the notch is 61–80 mm, the maximum speed allowed is 10 km/h. The wheelset must be replaced at the next depot.
  - d) If the length of the notch or the combined notches is more than 80 mm, the wheelset must be replaced at the station where the notch is measured.
  - e) If an overweight wagon has an over 45 mm long notch, the load should be lightened at the nearest station or the wagon should be transported at a maximum speed of 10 km/h to the nearest depot.
- II. The  $Q_{\text{imp}}$  limit values of the dynamic percussion force of the wheels on the rail have been specified in the table below. This force is usually caused by defects in the running surface of the wheel, such as notches, roughness or ovalisation. The dynamic force  $f_{\text{dyn}}$  indicates the ratio of wheel force variation for an unloaded wagon.

These forces are measured by wheel-flat detectors. The locations of these detectors are illustrated in figure 1.



Type of message	Level	Limit	Measures
<b>Dynamic force</b> $Q_{imp}$	Q5	> 500 kN	Must be detached from the train; max. speed 50 until detached
	Q4	> 450 kN	Max. speed 50 right after the message. The wheelset must be repaired before the next loading.
	Q3	> 350 kN	No speed limit; must be repaired before the next loading. If the same unit causes at least a Q3 alarm after the following loading, the measures required for Q4 must be taken
	Q2	> 300 kN	Must be repaired at the next depot, at the latest.
	Q1	> 250 kN	The maintainer can schedule the repair.
<b>Dynamic coefficient</b> $f_{dyn}$	f3	> 800 %	Must be repaired before the next loading. If the same unit causes at least an f3 alarm after the following loading, the measures required for Q4 must be taken
	f2	> 600 %	Must be repaired at the next depot, at the latest
	f1	> 400 %	The maintainer can schedule the repair.







Finnish Transport Agency

ISSN-L 1798-8276

ISSN 1798-8284

ISBN 978-952-317-165-7

[www.liikennevirasto.fi](http://www.liikennevirasto.fi)

---